

March 02, 2018 (Via Delivery & Email) J16.084

Carla Nixon, Town Planner Town of Cumberland 290 Tuttle Road Cumberland, Maine 04021

OceanView at Cumberland, Tuttle Road, Cumberland Revised Preliminary Subdivision Plan Submittal –*ADDENDA-1A* (Map R04 Parcels 4B, 4D, 4E and 5)

Dear Carla:

On behalf of OceanView at Cumberland LLC, we are pleased to present for staff and Planning Board review, *revised Preliminary Subdivision Plans dated March 02, 2018* for the development of Phase 1 of the "OceanView at Cumberland" active senior community located at 277 Tuttle Road across from the Town Hall and Town Forest property. The project was reviewed with the Planning Board at the February 20th Planning Board meeting and a public hearing held.

This submission shall serve as an *Addenda-1A* to the previous submittal of January 30, 2018 and provides responses to the following comments received:

- February 08, 2018 Email comments from Carla Nixon, Planner
- February 12, 2018 Review letter from Sevee & Maher Engineers
- February 20, 2018 Stormwater Review letter from Sevee & Maher Engineers
- February 20, 2018 Planning Board meeting comments
- Trail revisions from comments provided through the Lands and Conservation Commission -Trails Subcommittee and Cumberland-North Yarmouth Moonlite Snow Skimmers snowmobile club

Enclosed are 6 hard copies and an electronic PDF copy of the following materials:

Cover letter -Addenda-1 Revised Submission and Response to Comments

Responses to Sevee & Maher Subdivision/Site Plan Comments dated February 12, 2018.

Responses to Sevee & Maher Stormwater Comments dated February 20, 2018.

Exhibit 1 – Signage

Exhibit 2 - Additional Lighting Cuts – Driveways and Building Lights

Exhibit 3 – Updated Traffic Memo, Maine Traffic Resources, Dated 02-20-18

Exhibit 4 - Cottage Model A and B Elevations and color scheme photos

1. Responses to February 08 email, Carla Nixon, Planner:

Responses to the Planner's comments have been provided previously via email on February 14th. The following serves to provide additional clarification of several of the Planner's comments identified by the corresponding comment number of the February 8th email.



Items 1-4 – Right, Title and Interest: Purchase and Sale information and clarification have been provided to comments 1-4 previously, substantiating legal right, title and interest in the Doane and Allen properties.

Items 5/6 – Vernal Pool and Wetland reports – have been provided to the Planning Department.

Item 7 – Sign Locations are suggested at the entrance of Little Acres Drive (modest project identification sign) and Way finding Signage located further into the site near Station 15+50 in the open space prior to Cottage 52. *Exhibit 1* provides a photo and shop drawing of a "typical" sign design from the OceanView Falmouth campus as a sign template. We would anticipate providing final signage details at final plan submittal

Item 8 – Road names have been submitted for Town E911 review and have been added to the plans.

Item 9 – The Planning Board determined that a Market Study is not required.

Item 10 –Contour Line Waiver - This waiver is not required as the plans exceed the requirements for providing 2 foot contours by providing both 1 and 2 foot contour intervals on various plan sheets.

Item 11 – The reference to the SLODA "amendment" has been deleted and reference to the additional NRPA and MDOT Entrance Permit permits also added to the cover sheet.

Item 12 – DEP Applications have been submitted and copies delivered to the Town Hall.

Item 13- The 100-foot Stream Buffer has been added to the plans.

Item 14 – Standard Conditions of Approval and Sheet S4 Note 10: The applicant understands that any required Town standard conditions of approval and plan notes can be added at the final plan submittal. Note 10 on Plan Sheet S4 has had the specific language added regarding the 90-day period from approval as per Chapter 250-6.D.(2).

Item 15 –Photometric Plan –Has been added to the plan set. Refer to *Exhibit 2* for driveway and garage building lighting cuts. The Standard street light fixture (Beacon Model, LED) was submitted with the prior application.

Item 16 – All roads are to be private. Refer to item 8 for road name requests.

Item 17 – Driveways/parking - Each unit will provide either a one or two car garage and parking for a minimum of 1 car in the driveway satisfying the requirement for 2 spaces per unit. Note 8 on Plan S4 has been modified to further reflect this requirement.

Item 18 – HC Parking – 1 ADA space has been shown at the Community Center.

Items 19/20 - The speed table and grass emergency access details have been removed from the plans.

Item 21 – Foundation drains to connect to the stormdrain system where possible with backflow devices or to natural drainage ways where grading allows.



- Item 22 CTV reference has been revised to Spectrum Communications.
- Item 23 Boulder walls are shown at the culvert crossings and several site locations on the plans.

Item 24 – Building Elevations and Colors – Exhibit 4 provides reduced copies of elevations for the cottage models A and B. We have included photos from the OceanView Falmouth campus reflecting the typical natural color tones. The applicant reserves the right to modify color selections base on final marketing and will provide at the time of building permits.

Items 25/26 – All trails and open space will be available to the public. The applicant has indicated that the Community Center may be used for meetings or events via scheduling through OceanView at Cumberland management. The Community Center will be constructed in Phase 6 of the project. (Refer to Plan C1 for phasing.)

2. Responses to Sevee and Maher February 12th Subdivision/Site Plan Review letter and February 20th Stormwater letter.

Copies of the Sevee & Maher letters with responses provided are attached.

3. Planning Board and Additional Comments:

- a. Trails The applicant's team was directed by the Planning Board to work with stakeholders to finalize the re-routed snowmobile trail location and form of legal rights or license to be granted by OceanView at Cumberland, LLC for use of the property. The project team met with members of the Lands and Conservation Trails Subcommittee, Town Manager and Shawn Mcbrearity of the Moonlite Snow Skimmers Snowmobile Club again on February 27th to work out the trail logistics. The applicant has agreed to make a minor modification in the proposed "southern boundary" snowmobile/multipurpose trail where it connects and crosses the main wetland and stream corridor. That revision is shown on the revised Plan C12. Additionally Plan C12 has corrected the trail label for the proposed re-routed snowmobile trail and updated the plan graphically. The following actions were also agreed to:
 - i. The applicant will work with the Town Manager on an easement and license agreement for the use of the proposed trail along the southern project property line.
 - ii. The applicant has agreed, as noted earlier and in the public hearing, to participate in the construction and financing of the relocated snowmobile/multipurpose trail.
 - iii. Staff suggested that an amendment of the Crossing Brook Open Space deed and subdivision approval may be required. The Town Manager has indicated that the extension of the trail onto the Town Open Space property is consistent with the permitted use of the property deed and that a subdivision amendment is not required.
- b. Traffic Memo Update An updated memo dated February 20, 2018 is attached as Exhibit3 updating the traffic trip generation from 50 to 52 units. No changes in the total peak hour morning or evening trips results from this update.



In summary – we believe all Staff, Planning Board and Peer Review comments have been addressed and that the project should be considered for completeness and Preliminary Plan approval at the March Planning Board meeting. However should you find any items to be missing or require additional information please do not hesitate to contact me and we will respond quickly.

We look forward to meeting again with the Planning Board at the March 20thPlanning Board meeting and would respectfully request that the project be considered for Preliminary Subdivision Approval.

Sincerely,

Frederic (Rick) Licht, PE, LSE

Principal

Encl: As Noted

Cc: Matt Teare; OceanView at Cumberland LLC

Chris Wasileski: OceanView at Cumberland LLC Christian Haynes; OceanView at Cumberland LLC David Haynes; SeaCoast Management Company

Chris Belanger; Belanger Engineering Rex Croteau; Titcomb Associates

Mark Hampton; Mark Hampton Associates, Inc.

RESPONSES TO FEB. 12TH SEVEE & MAHER REVIEW MEMO PROVIDED BELOW IN RED. REFER TO REVISED PRELIMINARY PLANS DATED 03-02-18.

03-02-18

LED & BELANGER ENGINEERING RESPONSES

February 12, 2018

Ms. Carla Nixon, Town Planner Town of Cumberland 290 Tuttle Road Cumberland, Maine 04021

Subject: Peer Review of OceanView At Cumberland

Major Subdivision and Site Plan Application – Preliminary Review

Tuttle Road, Cumberland, Maine

Dear Ms. Nixon:

As requested, Sevee & Maher Engineers, Inc. (SME) has conducted a peer review of the preliminary application for a Major Subdivision and Site Plan for the proposed OceanView at Cumberland senior living community located off Tuttle Road. The application materials received by SME were prepared by LICHT Environmental Design, LLC (LICHT), and consist of the following:

- Cover letter by Frederic Licht, P.E., L.S.E, outlining the project and waiver requests, dated January 30, 2018;
- Application package prepared by LICHT, dated January 30, 2018;
- Project plan set dated January 31, 2018;
- Comment Response Letter from Frederic Licht, P.E., L.S.E, dated January 30, 2018; and
- Planner's Comments from Carla Nixon dated February 8, 2018.

Note: A Stormwater Management Report was not included in the application package transmitted to SME for review as of February 11, 2018.

PROJECT DESCRIPTION

The Applicant proposes to develop a 52-unit senior living facility on a combined 36.83-acre parcel currently owned by Richard Doane and Laurence Allen. The parcel is located off Tuttle Road in Cumberland, across the street from the Town of Cumberland (Town) Municipal Office. The development will be accessed by a proposed private roadway constructed in accordance with Town residential sub-collector roadway standards as outlined in Article VI and Table 2 of Chapter 250, Subdivision of Land, of the Cumberland Code. The subdivision will be served with public utilities, including water, sewer, natural gas, electric, telephone, and cable.

This project is being reviewed as a Major Subdivision as outlined in Chapter 250 - Subdivision of Land of the Town of Cumberland Ordinances, most recently amended and adopted on January 12, 2011, and Chapter 229 - Site Plan Review, most recently amended and adopted on March 26, 2012. The comments below relate to the appropriate Ordinance Sections.

Chapter 250: Subdivision of Land

SME has reviewed the applicable sections of Chapter 250 and has provided comments for those sections not found to be addressed by the Application. The remaining sections have been reviewed and found to comply with Chapter 250 requirements.

Section 250-1(C) – Municipal water supply

 SME understands that the applicant has contacted the Portland Water District regarding their capacity to serve the project. Please provide a verification letter from the District prior to final approval. Applicant to provide with final plan application.

Section 250-1(E) – Traffic

2. The Updated Traffic Impact Study included with this application prepared by Maine Traffic Resources and dated December 11, 2017 is based on a maximum of 50 residential units. SME recommends the study be updated to reflect the current planned development of 52 residential units. An updated 52 unit traffic memo has been prepared by Maine Traffic Resources, dated February, 20, 2018 and submitted to Staff, showing no change in trip generation from 50-52 units. A copy is attached for review.

Section 250-1(N) – Stormwater

3. The application SME reviewed did not include a Stormwater Management Exhibit. Please provide a stormwater report and stormwater management plan prior to preliminary approval. A final Stormwater Management report has been provided and reviewed. Refer to SME comment letter dated February 20, 2018. Additional updates to the stormwater report are provided with the revised Preliminary plans dated 03-02-18 addressing comments.

Section 250-1(O) – Freshwater Wetlands

The cover letter outlines 11,200 sf +/- of proposed wetland impacts. Plan sheet C2 outlined 12,700 sf of proposed wetland impacts. Please clarify. The revised submission has been updated to reflect 12,700 sf of wetland impacts, consistent with the DEP-NRPA Tier-1 application.

Section 250-1(P) – River, stream or brook

5. There are two stream crossings associated with the proposed development. Please submit additional detail regarding the proposed construction, including any State or Federal Permit approvals, for review prior to final approval. The applicant will provide any final culvert crossing details with the final plans commensurate with approvals from the DEP and Corps of Engineers final reviews.

Section 250-19 – Review and approval by other agencies

- 6. SME understands the following permit applications are underway for the project and applications will be filed with appropriate agencies following submittal of the preliminary subdivision and site plan application:
 - Maine Department of Environmental Protection (MEDEP) Site Location of Development Act (SLODA) permit,
 - MEDEP Natural Resources Protection Act (NRPA) Tier 1 permit for proposed wetland impacts,
 - United States Army Corps of Engineers (USACOE) permit for proposed stream crossings and culvert replacements,
 - Cumberland County Soil and Water Conservation District (CCS&WCD) stormwater and erosion control review, and (SSCWCD review not required per review by SME.)
 - Maine Department of Transportation (ME DOT) Driveway/Entrance Permit.

Where review and approval of any subdivision or site plan by any other governmental agency is required, approvals shall be submitted to the Planning Board in writing prior to the submission of the final plan. *Applicant shall submit copies of permits with or prior to the final plan application.*

Section 250-22 – Retention of proposed public sites and open spaces

7. The application package outlines portions of the development, including pedestrian trails and walkways, will be available for public use. SME recommends that areas designated for recreation and/or reserved as public open space be outlined in the project plan set. OceanView at Cumberland will operate under a returnable entrance fee model, used throughout the senior living industry, where the land and property is owned and maintained by OceanView at Cumberland, LLC. There are no separate open space "parcels" as with a condominium form of ownership. The applicant has reviewed this with SME engineers. The applicant is also working closely with the Town of Cumberland and local snowmobile club to create trails which would be open to the public at large as well as the senior residents.

Section 250-27 – Utilities

- 8. Design details for utility pipes and conduits are not included in the project plan set. SME recommends sizes of all utilities pipes and additional design information be provided with the final plan application. Final pipe and structure tables have been added to Plan Sheet C13A. Utilities have been added to the proflie views on Plan Sheets C6-C10.
- 9. SME recommends Water Detail sheets be signed and stamped by a registered Professional Engineer prior to final approval. Portland Water District standard details have been incorporated into the standard title block sheets and stamped.
- 10. SME understands Summit Natural Gas has been contacted to provide natural gas for the development. SME recommends a capacity to serve letter be provided with the final plan application. The applicant will provide a serviceability letter from Summit NG with the final plan application. The applicant continues to work with Summit NG to coordinate the natural gas distribution system and service agreements.
- 11. SME understands Central Maine Power (CMP) has been contacted to provide electricity for the development. SME recommends the location of underground electric lines, transformers, and electrical easements be added to the plan. Please provide a capacity to serve letter with the final plan application. The applicant is working with CMP, Fairpoint Communications and Spectrum Communications on electric and utility services and will provide a serviceability letter from CMP along with a final "CMP 905 Plan-showing transformer locations" with the final plan submittal. Utility easements are shown on the Subdivision Plans Sheets S1-S3.

Section 250-28 – Water Supply

12. SME understands that the applicant has contacted the Portland Water District regarding their capacity to serve the project. Please provide a verification letter from the District prior to final approval. The applicant will provide a final letter from PWD with the final plan approval.

Section 250-29 – Sewage disposal

13. The application includes a capacity to serve letter from the Town of Falmouth regarding their ability to accommodate the anticipated sewage flow from the development. In addition, SME recommends the applicant provide a letter from the Town of Cumberland and the Portland Water District to ensure capacity of the local system to accommodate additional loading. The applicant has requested a serviceability letter from Bill Shane, Town Manager and from the Portland Water District. The letters of serviceability will be provided to the Planning Staff when received.

Section 250-32 – Design and construction standards

14. SME understands proposed streets will be constructed in accordance with Town residential sub-collector roadway standards as outlined in Article VI and Table 2 of Chapter 250, Subdivision of Land, of the Cumberland Code. Plans for Arctic Fox Drive do not include a sidewalk, which is listed in the Ordinance as a required improvement unless waived by the Board. SME recommends the applicant add a sidewalk to the final plans or request a waiver to address this item. The applicant's engineers have review the sidewalk requirements with SME engineers and per the SHC Overlay Ordinance Section 315-28.4 .I Road Standards Table a sidewalk is not required for Arctic Fox Drive.

Section 250-36 through 250-43 – Storm Drainage Design and Construction Standards

15. SME has not received an updated Stormwater Management Report for the revised plan set. As outlined previously in Comment 3, a stormwater report and stormwater management plan for the proposed development should be provided prior to preliminary approval. (Refer to Comment #3 response.)

Section 250-44 – Fire Protection

16. SME understands the public water service will be used to sprinkle individual units in the proposed development. SME recommends the applicant provide documentation to support the Water District's capacity to meet the fire protection needs of the development prior to final approval. The applicant has been working with the Portland Water District MEANS Department who are familiar with the sprinkler systems for years with the OceanView Falmouth cottage development providing sprinkler designs to each cottage unit and will provide a serviceability letter from the Portland Water District for final approval.

Section 250-49 – Waivers and modifications

17. The applicant has requested a waiver from the requirement to show street signs for preliminary approval only. SME recommends approval of the requested waiver and that signs be included on the final plan application. At the February

- 20th meeting, the Planning Board deferred the waiver request to a final condition of approval for the Preliminary Plans.
- 18. The applicant has requested a waiver from the requirement to provide capacity to serve letters from selected utility providers for preliminary approval only. SME recommends approval of the requested waiver and that capacity to serve letters be provided with the final plan application. At the February 20th meeting, the Planning Board deferred the waiver request to a final condition of approval for the Preliminary Plans.
- 19. The applicant has requested a waiver from the requirement to locate 10-inch diameter or more trees on the property. SME recommends approval of this waiver. This waiver was granted at the February 20th Planning Board meeting. The waiver will be documented on the Final Subdivision Plat as required by statute.

Chapter 229: Site Plan Review

SME has reviewed the applicable sections of Chapter 229 and has provided comments for those sections not found to be addressed by the Application. The remaining sections have been reviewed and found to comply with Chapter 229 requirements.

Section 229-10(H) - Exterior lighting

20. SME understands the Applicant is evaluating site lighting options for the project. SME recommends that a final lighting layout and photometrics plan be provided with the final plan application. A photometric plan and nine (9) light fixture locations have been added to the Subdivision Plans.

General Comments

- 21. Site Plan Application Please update the project description to reflect the correct number of units in the proposed development. The application has been updated to 52 units and provided to the Town Planner.
- 22. Application Exhibit 6 Soils. The Soil Narrative Reports included in the exhibit should be signed and dated by Mark Hampton prior to final approval. Stamped soils reports have been provided to staff and SME.
- 23. Application Exhibit 10 Traffic Impact Assessment. As previously outlined in Comment 2, SME recommends the Traffic Impact Study be updated to reflect the current planned development of 52 residential units. The Traffic Impact Assessment has been updated. Refer to Feb 20th memo from Diane Morabito, Maine Traffic Resources.
- 24. Plan Sheet C0 Approvals Required Note 2 references a MEDEP SLODA permit *amendment*. Please update the plan to clarify the current project permitting status. Cover sheet has been updated and NRPA and MDOT permits added.
- 25. Subdivision Plat S1 The plan outlines overhead electric service from Tuttle Road to Units 51, 52 and 53. The application outlines underground utilities. Please clarify. The overhead line are existing (to the Allen Residence) and have been removed from the subdivision plat.
- 26. Subdivision Plat S1-3 Please add supplementary information to the drawings prior to final approval, including sight distances, stream setbacks, stormwater and grading easements, road layout information (alignment and intersection radii), and wetland impact areas, etc. Sight distances, MDIFW 100 ft. Stream Buffers (recommended), and wetland impact areas are noted on the revised Plans S1 S4. There are no need for stormwater easements as the stormwater system and roads are maintained by OceanView at Cumberland, LLC and do not cross onto adjacent properties. The road geometry has been added as a Table to the Engineering plans (Sheet 13A),

- 27. Topographic Site Plan by Titcomb Associates (Sheet 1 of 1) is not included in the plan set. Please add an existing conditions plan to the drawing set. The Existing Conditions plan has been included in the revised plan set.
- 28. Overall Plan Sheet C1 references a 50-foot buffer and golf cart trails not shown on the drawing. Plan C1 has been revised and is intended as an overall phasing and development plan. Refer to other plans in the drawing set for additional site information.
- 29. Site Development Plan Sheets C3 through C5 Please include additional labeling and detail for utilities, easements, stormwater management, and natural features such as streams and wetlands. Please update clearing limits should be updated to reflect modifications to stormwater treatment systems. Please add grading easements to reflect work scheduled outside the property boundary and access easement limits. SME recommends this information be added to the plan to verify compliance with applicable Town standards. We believe the revised plans have added additional detail and labeling of site information.
- 30. Plan and Profile Plan Sheets C6 through C10 do not outline utility information for force main, electric or communications wiring. SME recommends this information be added to the plan. Utility information has been added to the Plan and Profile Sheets C6-C10.
- 31. Roadway design does not conform to minimum K factors for sag vertical curves at Little Acres Drive STA 21+50; Arctic Fox Drive STA 41+99.64 and STA 44+99.90; and Arctic Fox Spur STA 21+61.63. SME recommends the applicant review these areas and adjust to meet Town construction standards. The applicant's engineers have met and reviewed the K factors and revised the plans. The SHC Overlay Ordinance Section 315-28.4. I allows a min, K factor of 15 for crest and 20 for sag vertical curves. The profiles have been modified to meet these requirements.
- 32. Improvements were noted at several locations in the no-cut buffer along the property boundaries for site grading. SME recommends the applicant amend the plans to minimize disturbance in the 50 foot no-cut buffer. The several minor encroachments on the 50 foot SHC buffer have been adjusted on the plans.
- 33. Roadway Sections and Details Sheet C13 –There are several references to Brunswick, Topsham, and SAD 75 in the notes on this plan sheet. SME recommends the notes be updated to reflect the current project. Sheet C13 details references have been revised.
- 34. Civil details C15 The Town of Cumberland does not usually include ladder rungs in catch basin structures. SME recommends the applicant amend the plans to reflect Town construction standards. The catch basin detail has been revised.

- 35. Erosion Control Notes C16 SME Recommends Note 1 be updated to reflect the current Maine Erosion and Sediment Control Best Management Practices edition (October 2016). Sheet C16 reference has been updated to reflect the 2016 Manual.
- 36. Erosion Control Notes C16 SME recommends the applicant update the Construction Plan Notes to reflect the current project. *The construction notes on Plan C16 have been updated.*
- 37. Misc. Details C19 SME recommends the applicant update the Trench Repair Detail to reflect current Town pavement sections. *Plan C19 trench detail has been updated.*
- 38. Arch 1 Culvert Details Profile does not include a sidewalk. SME recommends the applicant update the plan to reflect proposed construction. The culvert details and sizing have been revised (100 year storm design). It should be noted that final construction details will be provided for final plan submittal pending agency reviews.
- 39. Arch 2 Culvert Details C21 Profile does not include a sidewalk. SME recommends the applicant update the plan to reflect proposed construction. The culvert details and sizing have been revised (100 year storm design). It should be noted that final construction details will be provided for final plan submittal pending agency reviews.

40.

Please call me with any questions, or if you would like, I could meet with you to discuss our comments.

Sincerely,

SEVEE & MAHER ENGINEERS, INC.

Jeffrey T. Read, P.E. Project Engineer

03-02-18 RESPONSES TO COMMENTS BY LED AND BELANGER ENGINEERING IN RED. REFER ALSO TO REVISIONS TO STORMWATER MANAGEMENT REPORT AND REVISED SUBDIVISION PLANS DATED 03-01-18.

February 20, 2018

Ms. Carla Nixon, Town Planner Town of Cumberland 290 Tuttle Road Cumberland, Maine 04021

Subject: Peer Review of OceanView At Cumberland

Preliminary Stormwater Review for Major Subdivision and Site Plan Application

Tuttle Road, Cumberland, Maine

Dear Ms. Nixon:

As requested, Sevee & Maher Engineers, Inc. (SME) has conducted a peer review of the stormwater submission supporting the preliminary application for a Major Subdivision and Site Plan for the proposed OceanView at Cumberland senior living community located off Tuttle Road. The materials received by SME on February 13, 2018 were prepared by Belanger Engineering (BELANGER), and consist of the following:

- A stormwater management report prepared by Belanger Engineering dated February 7, 2018; and
- An updated project plan set dated February 7, 2018.

PROJECT DESCRIPTION

The Applicant proposes to develop a 52-unit senior living facility on a combined 36.83-acre parcel currently owned by Richard Doane and Laurence Allen. The parcel is located off Tuttle Road in Cumberland, across the street from the Town of Cumberland (Town) Municipal Office. The development will be accessed by a proposed private roadway constructed in accordance with Town residential sub-collector roadway standards as outlined in Article VI and Table 2 of Chapter 250, Subdivision of Land, of the Cumberland Code. The subdivision will be served with public utilities, including water, sewer, natural gas, electric, telephone, and cable. This project is located within the designated NPDES Phase II Stormwater Program MS4 Area for Cumberland as outlined in the Draft Stormwater Management Plan, revised in April 2014.

This project is being reviewed as a Major Subdivision as outlined in Chapter 250 - Subdivision of Land of the Town of Cumberland Ordinances, most recently amended and adopted on January 12, 2011, and Chapter 229 - Site Plan Review, most recently amended and adopted on March 26, 2012. The comments below relate to the appropriate Ordinance Sections.

Chapter 242: Stormwater Management

SME has reviewed the applicable sections of Chapter 242 and has provided comments for those sections not found to be addressed by the Application. The remaining sections have been reviewed and found to comply with Chapter 242 requirements.

Section 242-24(C)

1. SME understands the applicant intends to retain ownership of the stormwater management facilities shown in its post-construction stormwater management plan. Prior to final approval, SME recommends the applicant submit documentation that the applicant, its successors, heirs and assigns shall have the legal obligation and the resources available to operate, repair, maintain and replace the stormwater management facilities, as well as a maintenance agreement with the Town in conformance with this section of the Ordinance. The applicant, OceaView at Cumberland, LLC will own and maintain the stormwater system as with their other facilities. The stormwater management report contains a maintenance and inspection log. The applicant suggests that any final maintenance agreement with the Town be submitted for final plan review.

Section 242-1(D)

2. Stormwater management facilities not located in a public right-of-way and not offered to the Town for acceptance as public facilities may require access easements to the Town. SME recommends the Applicant clarify this item with the Town and add required easements, if necessary, prior to final approval. The stormwater management system will be private and not require easements. The applicant shall review any need for any third party easements with the Town should the Town require access in case of non performance of maintenance.

General Comments

3. Stormwater Management Report, Page 1, Surface Water on or Abutting the Site – SME recommends the Applicant coordinate with the Town Engineer regarding runoff from the site and proposed improvements scheduled for Tuttle Road in the Summer of 2018. Agreed. The applicant's engineers will consult with the Town Engineer. No increase in the peak flooding rate is proposed from development of the project.

- Stormwater Management Report, Page 2, Proposed Conditions SME recommends the section be updated to reflect the 52 residential units. Section has been updated.
- 5. Stormwater Management Report, Page 3, Impervious Area Summary The table references road sections not outlined in the plan detail sheets. SME recommends the Applicant update the plan set to include all applicable road section details. The impervious tables have been updated and reflect the proposed Allen lot acquisition.
- 6. Stormwater Management Report, Page 4, Focal Point Proprietary System This section references 500 feet of gutter line flow. Section 250-40, B(4) outlines 300 feet as the maximum length for stormwater in a street gutter prior to intake at a catch basin. SME recommends the Applicant adjust the length of flow or request a waiver prior to final approval. The engineers are reviewing the gutter flow requirements with Focal Point/ACF Environmental and will provide updated calculations.
- 7. Stormwater Management Report, Page 4, Forested Buffer Please verify that wetland buffers outlined on the plan qualify as stormwater treatment based on length, grade and soil type. If approved for treatment by MEDEP, SME recommends adding required sign details and boundary information to the plan set. Agreed. Upon approval from DEP, we will add a note to the final plans to include field markers for all DEP Buffers. Buffers will be recorded in the CCRD as a deed restriction on the property.
- 8. Stormwater Management Report, Page 5, Arctic Fox Wet Pond Design Criteria Please verify above pool and below pool treatment volume calculations.

 Calculations to be submitted verifying the PPV.
- 9. Stormwater Management Report, Page 5, Groundwater Impacts Please show boring/test pit locations on the plan set. *Test pits performed by Mark Hampton, CSS are being added to the SW Plans.*
- 10. Stormwater Management Report, Page 6, Mallard Way Wet Pond Design Criteria – Please verify above pool and below pool treatment volume and provided storage calculations. Calculations to be submitted verifying the PPV.
- Stormwater Management Report, Page 6, Groundwater Impacts Please show boring/test pit locations on the plan set. Test pits performed by Mark Hampton, CSS are being added to the SW Plans.
- 12. Stormwater Management Report, Page 7, Post Area Summary and General Standard Calculation Please verify total area calculations. The sum of component areas does not appear to match the total area. *The table has been updated and revised.*
- 13. Stormwater Management Report, Page 7, Flooding Standard Please verify the top of the watershed area. A significant contributing drainage area exists above the middle school entrance. The drainage area has been reviewed and adjusted. The applicant's engineer suggests that SME confirm their

- understanding of the extent of the watershed so that the applicant's watershed areas are consistent.
- 14. Stormwater Management Report, Page 7, Flooding Standard SME understands the site access was relocated from the former railroad bed to the Allen property. Please update the site entrance description. The report has been updated reflecting the new "Allen" lot access point.
- 15. Property Maintenance Part 3, page 17 Please update references to Loon Lane. *Report has been updated.*
- 16. Permitting Authorization Letter Please update authorizations to include OceanView at Cumberland. Letter has been updated to include OceanView at Cumberland, LLC.
- 17. Exhibit 3 Please update site footprint to reflect inclusion of the Allen Property. *Exhibit has been revised.*
- 18. Pre Development Drainage Plan SME recommends the plan be updated to include the full drainage area and subcatchment boundaries, soil boundaries, and topography outside the project area. Labels for 18R and 55R are missing from the plan sheet. *The Pre Development Plans have been updated*.
- 19. Post Development Drainage Plan SME recommends the plan be updated to include the full drainage area and subcatchment boundaries, soil boundaries, and topography outside the project area. Labels for 15S, 51S, and 51P are missing from the plan sheet. *The Post Development Plans have been updated*.

Please call me with any questions, or if you would like, I could meet with you to discuss our comments.
Sincerely,

Jeffrey T. Read, P.E. Project Engineer

SEVEE & MAHER ENGINEERS, INC.

REFERENCE: OCEANVIEW AT FALMOUTH SIGNAGE SAMPLE



TYPICAL SIGNAGE STYLE (OCEANVIEW AT FALMOUTH)





PREPARED FOR:

OCEANVIEW AT CUMBERLAND SENIOR COMMUNITY ■ <u>TITLE:</u>

TYPICAL SIGNAGE

SCALE: FILL IN DATE: 03-02-18

JOB NO: 16.084

EX. 1

• REFERENCE : STREET SIGN SAMPLE

6"x36" Reflective letters (2) 1 sided signs








PREPARED FOR:

• <u>TITLE:</u>
TYPICAL SIGNAGE

OCEANVIEW AT CUMBERLAND SENIOR COMMUNITY

SCALE: FILL INDATE: 03-02-18


■ <u>JOB NO:</u> 16.084 EX. 1.1





1 sided, metal posts, red cedar,

carved, 23kt. gold leaf

66"x35"







Cottage Building & Post lights Norwell **Cottage Onion Product Name**

Model Number

1323 1324 1321

15.75


Project Name

OceanView at Cumberland

Fixture Type

Quantity






Cottage Onion Small - 1323 Bronze (BR) Clear Glass (CL)

Lighting







10.625"

Black (BL) Clear Glass (CL) Finish Options Glass

Product Name / Model / Dimensions					
Cottage	Onion Sm	nall - 1323	3		
Cottage	Onion Me	dium - 13	324		
Cottage	Onion Po	st - 1321			
	Height	Width	Pro		

	Height	Width	Projection	TTO
1323	13.75"	8.25"	10.125"	9.5"
1324	15.75"	10.625"	12.5"	10"
1321	14.625"	10.625"		
Backplate Sconce 6.25" Diameter				

Standard	Standard
Black (BL)	Clear (CL) Seedy (SE)
Bronze (BR)	Seedy (SE)

Standard
Incandescent
(1) 100 Watt Edison

Lamping Options

1 _ 2018

INC-



SUMMARY MEMORANDUM

TO: Mr. Rick Licht, P.E.
Licht Environmental Design, LLC.
35 Fran Circle
Gray, ME 04039

RE: Revised Trip Generation Analysis for OceanView at Cumberland

The purpose of this memorandum is to summarize revised trip generation analysis for the proposed OceanView at Cumberland residential development on Tuttle Road in Cumberland, Maine. Maine Traffic Resources previously prepared "Updated Traffic Impact Study, Proposed Senior Residential Development, Cumberland, Maine", dated December 11, 2017. That study was performed for 50 senior residential dwelling units.

It is understood that the OceanView at Cumberland has been revised to include 52 dwelling units since some adjacent land is being acquired. In addition, there will be a small community center. The Town's Peer Reviewer, Sevee and Maher Engineers, have requested that the trip generation analysis be updated to reflect the currently proposed development level.

Trip Generation Analysis

Trip generation for the previously studied 50 units and currently proposed 52 dwelling units was estimated using the Institute of Transportation Engineers (ITE) "Trip Generation, 9th Edition" report. Land use codes (LUC) 251 – Senior Adult Housing – Detached and 252 – Senior Adult Housing – Attached were used on the basis of 50 and 52 dwelling units. Both of these land use codes include amenities such as the proposed community center. Hence, the community center trips are expected to be reflected in the following trip generation analysis. To be conservative, the higher of the two rates was used for each time period. The results are summarized below:

ITE Trip Generation	(One-Way Trip-Ends)
---------------------	---------------------

Time Period	50 Units	52 Units	Increase
Weekday	184	192	8
AM Peak Hour – Adjacent Street	11	11	0
Entering	4	4	0
Exiting	7	7	0

Time Period	50 Units	52 Units	<u>Increase</u>
AM Peak Hour – Generator	20	20	0
Entering	9	9	0
Exiting	11	11	0
PM Peak Hour – Adjacent Street	14	14	0
Entering	9	9	0
Exiting	5	5	0
PM Peak Hour – Generator	18	18	0
Entering	10	10	0
Exiting	8	8	0

As can be seen in the above table, the increase from 50 units to 52 units is not expected to increase trips during any peak hour over those already studied. On a daily basis, the trips will increase by four (4) round-trips per day due to the two (2) additional dwelling units. With no change in peak hour trip generation the original analysis is unchanged and fully valid. Hence, the change to 52 units will have no impact on the results or findings of the original December 2017 study.

As always, please do not hesitate to contact me if you or the Town of Cumberland have any questions or concerns regarding this updated trip generation analysis for OceanView at Cumberland.

MORABITO *

Sincerely, Diane W. Nords. 5

Diane W. Morabito, P.E. PTOE

President

• REFERENCE: OCEANVIEW AT FALMOUTH SCHOOLHOUSE COTTAGES









PREPARED FOR:

OCEANVIEW AT CUMBERLAND SENIOR COMMUNITY

TITLE:

TYPICAL COTTAGE COLORS AND PHOTOS

SCALE: FILL IN JOB NO: 16.084 **EX. 4**

SCHOOLHOUSE COTTAGES - A



OCEANVIEW

ABBREVATIONS SYMBOLS

PT & D

REINF

REQD

ACOUSTICAL CEILING TILE FEET (FOOT) **BITUMINOUS BENCH MARK** BRG BEARING BRK BRICK CARPET CABINT CHALK BOARD CENTER TO CENTER CONCRETE HARDENER CONTROL JOINT CENTER LINE CLG CEILING CMU CONCRETE MASONRY UNITS CONC CONT CONCRETE CONTINUOUS **CONST** CONSTRUCTION CONTRACTOR CERAMIC TILE DOUBLE DRINKING FOUNTAIN DIAMETER DIM DIMENSION DNA DOES NOT APPLY MAXIMUM DWG DRAWING **MECHANICAL** EACH

ELECTROMAGNETIC HOLD OPEN MTL

PROJECT DIRECTORY

GAWRON TURGEON ARCHITECTS

SCARBOROUGH, MAINE 04074

29 BLACK POINT ROAD

ELECTRIC WATER COOLER

FINISH FLOOR ELEVATION

EACH FACE

ELEVATION

ELECTRICAL

ELEVATOR

EQUAL **EACH WAY**

EXISTING

EXPANSION

FLOOR DRAIN

FOUNDATION FIRE EXTINGUISHER

FINISH FLOOR

OCEANVIEW AT FALMOUTH

FALMOUTH, MAINE 04105

20 BLUEBERRY LANE

207-781-4460

FINISH GRADE

EXTERIOR

ELEV

EMHO

FDN

FFE

EXIT OR (E)

FIN FL OR FF

EXPANSION JOINT

FIELD VERIFY FABRIC WALL COVERING GRANITE GAUGE GALVANIZED GRAB BARS GENERAL CONTRACTOR GYPSUM WALL BOARD HANDICAP **HARDWOOD** HEADER **HOLLOW METAL** HORIZONTAL HEIGHT INSIDE DIAMETER INSIDE FACE INCHES **INSULATION** INTERIOR INTERIOR LOCATION MARBLE MASONRY

MINIMUM

NORTH

NUMBER

NOMINAL

OVERALL

OPENING

OPPOSITE

PAINTED

STRUCT

MARKER BOARD MANUFACTURER MISCELLANEOUS MASONRY OPENING MOP RECEPTOR MOISTURE REST. GYP. BRD. NOT APPLICABLE VCT VERT NOT IN CONTACT VWC NOT TO SCALE ON CENTER **OUTSIDE DIAMETER** OUTSIDE FACE

PRESSURE TREATED PAPER TOWEL AND WASTE DISP. PARTITION **ROOF DRAIN** REFRIGERATOR REINFORCED REQUIRED

ROUGH OPENING

SHOWER CURTAIN

SOAP DISPENSER

SCHEDULE

STANDARD

SECTION

SHEET

SIMILAR

DOOR TAG

WALL TYPE

WINDOW TYPE

CEILING LABEL

INTERIOR LABEL

COLUMN LINE HEAD LABEL

BUILDING ELEVATION

BUILDING SECTION

WALL SECTION

DETAIL SECTION

INTERIOR ELEVATION

DEMO LABEL

SANITARY NAPKIN DISPOSAL SYNTHETIC SPORTS SURFACE

STRUCTURAL SHEET VINYL TEMPERED (GLASS) TACK BOARD THICKNESS TOP OF TOP OF BEAM TOP OF MASONRY TOP OF WALL

TOILET PAPER DISPENSER TYPICAL UNLESS NOTED OTHERWISE VAPOR BARRIER VINYL COMPOSITION TILE VERTICAL VINYL WALL COVERING

WATER CLOSET Name VERTICAL ELEVATION

GENERAL NOTES

1. THE GENERAL CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS, AND REPORT ANY DISCREPANCIES TO THE ARCHITECT. CONTRACTOR SHALL PROCEED WITH THE WORK ONLY AFTER

2. THE BUILDING SHALL BE CONSTRUCTED TO CONFORM WITH ALL APPLICABLE CODES INCLUDING, BUT NOT LIMITED TO, THE LATEST EDITIONS OF IBC, BOCA, NFPA 101, ADA & ANSI.

3. ALL WOOD IN CONTACT WITH CONCRETE SHALL BE PRESSURE PRESERVATIVE TREATED & ALL FASTENERS TO BE STAINLESS STEEL OR HOT DIPPED GALVANIZED. 4. CONTRACTOR SHALL WORK FROM GIVEN DIMENSIONS AND LARGE SCALE DETAILS ONLY.

5. ALL FLOORS SHALL BE LEVELED TO A TOLERANCE OF 1/8" IN 10'-0" WHEN CHECKED AT ANY AREA WITH

6. INSTALL BLOCKING BEHIND ALL SURFACE APPLIED FIXTURES, TRIM, CABINETS, COUNTER TOPS, AND GRAB BARS WHEN MOUNTED ON STUD WALLS, INCLUDING FUTURE WORK.

7. ALL GRAB BARS SHALL BE ABLE TO SUPPORT A DEAD WEIGHT OF 250 LBS AT ANY POINT

8. INSTALL MOISTURE RESISTANT GYPSUM BOARD IN LAVATORIES, JANITOR CLOSETS AND ALL OTHER HIGH

9. ALL SEALANT AROUND WINDOWS SHALL BE NON-HARDENING TYPE SEALANT

10. EXTEND WATERPROOF UNDERLAYMENT FROM EAVE UP ROOF TO MINIMUM 6'-0", 3'-0" MINIMUM AT ALL RAKES, HIPS, 11. ANY DOORS NOT LOCATED DIMENSIONALLY ARE TO BE 6" MIN. OFF ADJACENT WALL AT HINGE SIDE OF DOOR.


12. THE GENERAL CONTRACTOR SHALL COORDINATE ALL UTILITIES.

13. COTTAGE FRAMING MATERIAL SUBSTITUTIONS SHALL BE APPROVED BY THE ARCHITECT.

14. AT THE CRAWL SPACE PROVIDE 1/4" LUAN AT ALL CERAMIC TILE & SHEET VINYL AREAS OVER FLOOR JOISTS AND

15. REFER TO OWNER SELECTED FINISHES.

SITE LOCATION MAP



FALMOUTH, MAINE

MATERIALS

CONCRETE

CONCRETE MASONRY UNIT

GRAVEL

SOIL

WOOD FRAMING

WOOD BLOCKING

PLYWOOD

GYPSUM BOARD

BATT INSULATION

RIGID INSULATION

EXPANSION MATERIAL FINISH WOOD

CROWN MOLDING

CHAIR RAIL

SQUARE FOOTAGE

DRAWING INDEX

A502 BUILDING SECTION - CRAWL SPACE, FOUNDATION DETAILS & SCHEDULES

JNDATION PLAN - CRAWL SPACE OPTION W/ SECOND FLOOR OPTION

GENERAL NOTES, LEGEND AND BASIS OF DESIGN

G101 COVER SHEET

A101 FIRST FLOOR PLAN / WALL TYPES

BUILDING ELEVATIONS

BUILDING SECTIONS & WALL SECTION

A201 ROOF PLAN AND DETAILS

1ST FLOOR:

1,532 SF +/-

GARAGE/MECH:

419 SF +/-

	REVISIONS					
	#	DATE	DESCRIPTION			
	1	07.11.16	PRICING SET- PHASE FOUR			

DATE:	07.11.16	
PROJECT#	050712	
DRAWN BY:	AEP	
CHECKED BY:	RLD	
DRAWING SCALE	As indicated	

SHEET TITLE

COVER SHEET

1. UNIT PRICE NO. 1: CONSTRUCTION OF A ONE STORY COTTAGE WITH CRAWL SPACE

2. UNIT PRICE NO. 2: CONSTRUCTION OF A SECOND FLOOR- SEE BASEMENT DRAWINGS FOR SECOND FLOOR OPTION

3. UNIT PRICE NO. 3: CONSTRUCTION OF A TWO-CAR GARAGE.


UNIT PRICES


CRAWL SPACE

© COPYRIGHT 1985-2013











LEGEND: PROPOSED EXISTING O OR 🖸 OR 🌌 IRON PIPE OR MONUMENT BENCH MARK (SEE NOTES) TRAVERSE STATION TEST PIT CATCH BASIN SEWER MANHOLE FIRE HYDRANT WATER GATE VALVE WATER SHUT-OFF BLOW-OFF/CLEAN-OUT WELL UTILITY POLE POLE W/SINGLE LIGHT $\Diamond \Box \Diamond$ POLE W/DOUBLE LIGHT SPOT LIGHT & WALL LIGHT BOLLARD LIGHT RESIDENTIAL SEWER PUMP STATION GAS VALVE HANDICAP SYMBOL PAVEMENT PAINT MARKINGS PARKING SPACE COUNT PROPERTY LINE EASEMENTS SETBACK/BUFFER SOILS BOUNDARY WETLAND BOUNDARY STREAM CULVERT CONCRETE SLIPFORM GRANITE CURB VERTICAL CONCRETE CURE EDGE OF PAVEMENT ROAD CENTERLINE BUILDING STORM DRAIN(SEE PLAN FOR SIZE) SEWER LINE(SEE PLAN FOR SIZE) WATER LINE(SEE PLAN FOR SIZE) — w—— w—— w— - - - - WC - - - -CHILLER LINES SPOT ELEVATION SPOT: CURB TOP & BOTTOM CONTOURS CATCH BASIN HAY BALE BARRIER CLEARING LIMIT TREE LINE SILT FENCE CHAIN LINK FENCE WOOD GUARD RAIL RIPRAP CONSTRUCTION ENTRANCE CONCRETE PAVEMENT PAVEMENT OVERLAY BUILDING EXISTING BUILDING NOT IN CONTRACT PROGRESS PLAN NOT FOR CONSTRUCTION THIS DOCUMENT IS ISSUED FOR INFORMATIONAL PURPOSES ONLY. THE DATA SHOWN HEREON IS SUBJECT TO REVISION.

PROJECT SCALES

GRAPHIC SCALE (IN FEET) 1 inch = 20 ft.GRAPHIC SCALE (IN FEET) 1 inch = 40 ft.GRAPHIC SCALE (IN FEET) 1 inch = 100 ft.

GENERAL NOTES:

- TOPOGRAPHIC DATA IS BASED ON COMPILATIONS OF INFORMATION INCLUDING AERIAL INFORMATION, ON THE GROUND SURVEY, APPROVED DESIGN PLANS, AND FIELD OBSERVATIONS. ON THE GROUND SURVEYS HAVE BEEN COMPLETED BY TITCOMB ASSOCIATES IN 2017
- THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR THE ELEVATION OF THE EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND WHERE POSSIBLE MEASUREMENTS TAKEN IN THE FIELD. THIS INFORMATION HAS NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE AND IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR SHALL CALL THE APPROPRIATE UTILITY COMPANY AND DIG SAFE (1-800-DIG-SAFE) AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.
- SEE ARCHITECTURAL DRAWINGS FOR EXACT BUILDING DIMENSIONS AND ALL DETAILS CONTIGUOUS TO THE BUILDING, INCLUDING SIDEWALKS, RAMPS, BUILDING ENTRANCES, STAIRWAYS, UTILITY PENETRATIONS, CONCRETE DOOR PADS, COMPACTOR PAD, LOADING DOCKS, BOLLARDS ETC.
- LAYOUT DIMENSIONS ARE FROM FACE OF BUILDING, RETAINING WALLS, CURBS OR BERMS.
- RIM ELEVATIONS OF PROPOSED DRAINAGE AND SANITARY SEWER MANHOLES AND ASSOCIATED STRUCTURES ARE APPROXIMATE. FINAL ELEVATIONS ARE TO BE SET FLUSH AND CONSISTENT WITH THE GRADING PLANS. ADJUST ALL OTHER RIM ELEVATIONS OF MANHOLES, WATER GATES, GAS GATES AND OTHER UTILITIES TO FINISH GRADE WITHIN LIMITS OF WORK
- THE LOCATION, SIZE, DEPTH, AND SPECIFICATIONS FOR CONSTRUCTION OF PROPOSED PRIVATE UTILITY SERVICES SHALL BE INSTALLED ACCORDING TO THE REQUIREMENTS PROVIDED BY, AND APPROVED BY THE RESPECTIVE UTILITY COMPANY (GAS. TELEPHONE, ELECTRIC AND FIRE ALARM). FINAL DESIGN LOADS AND LOCATIONS TO BE COORDINATED WITH OWNER AND ARCHITECT.
- THE CONTRACTOR SHALL FIELD VERIFY THE LOCATION, SIZE, INVERTS AND TYPES OF EXISTING PIPES AT ALL PROPOSED POINTS OF CONNECTION PRIOR TO ORDERING MATERIALS. WHERE AN EXISTING UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, THE LOCATIONS, ELEVATION, AND SIZE OF THE UTILITY SHALL BE ACCURATELY DETERMINED WITHOUT DELAY BY THE CONTRACTOR, AND THE INFORMATION FURNISHED IN WRITING TO THE OWNER'S REPRESENTATIVE FOR THE RESOLUTION OF THE CONFLICT.
- ALL AREAS OUTSIDE THE LIMIT OF WORK THAT ARE DISTURBED SHALL BE RESTORED BY THE CONTRACTOR TO THEIR ORIGINAL CONDITION AT THE CONTRACTOR'S EXPENSE. ALL AREAS DISTURBED DURING CONSTRUCTION NOT COVERED WITH BUILDINGS, STRUCTURES, OR PAVEMENT SHALL RECEIVE 6 INCHES OF LOAM AND SEED.
- CONTRACTOR SHALL MAKE ALL ARRANGEMENTS AND SHALL BE RESPONSIBLE FOR PAYING ANY FEES FOR ANY POLE RELOCATION AND FOR THE ALTERATION OR ADJUSTMENT OF GAS. ELECTRIC. TELEPHONE. FIRE ALARM AND ANY OTHER PRIVATE UTILITIES BY THE UTILITY COMPANIES.
- UPON AWARD OF CONTRACT, CONTRACTOR SHALL MAKE ALL NECESSARY CONSTRUCTION NOTIFICATIONS AND APPLY FOR AND OBTAIN ALL NECESSARY PERMITS, PAY ALL FEES AND POST ALL BONDS ASSOCIATED WITH THE WORK INDICATED ON THE DRAWINGS.
- ALL PROPERTY MONUMENTATION DISTURBED DURING CONSTRUCTION SHALL BE RESET TO THEIR ORIGINAL LOCATION BY A MAINE REGISTERED PROFESSIONAL LAND SURVEYOR (PLS) AT THE
- THE CONTRACTOR SHALL PREPARE/PROVIDE AN AS-BUILT SURVEY SHOWING LOCATIONS OF ALL CONSTRUCTED SURFACE FEATURES AND SUBSURFACE UTILITY SYSTEMS INCLUDING THE GPS POINT LOCATION, TYPE, SIZE AND INVERTS. THE CONTRACTOR SHALL PROVIDE SURVEY POINTS AND DATA TO THE ENGINEER.
- CONTRACTOR SHALL INSTALL ALL EROSION CONTROL MEASURES PRIOR TO EARTHWORK OPERATION AND MAINTAIN ALL EROSION CONTROL MEASURES AND SEEDED EMBANKMENTS DURING CONSTRUCTION. EROSION CONTROL SHALL BE REMOVED ONLY UPON THE ESTABLISHMENT OF ALL LANDSCAPED AREAS. AL WORK SHALL BE IN COMPLIANCE WITH THE ENVIRONMENTAL QUALITY HANDBOOK FOR EROSION AND SEDIMENT CONTROL, LATEST EDITION, AS ADOPTED BY THE MAINE DEPARTMENT OF ENVIRONMENTAL PROTECTION.
- CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR SITE SECURITY AND JOB SAFETY. ALL CONSTRUCTION ACTIVITY SHALL BE IN ACCORDANCE WITH OSHA STANDARDS AND LOCAL REQUIREMENTS.
- ALL MATERIALS AND CONSTRUCTION METHODS USED WITHIN THE PUBLIC RIGHT-OF-WAY SHALL CONFORM TO ALL LOCAL MUNICIPAL STANDARDS AND MAINE DEPARTMENT OF TRANSPORTATION
- ALL HANDICAP ACCESSIBLE PARKING SPACES, RAMPS AND SIDEWALKS SHALL BE CONSTRUCTED IN CONFORMANCE WITH THE AMERICANS WITH DISABILITIES ACT (ADA).
- ALL SITE SIGNAGE AND PAVEMENT MARKINGS SHALL CONFORM TO THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.

LAYOUT NOTES:

- ALL DIMENSIONING, UNLESS NOTED OTHERWISE, IS TO THE FACE OF CURB OR BUILDING.
- OFFSETS TO CATCH BASINS AND MANHOLES ARE TO THE CENTER OF THE FRAME.

ACTUAL SURVEY AND BOUNDARY SURVEY REFERENCES.

- PIPE LENGTH EQUALS THE CENTER TO CENTER DISTANCES BETWEEN CATCH BASINS AND/OR MANHOLES MINUS ONE HALF THE DIAMETER OF EACH CATCH BASIN OR MANHOLE.
- BOUNDARY INFORMATION ON LAYOUT PLAN IS FOR REFERENCE ONLY, REFER TO ALTA SURVEY FOR

GRADING AND DRAINAGE NOTES:

SMOOTH BORE HDPE POLYETHYLENE PIPE

- UNLESS OTHERWISE NOTED, ALL STORM DRAIN PIPE SHALL BE IN ACCORDANCE WITH MDOT SPECIFICATIONS SECTION 603. PIPE CULVERTS AND STORM DRAINS, LATEST REVISION WITH THE EXCEPTION THAT THE ONLY ACCEPTABLE TYPES OF PIPE ARE AS FOLLOWS: REINFORCED CONCRETE PIPE POLYVINYL CHLORIDE PIPE (PVC)
- TOPSOIL STRIPPED IN AREAS OF CONSTRUCTION THAT IS SUITABLE FOR REUSE AS LOAM SHALL BE
- STOCKPILED ON SITE AT A LOCATION TO BE DESIGNATED BY OWNER. UNSUITABLE SOIL SHALL BE SEPARATED, REMOVED AND DISPOSED OF AT AN APPROVED DISPOSAL LOCATION OFF SITE.
- THE CONTRACTOR SHALL ANTICIPATE THAT GROUNDWATER WILL BE ENCOUNTERED DURING CONSTRUCTION AND SHALL INCLUDE SUFFICIENT COSTS WITHIN THEIR BID TO PROVIDE DEWATERING AS NECESSARY NO SEPARATE PAYMENT SHALL BE MADE TO THE CONTRACTOR FOR DEWATERING.

EROSION CONTROL NOTES:

- LAND DISTURBING ACTIVITIES SHALL BE ACCOMPLISHED IN A MANNER AND SEQUENCE THAT CAUSES THE LEAST PRACTICAL DISTURBANCE OF THE SITE. SEE EROSION CONTROL PLAN FOR EROSION CONTROL SEQUENCING.
- ALL EROSION CONTROL METHODS IMPLEMENTED SHALL CONFORM TO THE "MAINE EROSION AND SEDIMENT CONTROL EST MANAGEMENT PRACTICES (BMP's) MANUAL" DATED OCTOBER 2016 BY THE DEPARTMENT OF ENVIRONMENTAL PROTECTION. http://www.maine.gov/dep/land/erosion/escbmps/esc_bmp_engineers.pdf
- PRIOR TO THE COMMENCEMENT OF CONSTRUCTION, THE CONTRACTOR SHALL PLACE THE EROSION CONTROL BMPS INCLUDING SILT FENCE, BERMS, EROSION CONTROL MIX, ETC.. THE CONTRACTOR SHALL INSPECT THE BARRIER AND OTHER PREVENTATIVE MEASURES BI-WEEKLY, BEFORE ANY PREDICTED RAIN EVENT, AND AFTER ANY RAIN EVENT. THE CONTRACTOR SHALL REMOVE ANY ACCUMULATED SILT AND/OR MAKE REPAIRS AS
- THE CONTRACTOR IS CAUTIONED THAT FAILURE TO COMPLY WITH THE SEQUENCE OF CONSTRUCTION, EROSION/SEDIMENT CONTROL PLAN, AND OTHER PERMIT REQUIREMENTS MAY RESULT IN MONETARY PENALTIES. THE CONTRACTOR SHALL BE ASSESSED ALL SUCH PENALTIES AT NO COST TO THE OWNER OR PERMITTEE.

APPROVALS REQUIRED:

- TOWN OF CUMBERLAND PLANNING BOARD 2. MAINE DEP SITE LOCATION OF DEVELOPMENT PERMIT.
- 3. MAINE DEP NRPA TIER 1 PERMIT.
- 4. MAINE DOT ENTRANCE PERMIT.

OCEANVIEW @ CUMBERLAND Tuttle Road, Cumberland, Maine

SHEET INDEX:

COVER SHEET

C11A-C11B. LANDSCAPE PLANS 1"=60"

SUBDIVISION PLAT BY TITCOMB ASSOCIATES

OVERALL PHASING PLAN 1"=100'

PLAN & PROFILES *SCALE:* 1" = 40'

STRUCTURE NOTES AND TABLES

EROSION CONTROL NOTES AND DETAILS

LOW PRESSURE SEWER MAIN DETAILS

FORESTED BUFFER BEHIND UNITS 50-52

FOCALPOINT 20 SCALE PLAN VIEW

SITE DEVELOPMENT DETAILS

ARCH CULVERT DETAILS

WET POND DETAILS

FOCALPOINT DETAILS

TOPOGRAPHIC SITE PLAN BY TITCOMB ASSOCIATES

OVERALL SITE DEVELOPMENT PLAN *SCALE:* 1" = 60"

OVERALL SITE DEVELOPMENT PLAN *SCALE:* 1" = 40"

OVERALL SITE DEVELOPMENT PLAN *SCALE:* 1" = 40'

OVERALL SITE DEVELOPMENT PLAN SCALE: 1" = 40'

TRAIL AND WALKWAY MASTER PLAN 1" = 100'

ROADWAY SECTIONS, EROSION DETAILS, AND GENERAL NOTES

ROOF DRIPLINE BMP, BOULDER WALL, AND MISC. DETAILS

CLASS B HIGH INTENSITY SOIL SURVEY BY MARK HAMPTON

PRE DEVELOPMENT DRAINAGE PLAN - SUBMITTED SEPARATELY

POST DEVELOPMENT DRAINAGE PLAN - SUBMITTED SEPARATELY


SH 1 PORTLAND WATER DISTRICT STANDARD DETAILS

SH 2 PORTLAND WATER DISTRICT STANDARD DETAILS

MANCINI ELECTRICAL PHOTOMETRIC PLAN

EXISTING CONDITIONS AND REMOVALS PLAN 1"=100'

March 1, 2018 Town Re-submittal Submission Set



LOCATION MAP

UTILITY INFO & CONTACTS:

CONTACT: HERB STEVENS, 800.750.4000

SUMMIT NATURAL GAS: 12 INCH MAIN, W. SIDE TUTTLE RD. CONTACT: MICHAEL STINCHFIELD, PROJECT MANAGER 207.620.8000

WATER: PORTLAND WATER DISTRICT: 12 C.I.INCH MAIN, E. SIDE TUTTLE RD. CONTACT: ROBERT BARTELS, MEANS DEPT. 207.774.5961 X3199

SANITARY SEWER: PORTLAND WATER DISTRICT - 8 INCH GRAVITY SS, W. SIDE TUTTLE RD. CONTACT: ROBERT BARTELS, MEANS DEPT. 207.774.5961 X3199

ELECTRIC CENTRAL MAINE POWER: 3 PHASE OVERHEAD, W. SIDE TUTTLE RD.

COMMUNICATIONS/CTV: SPECTRUM COMMUNICATIONS, OVERHEAD, W. SIDE TUTTLE ROAD CONTACT: PETER DETESO, 207.318.6542

TELE; FAIRPOINT & CONSOLIDATED, OVERHEAD, W. SIDE TUTTLE ROAD

CONTACT MATT FREE (CONSOLIDATED), 207.626.2007

STREET OPENING: TOWN OF CUMBERLAND URBAN COMPACT& (MDOT) CONTACT: MDOT SCARBOROGH, REGION 1, 207.885.7000 CONTACT: CUMBERLAND DPW: CHRIS BOLDUC, 207.829.2220

DESIGN CONSULTANTS:

BELANGER ENGINEERING *63 SECOND AVENUE*

AUGUSTA, ME 04330 (207) 622-0543

LICHT ENVIRONMENTAL DESIGN

GRAY, ME 04330 (207) 749-4924

Prepared in association with:

DAVE HAYNES

MAINE REGISTERED LANDSCAPE ARCHITECT OCEAN VIEW RETIREMENT **COMMUNITY** 207-653-9427

TITCOMB ASSOCIATES

39 COURT STREET BATH, ME 04530 (207) 443-9199

ANTHONY MANCINI, INC. *179 SHERIDAN STREET*

PORTLAND, MAINE 04101 (207) 774-5829

35 FRAN CIRCLE

SCARBOROUGH, MAINE 04074 207-883-6307

GAWRON / TURGEON ARCHITECTS

29 BLACK PT. ROAD

3.	3-1-2018	Respond to Town Memos, Re-submit to Town	CSB
2.	2-7-2018	Submit to Maine DEP	CSB
1.	1-31-2018	Respond to Town Memos, submit to Town	CSB
		Cover Sheet and Notes	
	2	Oceanview at Cumberland LLC 77 Tuttle Road, Cumberland, Maine	
		Seacoast Management Company	

20 Blueberry Lane, Falmouth, Maine


SITE PLANNING & DESIGN





CONSULTING ENGINEERS Email: cbelanger@roadrunner.com 63 Second Avenue , Augusta, Maine 04330 Ph 207-622-1462, Cell 207-242-5713 JOB #: 109

FIELD WK: DRN BY: SS: CH'D BY: FILE: DATE: 3-1-2018

CHRISTOPHER BELANGER 9098 3/ONAL







OV AT CUMBERLAND SUBDIV PLAN NOTES

1) THIS PROJECT IS BEING PROPOSED AS A SENIOR HOUSING COMMUNITY PERMITTED UNDER THE TOWN OF CUMBERLAND LAND USE ORDINANCE SECTION 315-28.4. THE PROJECT INCLUDES 52 COTTAGE UNITS, A COMMUNITY CENTER AND ASSOCIATED INFRASTRUCTURE.

2) PROJECT LIES WITHIN THE RR1 ZONING DISTRICT AND SENIOR HOUSING COMMUNITY (SHC) OVERLAY DISTRICT

3) WETLANDS MAPPING BY HAMPTON ASSOCIATES, FALL 2016 AND LOCATED BY GPS SURVEY (HAMPTON ASSOC. AND TITCOMB ASSOC, SURVEYORS.)

4) SITE TOPOGRAPHY AND EXISTING CONDITIONS FROM A FIELD SURVEY BY TITCOMB ASSOCIATES, SURVEYORS WITH INFORMATION SUPPLEMENTED FROM THE STATE OF MAINE GIS DIGITAL ORTHO AND LIDAR MAPPING AS NOTED.

5) PROJECT TO BE SERVICED BY PUBLIC WATER, PRIVATE ON—SITE LOW PRESSURE SEWER SYSTEM DISCHARGING TO THE PORTLAND WATER DISTRICT PUBLIC SEWERAGE SYSTEM IN TUTTLE ROAD, NATURAL GAS AND UNDERGROUND CABLE UTILITIES.

6) ARCTIC FOX DRIVE, BUTTERNUT LANE, DOGWOOD LANE, LITTLE ACRES DRIVE, LONE PINE LANE, MALLARD WAY AND SWEETFERN LANE SHALL REMAIN PRIVATE.

7) COTTAGE UNITS AND FOOTPRINT STYLES AND DRIVEWAY LOCATIONS ARE SHOWN IN THE GENERAL LOCATIONS INTENDED TO BE CONSTRUCTED. HOWEVER APPROVAL. FINAL LOCATIONS AND BUILDING TYPES MAY VARY SLIGHTLY TO FIT FIELD CONDITIONS.

8) THERE SHALL BE NO LESS THAN TWO PARKING SPACE PER UNIT PER ORDINANCE SECTION 315-28.4.F. GARAGES AND ONE SPACE IN THE DRIVEWAY MAY BE USED TO MEET THIS REQUIREMENT.

9) REFER TO SITE DATA TABLE FOR SETBACKS AND DIMENSIONAL REQUIREMENTS.

10) THIS PLAT SHALL BE RECORDED WITHIN 90 DAYS OF FINAL SUBDIVISION APPROVAL AND SIGNING OF THE PLAT BY THE TOWN OF CUMBERLAND PLANNING BOARD, SUBJECT TO THE ESTABLISHMENT OF ANY PERFORMANCE GUARANTEE. APPROVAL OF ANY SUBDIVISION PLAN NOT RECORDED WITHIN 90 DAYS AFTER FINAL PLAN APPROVAL SHALL BECOME NULL AND VOID.

RR1 AND SENIOR HOUSING COMMUNITY ZONING (SHC) OVERLAY DISTRICT **PROVIDED** STANDARD MIN. LOT AREA (AC) 5 AC 36.83 (1) MIN. FRONTAGE (FT) A. EDGE PAVED ROAD 25+ B. BETWEEN STRUCTURES 20+ C. DEVELOPMENT PROPERTY LINE 50+ MAXIMUM DENSITY (LAND 30,852 AREA/UNIT) (3.) MAX. ALLOWABLE UNITS (2) 78% (28.8 AC.) **OPEN SPACE** 20% (7.4 AC.) MAX. STRUCTURE HEIGHT (FT.) 40 (4.) PERIMETER BUFFER (FT.)

NOTES:

1. ACCESS EASEMENT IS 1.67 AC. -TOTAL "PROJECT" = 38.50 ACRES

PROJECT EXCLUDES 2.8 ACRE ALLEN OUT-LOT
2. NOT INCLUDING PROPOSED COMMUNITY CENTER

3. DENSITY BASED ON LOT AREA OF 36.83 AC. NOT INCLUDING ACCESS ESMT.
4. TYPICAL COTTAGE HEIGHTS ARE 23 FEET+/-. NO BUILDING SHALL EXCEED 40 FT.

SURVEY NOTES

1) BOOK AND PAGE REFERENCES ARE TO THE CUMBERLAND COUNTY REGISTRY OF DEEDS.

2) BEARINGS ARE REFERENCED TO GRID NORTH, MAINE STATE PLANE COORDINATE SYSTEM, NAD83, WEST ZONE.

4) UTILITY INFORMATION ON THIS PLAN IS APPROXIMATE, BASED ON LOCATION OF VISIBLE FEATURES. DIGSAFE AND/OR THE APPROPRIATE UTILITIES SHOULD BE CONTACTED PRIOR TO ANY CONSTRUCTION.

5) PROPERTY LIES WITHIN ZONE C BASED ON FIRM COMMUNITY #230162 PANEL #0015 B, DATED MAY 19, 1981. IT DOES NOT LIE WITHIN A SPECIAL FLOOD HAZARD AREA.

OWNERS OF RECORD

Richard W. Doane Book 2851, Page 184 Book 15205, Page 239

Laurence S, Allen Book 3003, Page 347

PROJECT AREA

36.83 acres

PLAN REFERENCES

1) RIGHT-OF-WAY AND TRACK MAP, MAINE CENTRAL R.R., STATION 307+80 TO STATION 360+60, JUNE 30, 1916. MCRR FILE NO. V2/S1 AND V2/S2.

2) STANDARD BOUNDARY SURVEY PREPARED FOR MARION B. SMALL BY GARY E. JOHNSON, RLS. 1261, DATED AUG. 1987. UNRECORDED.

3) PLAN OF WYMAN FARM, CUMBERLAND CENTER, MAINE, BY EARL RAND, DATED MAY 2, 1931. UNRECORDED.

4) PLAN OF TUTTLE ROAD IN CUMBERLAND FROM CUMBERLAND CENTER TO FEDERAL ROAD, SURVEYED OCT. 11, 1926 BY WM. E. WINSLOW. RECORDED IN THE CUMBERLAND COUNTY COMMISSIONERS PLAN BOOK 5, PAGE 2.

5) ORIGINAL LOTTING PLAN OF NORTH YARMOUTH, RECORDED INTHE CUMBERLAND COUNTY REGISTRY OF DEEDS, PLAN BOOK 24,PAGE 14. CUMBERLAND COUNTY REGISTRY OF DEEDS IN PLAN BOOK 203, PAGE 82.


6) AMENDED PLAN OF PRIVATE WAY MADE FOR RICHARD DOANE BY TITCOMB ASSOCIATES DATED MAY 7, 1990 AND REVISED THROUGH NOV. 11. 2009 AND RECORDED IN PLAN BOOK 204, PAGE 895

7) RECORDING PLAT OF SMALL'S BROOK CROSSING SUBDIVISION MADE BY LAND USE CONSULTANTS, DATED OCTOBER 14, 1991 AND REVISED THROUGH OCTOBER 7, 1992 AND RECORDED IN PLAN BOOK 192, PAGE 312-314.

PRELIMINARY

n
ľ

pproved by the Town of umberland Planning Board
ed



S-4 Sheet 4 of 4

Rev. 3	03/02/18	miscellaneous staff comment revisions	RjC				
Rev. 2	02/21/18	additional feature locations	JS				
Rev. 1	01/30/18	Allen lot, design revisions					
		SUBDIVISION PLAN					
		Oceanview at Cumberland					
	Tuttle Road	Cumberland, Maine					
		MADE FOR					
	O	ceanview at Cumberland LLC					
20	20 Blueberry Lane Falmouth, Maine						

BOOK #898

89076_2016.dwg

DATE: December 26, 2017 | SCALE: 1" = 50'

(207)797-9199 www.titcombsurvey.com


Rex J. Croteau, P.L.S. #2273


Licensure for Land Surveyors.


This survey conforms to the current standards of


practice set forth by the Maine State Board of


CERTIFICATION
































Prepared in association with:

1. 1-31-2018 Respond to Town Memos, submit to Town and DEP


2. 2-7-2018 SUBMIT TO DEP

Plan and Profile

CSB

Oceanview at Cumberland 291 Tuttle Road, Cumberland, Maine


Seacoast Management Company 20 Blueberry Lane, Falmouth, Maine





	!	BEL	<u>AN</u>	GER	
人	> EN	IGII	NEE	RII	NG
63 Seco	ond Avenue	CONSUL	TING ENG	SINEERS	Email: c

• COMMERCIAL PROJECTS
• RESIDENTIAL SUBDIVISIONS
• TOWN AND STATE APPROVALS
• SITE PLANNING & DESIGN
• STORMWATER MANAGEMENT
• ROAD AND UTILITY DESIGN
• EROSION CONTROL PLANS
mail: cbelanger@roadrunner.com
2h 207-622-1462, Cell 207-242-5713

FIELD WK:	SCALE: 1"=40'	SHEET:
DRN BY:	JOB #: 109	
CH'D BY:	SS:	
DATE: 2-7-2018	FILE:	









PROGRESS PLAN NOT FOR CONSTRUCTION

THIS DOCUMENT IS ISSUED FOR INFORMATIONAL PURPOSES ONLY.
THE DATA SHOWN HEREON IS SUBJECT TO REVISION.

3	3-1-2018	Respond to Town Comments, Re-submit to Town	CSB
2	2-7-2018	SUBMIT TO DEP	CSB
1	1-31-2018	Respond to Town Memos, submit to Town and DEP	CSB

Plan and Profile

Oceanview at Cumberland LLC 277 Tuttle Road, Cumberland, Maine


Seacoast Management Company
20 Blueberry Lane, Falmouth, Maine





blackerry Lane, raililoa	cii, ividiiic
ELANGER	 COMMERCIAL PROJECTS RESIDENTIAL SUBDIVISION TOWN AND STATE APPRO
GINEERING	 SITE PLANNING & DESIGN STORMWATER MANAGER ROAD AND UTILITY DESIGN FROSION CONTROL PLAN


ENGINEERING : STORMWATER MANAGEMENT ROAD AND UTILITY DESIGN EROSION CONTROL PLANS Email: cbelanger@roadrunner.com
Ph 207-622-1462, Cell 207-242-5713


FIELD WK:	SCALE: 1"=40'	SHEET:
DRN BY:	JOB #: 109	CO
CH'D BY:	SS:	C8
DATE: 3-1-2018	FILE:	














1. ALL EROSION CONTROL METHODS SHALL CONFORM TO THE MAINE EROSION AND

ENCOUNTERED. CONTRACTOR SHALL ASSUME UNDERDRAIN IS REQUIRED IN CUT

UNDERDRAIN ON THAT SIDE OF ROAD. UNDERDRAIN IS STILL REQUIRED ON OTHER SIDE OF ROAD TO MEET TOWN SPECIFICATION. INSTALL TYPE C UNDERDRAIN WITH UNDERDRAIN IS USED (HOLES DOWN). TIE UNDERDRAIN INTO CATCH BASINS AS

EROSION CONTROL NOTES:

AFTER FINAL PAVEMENT OVERLAY.

SEDIMENT CONTROL HANDBOOK FOR CONSTRUCTION BEST MANAGEMENT PRACTICES BY THE 1. ALL UTILITIES TO BE LOCATED UNDERGROUND. CUMBERLAND COUNTY SOIL WATER CONSERVATION DISTRICT, AND THE DEPARTMENT OF ENVIRONMENTAL PROTECTION.

2. PRIOR TO THE COMMENCEMENT OF CONSTRUCTION, THE CONTRACTOR SHALL PLACE THE WITH THE RESPECTIVE OWNERS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLYING SILT FENCE. THE CONTRACTOR SHALL INSPECT THE BARRIER AND OTHER PREVENTATIVE MEASURES BI-WEEKLY, BEFORE ANY PREDICTED RAIN EVENT, AND AFTER ANY RAIN EVENT. THE CONTRACTOR SHALL REMOVE ANY ACCUMULATED SILT AND/OR MAKE REPAIRS AS

3. ALL TOPSOIL SHALL BE SAVED TO LOAM LANDSCAPED AREAS TO A DEPTH OF 4". LOAM SHALL BE STOCKPILED ON SITE IN A LOCATION CONVENIENT TO THE CONTRACTOR. THE STOCKPILE WILL BE TEMPORARILY SEEDED WITH RYE GRASS AND MULCHED AT 75 90 LBS/1000SF, ALL SOIL STOCKPILES ARE TO BE ENCLOSED WITH SILT FENCE. STOCKPILES SHALL PRE- CONSTRUCTION CONFERENCE MUST BE HELD WITH ALL UTILITY REPRESENTATIVES. NOT BE LOCATED IN WETLAND STEEP SLOPES, OR AREAS OF CONCERTRATING FLOW.

4. ALL AREAS DISTURBED BY CONSTRUCTION SHALL BE PERMANENTLY SEEDED. SEEDING SHALL BE PERFORMED IN ACCORDANCE WITH MOOT SPECIFICATION: LIME AT 3 TONS/ACRE: 6. 4" CABLE & TELEPHONE SERVICE WILL BE CONSTRUCTED IN THE SAME TRENCH AS ELECTRIC FERTILIZER 10-10-10 AT 13.8LBS/1000 SF: SEED MDOT PARK MIX AT 3 LBS/1000 SF. - SEEDING SHALL BE PERFORMED BETWEEN APRIL 15 - JUNE 15 OR AUGUST 15 - SEPTEMBER 15. WINTER RYE SHALL BE USED AS TEMPORARY SEED BETWEEN SEPTEMBER 15 - OCTOBER 15. ALL FINISHED SLOPES EXCEEDING 15% SHALL ALSO HAVE MULCH NETTING INSTALLED AND PINNED PADS. THE ROAD CONTRACTOR SHALL INSTALL ANY ADDITIONAL CONDUIT NEEDED WHERE DOWN. AFTER SEPTEMBER 15, THE SAME APPLIES TO ALL SLOPES EXCEEDING 8%.

5. ALL AREAS TO BE SEEDED SHALL BE MULCHED. MULCH SHALL BE LONG FIBERED HAY OR STRAW AND SPREAD UNIFORMLY. 1.5 TO 2.0 TONS PER ACRE. TO BE MAINTAINED MOIST TO MINIMIZE BLOWING AS NECESSARY. IN WINTER CONDITIONS, NO MULCH IS TO BE APPLIED OVER SNOW. THE SNOW MUST FIRST BE REMOVED AND THEN MULCH APPLIED ACCORDING TO SPECIFICATIONS STATED PRIOR. IN ALL CASES MULCH SHALL BE APPLIED SUCH THAT THE SOIL SURFACE IS NOT VISIBLE THROUGH THE MULCH. DURING NOVEMBER 1 THROUGH APRIL 1 BEFORE CONSTRUCTION.

MULCHING SHALL BE COMPLETED DAILY BY THE END OF THE WORK DAY. 6. PLACE SILT SACKS IN CATCH BASIN INLET DURING CONSTRUCTION. CONTACT AH HARRIS IN PORTLAND (207) 775-5764 OR AUGUSTA (207) 622-0821 SILT SACKS SHALL BE REMOVED

7. ALL SEDIMENT CONTROL FENCING AND SILT SACKS BARRIERS WILL REMAIN IN PLACE UNTIL SEEDLINGS HAVE BEEN ESTABLISHED.

8. ALL EARTH CHANGES WILL BE CONSTRUCTED AND COMPLETED IN SUCH A MANNER SO THAT THE EXPOSED AREA OF ANY DISTURBED LAND WILL BE LIMITED TO THE SHORTEST PERIOD OF TIME POSSIBLE. THE CONTRACTOR SHALL COMPLETE FINAL GRADING, SEEDING, AND MULCHING IN CONJUNCTION WITH THE COMPLETION OF THE CORRESPONDING BUILDINGS WHENEVER POSSIBLE. IF FINAL GRADING CANNOT BE COMPLETED THEN THE CONTRACTOR IS TO MULCH ANY DISTURBED LAND AND WORK ON TOP OF THE MULCH. AREAS OF DISTURBED SOIL WILL BE TEMPORARILY MULCHED OR SEEDED WITHIN 30 DAYS OF INITIAL

9. SEDIMENT CAUSED BY ACCELERATED SOIL EROSION WILL BE REMOVED FROM RUNOFF WATER BEFORE IT LEAVES THE DEVELOPMENT SITE.

10. ALL TEMPORARY OR PERMANENT FACILITY CONSTRUCTED FOR THE CONVEYANCE OF WATER AROUND, THROUGH, OR FROM THE DEVELOPMENT SITE WILL BE CONSTRUCTED TO LIMIT THE WATER FLOW TO A NON-EROSIVE VELOCITY.

11. PERMANENT SOIL EROSION CONTROL MEASURES FOR ALL SLOPES, CHANNELS, DITCHES, OR ANY DISTURBED LAND AREA WILL BE COMPLETED WITHIN 15 DAYS AFTER FINAL GRADING HAS BEEN COMPLETED.

12. IN THE EVENT THAT TEMPORARY OR PERMANENT SEEDLINGS HAVE NOT BEEN ESTABLISHED (90% SURFACE COVERAGE) BY SEPTEMBER 15, TEMPORARY MULCHING SHALL BE APPLIED FOR PROTECTION OVER WINTER (PAST THE GROWING SEASON) IN ACCORDANCE WITH THE TEMPORARY MULCHING BMP OF THE MAINE EROSION AND SEDIMENT CONTROL

HANDBOOK. A. MULCHING FOR OVER WINTER PROTECTION WILL BE COMPLETED BY NOVEMBER 15 B. WINTER MULCH ON SLOPES 8% OR GREATER WILL BE ANCHORED WITH NETTING. C. ALL SOILS DISTURBED PRIOR TO NOVEMBER 1 AND NOT HAVING THE REQUIRED COVER OF VEGETATION WILL BE STABILIZED WITH ANCHORED MULCH BY NOVEMBER 15.

13. PROVIDE TWO TEMPORARY CMP RISERS AT EXISTING CATCH BASIN AND WRAP WITH EROSION CONTROL FABRIC TO CONTROL POTENTIAL SEDIMENTATION. INSTALL STONE BERM OR HAY BALES AROUND CATCH DURING CONSTRUCTION..

14. NO EARTH MOVING OR CONSTRUCTION OPERATIONS ARE ANTICIPATED ON THE EXISTING STEEP SLOPE EXCEPT FOR RIP-RAP SLOPE PROTECTION. ALL DISTURBED AREAS SHALL BE SEEDED AND MULCHED IN ACCORDANCE WITH OTHER EROSION CONTROL NOTES.

15. DURING WINTER CONSTRUCTION THE CONTRACTOR SHALL INSTALL AN EROSION CONTROL FILTER BERM. THE CONTRACTOR SHALL INSTALL THE BERMS AS SEDIMENT BARRIERS DURING FROZEN GROUND CONDITIONS.

PAVING, GRADING & DRAINAGE NOTES

1. VERTICAL DATUM IS NATIONAL GEODETIC DATUM 1929 DEFINITION. BENCHMARK LOCATIONS ARE SPECIFIED ON TITCOMB SURVEY.

2. CLEARING LIMITS WILL BE FLAGGED BY THE ENGINEER AND THE OWNER. THE CONTRACTOR 6. THE CABLE COMPANY WILL SUPPLY THE SERVICE WIRES. SHALL NOT CUT BEYOND THE LIMITS OR REMOVE A TREE DESIGNATED TO BE SAVED WITHOUT THE OWNER'S AND ENGINEER'S CONSENT.

3. ALL CURBS AND WALKS SHALL BE STAKED OUT BY THE CONTRACTOR AND APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION. SIDEWALKS TO BE 4' WIDE FROM DRIVEWAY TO THE FRONT DOOR AND SET BACK 4' FROM THE HOUSE

APPROPRIATE TO MEET SITE CONDITIONS.

TRAIL SYSTEM NOTES:

1. A TRAIL SYSTEM SHALL BE INSTALLED THROUGH OCEANVIEW AT CUMBERLAND PROPERTY TO PROVIDE PEDESTRIAN ACCESS. THE TRAIL SYSTEM WILL FORM LINKS TO ABUTTING PARCELS AND CONNECTION TO TOWN TRAIL SYSTEMS. THE TRAIL SYSTEM WILL BE AVAILABLE FOR PUBLIC & PRIVATE USE. THE DETAILED DESIGN WILL BE COORDINATED WITH THE TOWN PLANNER, PLANNING BOARD, AND THE OWNER.

1. ALL CONSTRUCTION TO BE IN COMPLIANCE WITH VERIZON CONSTRUCTION STANDARDS.

2. ALL TRENCHING, CONDUIT AND BACK FILLING IS THE CONTRACTOR'S RESPONSIBILITY.


3. ALL CABLES SHALL BE IN CONDUIT UNDER ALL PAVED ROADS, DRIVEWAYS AND WALKWAYS. 4" FOR THE MAIN CABLE AND 2" FOR SERVICE WIRES.

4. CONDUITS FOR SERVICE WIRES SHOULD BE INSTALLED AT ALL LOCATIONS WHERE REQUIRED DURING THE INITIAL INSTALLATION OF THE MAIN CABLE. 5. THE TRENCH MUST BE FILLED WITH "SUITABLE" BACK FILL, I.E., SAND BACK FILL WITH NO

STONE LARGER THAN 1/4" IN DIAMETER

6. VERIZON WILL SUPPLY THE CABLE AND LABOR TO INSTALL SAME.

7. A SEPARATION OF 12" HORIZONTAL OR VERTICAL MUST BE MAINTAINED BETWEEN VERIZON AND ALL OTHER UTILITIES SUCH AS ELECTRIC, CABLE TV, OR OTHERS.



UTILITIES GENERAL NOTES

2. THE LOCATION OF EXISTING UNDERGROUND UTILITIES IS NOT GUARANTEED. THE CONTRACTOR SHALL VERIFY THE LOCATION OF UNDERGROUND UTILITIES AND STRUCTURES WITH THE REQUIREMENTS OF UTILITY AN STRUCTURE OWNERS REGARDING NOTIFICATION OF WORK AND PROTECTION OF EXISTING FACILITIES.

SEWER CONSTRUCTION NOTES:

COPIES OF UTILITY PLAN.

OF CUMBERLAND STANDARD SPECIFICATIONS.

1. SEWER LINE CONSTRUCTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE TOWN

2. MINIMUM DIAMETER FOR MAINLINE SEWER IS EIGHT INCH (8") WITH A MINIMUM SLOPE

3. SANITARY SEWER SERVICE STUBS TO BE SIX INCH (6") DIAMETER MINIMUM AND TO BE

INSTALLED BEYOND THE EDGE OF PAVEMENT, AND UTILITY TRENCH AS SHOWN ON PLAN.

BITUMINOUS COATING. WITH SMOOTH CHANNELED INVERTS. AND PROPERLY SIZED AND

ORIENTED PRECAST PIPE OPENINGS WITH FLEXIBLE PIPE BOOTS. STEPS TO BE INSTALLED

PARALLEL TO INVERT CHANNEL. SERVICE CONNECTIONS TO BE INCORPORATED IN INVERT

6. MANHOLE FRAMES AND COVERS TO BE SUITABLE FOR HIGHWAY LOADING AND TO BE TO

7. DESIGN AND CONSTRUCTION OF PROJECT SANITARY SEWER UTILITY WILL BE CARRIED OU

TO SPECIFICALLY EXCLUDE THE INTRODUCTION OF NON-SANITARY GROUND AND / OR

8. ALL GRAVITY SEWER TO BE LOW PRESSURE AIR AND DEFLECTION TESTED AFTER BACK

9. PRIOR TO THE START OF CONSTRUCTION, DEVELOPER TO PROVIDE TO DISTRICT TWO (2)

10. MINIMUM HORIZONTAL CLEARANCES TO BE MAINTAINED BETWEEN UTILITIES, TO PERMIT

L. TEST PITS SHALL BE EXCAVATED AT CROSSINGS OF UTILITIES TO DETERMINE LOCATION

2. MINIMUM DEPTH OF COVER FOR ALL WATER LINES SHALL BE 5.5' FROM FINISHED GRADE

3. PROPOSED PIPELINE, VALVE, AND HYDRANT LOCATIONS ARE APPROXIMATE. FINAL

LOCATION MAY BE ADJUSTED AS REQUIRED TO AVOID CONFLICTS WITH OTHER UTILITIES

AND STRUCTURES. NO ADDITIONAL PAYMENT WILL BE MADE FOR EXCAVATION AND BACK

4. ANY EXISTING PIPELINE, UTILITY OR STRUCTURE, INCLUDING EXISTING WATER MAINS,

5. ALL PROPERTY REMOVED, DAMAGED OR ALTERED IN THE COURSE OF THE WORK SHALL

MATERIALS FOR THE PROJECT INCLUDING PIPE, COUPLINGS, VALVES, FITTINGS, HYDRANTS

PIPING, CURB BOXES, RETAINER GLANDS, AND ACCESSORIES SUCH AS GASKETS, BOLTS,

8. A SEPARATION OF 12" VERTICAL CLEARANCE MUST BE MAINTAINED BETWEEN THE

SERVICED BY A 1 1/2" LINE OFF THE MAIN, SPLIT AT THE UNIT TO PROVIDE A 1"CTS

STANDARDS OF THE PORTLAND WATER DISTRICT. SIZES SHALL BE CONFIRMED BY THE

TESTED BY THE CONTRACTOR PRIOR TO ACCEPTANCE BY THE OWNER, SERVICES SHALL BE

INSTALLED UNDER LINE PRESSURE AFTER THE MAIN HAS BEEN SUCCESSFULLY PRESSURE

9. ALL WATER MAIN SIZES ARE AS INDICATED ON THE PLAN/PROFILES. EACH UNIT SHALL BE

DOMESTIC SUPPLY AND A 1 1/2" SPRINKLER SUPPLY INSTALLED IN ACCORDANCE WITH THE

GRAVEL, SAND, AND BORROW SHALL BE FURNISHED BY THE CONTRACTOR.

NUTS, AND GLANDS AS REQUIRED TO MAKE THE PIPING SYSTEMS COMPLETE SHALL MEET

PWD SPECIFICATIONS. ALL CONCRETE AND EARTH MATERIALS INCLUDING CRUSHED STONE

BE REPLACED OR RESTORED TO EQUAL OR BETTER CONDITION TO THAT WHICH EXISTED

DAMAGED BY CONTRACTOR'S OPERATIONS SHALL BE IMMEDIATELY REPAIRED BY

AND DEPTH SUFFICIENTLY IN ADVANCE OF WATER MAIN CONSTRUCTION TO PERMIT

ADJUSTMENT OF WATER MAIN LOCATION BY DEFLECTION OF THE PIPE.

FILL BEYOND THE TRENCH LIMITS SHOWN.

BEFORE THE WORK COMMENCED.

WITH GRIP-RING RETAINER GLANDS.

WATER MAIN AND ALL OTHER UTILITIES.

SPRINKLER INSTALLER PRIOR TO CONSTRUCTION.

CONTRACTOR AT NO ADDITIONAL COST TO OWNER.

FILLING AND COMPACTION AND PRIOR TO CONNECTION OF BUILDING SEWER.

FUTURE MAINTENANCE OPERATIONS WITHOUT DISTURBING ADJACENT UTILITIES,

3. CONTRACTOR SHALL VERIFY ALL CRITICAL DIMENSIONS AND GRADES TO HIS SATISFACTION 4. SANITARY SEWER SERVICE STUBS TO BE CONNECTED TO THE MAIN LINE BY USE OF 8X8X6 BEFORE WORK BEGINS. ANY DISCREPANCIES SHALL BE REPORTED IMMEDIATELY TO THE WYES. TEE STUBS WILL NOT BE ALLOWED.

4. ALL UTILITIES ARE TO BE CONSTRUCTED TO THE STANDARDS SET BY THE RESPECTIVE UTILITY. 5. SANITARY SEWER MANHOLES TO BE PER ASTM SPECIFICATIONS, WITH TWO (2) COATS OF

5. A MINIMUM OF 12" HORIZONTAL SPACING IS NECESSARY BETWEEN CABLES.

7. THE ROAD CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING ELECTRIC, TELEPHONE, & CABLE UP TO AND INCLUDING THE INSTALLATION OF JUNCTION BOXES AND TRANSFORMER INDIVIDUAL UNIT SERVICES CROSS THE ROADWAY. THE SITE CONTRACTOR SHALL BE RESPONSIBLE TO EXTEND INDIVIDUAL SERVICE FROM THE TRANSFORMER PAD TO THE BUILDING. SURFACE WATER INTO THE SANITARY SEWER SYSTEM. THE SITE CONTRACTOR IS REQUIRED TO INSTALL CONDUIT AT ALL PAVEMENT CROSSINGS OTHER THAN THE ROADWAY

8. THE ROADWAY CONTRACTOR SHALL SET UP A SCOPING MEETING WITH THE SITE CONTRACTOR TO CONFIRM LIMITS OF WORK, SCHEDULING, AND CONSTRUCTION SEQUENCE

1. THE PROPOSED DISTRIBUTION SYSTEM PLAN SHALL BE COORDINATED WITH CENTRAL MAINE WATER CONSTRUCTION NOTES: POWER COMPANY

2. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH CMP'S CONSTRUCTION STANDARDS AND THE LATEST REVISION OF THE NATIONAL ELECTRICAL SAFTEY CODE.

3. ALL TRENCHING, CONDUIT AND BACK FILLING IS THE CONTRACTOR'S RESPONSIBILITY. 4. CONDUITS SHALL BE A MINIMUM OF SCHEDULE 40 PVC OR EQUIVALENT.

REQUIRED DURING THE INITIAL INSTALLATION OF THE PRIMARY CABLE.

5. ALL CABLES SHALL BE IN CONDUIT UNDER ALL PAVED AREAS, ROADWAYS, AND DRIVEWAYS PRIMARY CABLES ARE TO BE INSTALLED IN CONDUIT IF DRIVEWAYS ARE NOT ROUGH GRADED. 6. CONDUITS FOR SECONDARY CABLES SHOULD BE INSTALLED AT ALL LOCATIONS WHERE

7. PRIMARY CABLE TO BE #2 AL 15 KV.

8. SEE CMP'S CONTRACTOR HANDBOOK, SECTION IX, PARAGRAPHS 910, 911, AND 912 FOR SPECIFICATIONS ON BACK-FILL MATERIALS AND DEPTHS, ETC.

9. ALL TRANSFORMER PADS MUST BE SUPPLIED AND INSTALLED BY THE CONTRACTOR. PAD DESIGNS MUST CONFORM TO CMP SPECIFICATIONS. SEE ILLUSTRATIONS NO. 19, NO. 20, NO. 21

6. ALL FITTINGS, VALVES, AND HYDRANTS SHALL HAVE MECHANICAL JOINTS RESTRAINED IN SECTION XII OF THE CONTRACTOR'S HANDBOOK.

10. ALL JUNCTION BOXES WILL BE PURCHASED AND INSTALLED BY THE CONTRACTOR. CMP WILL 7. CONSTRUCTION SHALL FOLLOW PORTLAND WATER DISTRICT STANDARDS. ALL PROVIDE THE JUNCTION BOX, HOWEVER, THE EXCESS COST WILL BE BILLED TO THE OWNER. FIBERGLASS OR CONCRETE PADS REQUIRED FOR STELL CABINETS AND JUNCTION BOXES. TAPPING SLEEVES AND VALVES, VALVE BOXES, CORPORATION STOPS, CURB STOPS, SERVICE

11. CMP WILL SUPPLY THE CABLE, TRANSFORMERS AND LABOR TO INSTALL SAME. 12. ALL METERING ENCLOSURES WILL BE PUNCHED AND INSTALLED BY THE CONTRACTOR.

13. A SEPARATION OF 12" MUST BE MAINTAINED BETWEEN CMP AND ALL OTHER UTILITIES AND/OR TELEPHONE, CABLE ETC.

1. ALL TRENCHING, CONDUIT & BACK FILLING IS THE CONTRACTORS RESPONSIBILITY.

2. CONDUITS SHALL BE SCHEDULE 40 PVC AND WILL BE ROPED WITH 1/4" ROPE.

3. ALL CABLES SHALL BE IN CONDUIT UNDER ALL PAVED ROADS, DRIVEWAYS AND WALKWAYS AS 10. THE COMPLETE PIPING SYSTEM SHALL BE FLUSHED, CHLORINATED, AND PRESSURE NOTED OR SHOWN ON THE PLAN; 4" FOR THE MAIN CABLE AND 2" FOR THE SERVICE WIRES. 4. CONDUITS FOR SERVICE WIRES SHOULD BE INSTALLED AT ALL LOCATIONS WHERE REQUIRED TESTED. DURING THE INSTALLATION OF THE MAIN CABLE.

5. THE CABLE COMPANY WILL SUPPLY THE MAIN CABLE AND PEDESTALS AND THE LABOR TO

7. ELECTRICAL CONTRACTOR SHALL COORDINATE WITH THE CABLE COMPANY FOR INTERNAL


8. ALL SERVICE WIRE INSTALLATIONS AND INTERIOR WIRING SHALL CONFORM TO THE CABLE COMPANY SPECIFICATIONS.

4. DRIVEWAYS TO BE 24' WIDE AT THE GARAGE DOOR AND MAY TRANSITION TO 20' WIDTH AS

9. A SEPARATION OF 12" HORIZONTAL OR VERTICAL MUST BE MAINTAINED BETWEEN THE CABLE

COMPANY AND ALL OTHER UTILITIES SUCH AS ELECTRIC, TELEPHONE OR OTHERS.

10. CONTRACTOR SHALL EXPOSE GROUND ROD AT ALL PAD LOCATIONS TO INSURE PROPER GROUNDING FOR THE CABLE COMPANY.




2. 2-7-2018 Re-Submit to Town and Maine DEP 1. 1-31-2018

Roadway Sections and Details

Respond to Town Memos, Re-submit to Town

Oceanview at Cumberland 291 Tuttle Road, Cumberland, Maine

Seacoast Management Company 20 Blueberry Lane, Falmouth, Maine





SHEET: FIELD WK: JOB #: 109 CH'D BY: SS: FILE: DATE: 3-1-2018

CSB

STRUCTURE NAME: RIM ELEVATION INV. IN: INV. OUT STA / OFFS C2 RIM = 87.57 INV OUT =87.00 Sta 38+36.10, Offset CB2 RIM = 89.26 INV IN =84.80 INV OUT =84.55 Sta 12+51.28, Offset CB2A RIM = 89.25 INV OUT =84.76 Sta 12+50.68, Offset CB3 RIM = 94.14 INV IN =82.93 INV OUT =82.80 Sta 15+59.36, Offset	SET
CB2 RIM = 89.26 INV IN =84.80 INV OUT =84.55 Sta 12+51.28, Offset CB2A RIM = 89.25 INV OUT =84.76 Sta 12+50.68, Offset CB3 RIM = 94.14 INV IN =82.93 INV OUT =82.80 Sta 15+59.36 Offset	
CB2 RIM = 89.26 INV IN =84.56 INV OUT =84.55 Sta 12+51.28, Offset CB2A RIM = 89.25 INV OUT =84.76 Sta 12+50.68, Offset	t 274.81, R
CB3 RIM = 94.14 INV IN =82.93 INV OUT =82.80 Sta 15+59.36 Offset	t -9.94, L
	t 9.57, R
	t 44.00, R
CB3A RIM = 94.13 INV IN =82.70 INV OUT =82.50 Sta 15+73.78, Offset	t 10.06, R
CB4 RIM = 99.40 INV OUT =95.80 Sta 43+22.15, Offset	t 28.98, R
CB5 RIM = 93.69 INV OUT =89.50 Sta 15+33.30, Offset	t -17.98, L
CB6 RIM = 93.05 INV IN =87.90 INV OUT =87.80 Sta 21+44.88, Offset	t -10.17, L
CB7 RIM = 93.05 INV OUT =88.00 Sta 21+44.34, Offset	t 10.09, R
CB13 RIM = 101.27 INV IN =96.36 INV OUT =93.00 Sta 24+06.66, Offset	t 10.34, R
CB13A RIM = 101.30 INV IN =96.85 INV OUT =96.56 Sta 24+05.98, Offset	
CB16 RIM = 99.41 INV IN =92.69 INV OUT =91.30 Sta 43+85.19, Offset	t 36.32, R
CB17 RIM = 98.31 INV IN =90.24 INV OUT =90.14 Sta 44+34.93, Offset INV IN =91.47	t 10.13, R
CB17A RIM = 98.32 INV IN =90.52 INV OUT =92.82 Sta 44+41.65, Offset	t 29.06, R
CB18 RIM = 100.70 INV IN =89.54 INV OUT =89.44 Sta 42+71.08, Offset	t -10.11, L
CB18A RIM = 99.90 INV IN =91.96 INV OUT =91.80 Sta 44+50.00, Offset	t 40.60, R
CB18B RIM = 99.90 INV OUT =93.00 Sta 22+68.58, Offset	t 219.16, R
CB20 RIM = 100.41 INV IN =88.65 INV IN =93.07 INV OUT =88.50 Sta ???, Offset ???,	???
CB21 RIM = 100.40 INV IN =93.31 INV OUT =93.21 Sta 46+79.11, Offset	t -41.43, L
CB22 RIM = 102.32 INV OUT =97.54 Sta 28+99.93, Offset	t -9.87, L
CB23 RIM = 102.32 INV IN =97.35 INV OUT =97.25 Sta 28+99.71, Offset	t 9.96, R
CB24 RIM = 99.65 INV IN =93.00 INV OUT =92.87 Sta 31+79.30, Offset INV IN =93.00	t 9.43, R
CB24A RIM = 99.74 INV IN =93.20 INV OUT =93.10 Sta 31+79.17, Offset	t -9.82, L
CB25 RIM = 98.99 INV IN =92.60 INV OUT =92.50 Sta 31+90.51, Offset	t 15.48, R
CB26 RIM = 98.05 INV IN =93.59 INV OUT =93.04 Sta 33+15.17, Offset	t 10.00, R
CB27 RIM = 98.05 INV IN =92.21 INV OUT =93.79 Sta 33+57.13, Offset	t -10.18, L
CB28 RIM = 100.04 INV IN =91.95 INV OUT =91.85 Sta 51+24.60, Offset	t -9.12, L
CB30 RIM = 96.97 INV IN =90.26 INV OUT =90.16 Sta 31+66.96, Offset	t 396.00, R
CB30A RIM = 96.97 INV OUT =92.35 Sta 31+56.84, Offset	t 397.97, R
CB31 RIM = 94.95 INV IN =89.67 INV OUT =89.57 Sta 55+05.31, Offset	t -9.64, L
INV IN =89.67	,
INV IN =89.14 INV OUT =89.00 Sta 56+05.12, Offset	
CB32A RIM = 93.92 INV OUT =89.34 Sta 38+31.41, Offset	
CB33 RIM = 95.70 INV IN =88.25 INV OUT =88.15 Sta 57+62.97, Offset	
INV IN =87.66 INV OUT =87.58 Sta 37+77.85, Offset	t 157.72, R
CB35 RIM = 94.04 INV IN =88.60 INV OUT =88.46 Sta 38+94.02, Offset	t 23.37, R
CB35A RIM = 93.70 INV OUT =89.65 Sta 39+36.12, Offset	t 9.99, R
CB36 RIM = 95.25 INV OUT =90.38 Sta 38+28.26, Offset	t -9.62, L
CB40 RIM = 99.90 INV IN =93.92 INV OUT =93.82 Sta 30+26.99, Offset	t 35.97, R
CB41 RIM = 101.67 INV IN =94.37 INV OUT =94.27 Sta 30+46.50, Offset	·
CB42 RIM = 100.14 INV IN =95.04 INV OUT =94.94 Sta 20+31.07, Offset	
CB43 RIM = 100.15 INV OUT =95.24 Sta 31+56.47, Offset	
CB44 RIM = 95.91 INV OUT =93.37 Sta ???, Offset ???, 1 CB45 RIM = 95.78 INV IN =93.17 INV OUT =93.07 Sta 21+21.00, Offset	
CB45 RIM = 95.78 INV IN =93.17 INV OUT =93.07 Sta 21+21.00, Offset CB46 RIM = 97.80 INV OUT =93.54 Sta 34+50.93, Offset	
CB46 RIM = 97.80 INV IN =92.83 INV OUT =93.54 Sta 34+50.95, Offset	
CB48 RIM = 98.07 INV OUT =93.00 Sta 66+00.63, Offset	
CB49 RIM = 97.90 INV OUT =93.91 Sta 33+00.54, Offset	
CB50 RIM = 99.90 INV IN =93.46 INV OUT =93.36 Sta 32+07.60, Offset	·
CB51 RIM = 97.90 INV OUT =93.54 Sta 31+72.78, Offset	t 38.89, R
CB60 RIM = 94.93 INV IN =90.50 INV OUT =90.40 Sta 60+65.91, Offset	t -8.03, L

					Pipe Table	
NAME	SIZE	LENGTH	SLOPE	Inv. in	Inv. out	MATERIAL
Arch 2	122"	73.61'	2.04%	Inv. in=90.00	Inv. out=88.50	122 x 77 inch Concrete Horizontal Elliptical Arch Pipe
ARCH1	88"	68.93'	0.73%	Inv. in=81.50	Inv. out=81.00	
Culv1	15"	63.38'	0.63%	Inv. in=83.50	Inv. out=83.10	15 inch Corrugated HDPE Pipe
CULV3	18"	90.56'	0.55%	Inv. in=82.50	Inv. out=82.00	18 inch Corrugated HDPE Pipe
CULV4	12"	51.30'	1.95%	Inv. in=96.00	Inv. out=95.00	12" N-12 ADS
CULV5	12"	46.36'	3.66%	Inv. in=86.50	Inv. out=84.80	12 inch Corrugated HDPE Pipe
CULV5 (1)	12"	46.36'	3.66%	Inv. in=86.50	Inv. out=84.80	12 inch Corrugated HDPE Pipe
CULV5 (2)	12"	46.36'	3.66%	Inv. in=86.50	Inv. out=84.80	12 inch Corrugated HDPE Pipe
01	6"	3.04'	0.99%	Inv. in=74.78	Inv. out=74.75	6" ORIFICE CORED INTO STRUCTURE
02	6"	2.73'	0.00%	Inv. in=89.50	Inv. out=89.50	Cut 6"X6" Notch into top Outlet Control Structure
SD OCS1	18"	58.06'	6.89%	Inv. in=74.00	Inv. out=70.00	18 inch Corrugated HDPE Pipe
SD OCS2	24"	31.08'	1.61%	Inv. in=86.50	Inv. out=86.00	24" N-12 ADS HDPE Pipe
						·
SD2	18"	321.93'	0.50%	Inv. in=84.55	Inv. out=82.93	18 inch Corrugated HDPE Pipe
SD2A	18"	19.52'	1.03%	Inv. in=84.76	Inv. out=84.56	18 inch Corrugated HDPE Pipe
SD3	18"	19.90'	0.50%	Inv. in=82.80	Inv. out=82.70	10 inch Commissated UDDE Disc.
SD3A	18"	167.07'	0.63%		Inv. out=81.45	18 inch Corrugated HDPE Pipe
SD4	12"	64.31'	1.00%	Inv. in=95.80	Inv. out=95.15	
SD5	15"	40.52'	1.00%	Inv. in=89.50	Inv. out=89.09	
SD6	15"	28.15'	1.89%	Inv. in=87.80	Inv. out=87.27	45 N 42 ADC
SD7	15"	20.26'	0.50%	Inv. in=88.00	Inv. out=87.90	15" N-12 ADS
SD13	18"	123.57'	0.25%	Inv. in=93.00	Inv. out=92.69	18 inch Corrugated HDPE Pipe
SD13A	15"	19.81'	1.01%	Inv. in=96.56	Inv. out=96.36	10 in the Commented LIDDE Ding
SD16	18"	56.22'	1.89%	Inv. in=91.30	Inv. out=90.24	18 inch Corrugated HDPE Pipe
SD17	18"	97.00'	0.61%	Inv. in=90.14	Inv. out=89.54	18 inch Corrugated HDPE Pipe
SD17A	15"	20.09'	0.98%	Inv. in=92.82	Inv. out=92.62	
SD18	18"	83.89'	0.95%	Inv. in=89.44	Inv. out=88.65	18 inch Corrugated HDPE Pipe
SD18A	15"	14.24'	8.96%	Inv. in=91.80	Inv. out=90.52	15 inch Corrugated HDPE Pipe
SD18B	15"	94.43'	1.10%	Inv. in=93.00	Inv. out=91.96	15 inch Corrugated HDPE Pipe
SD20	18"	118.03'	4.66%	Inv. in=88.50	Inv. out=83.00	18 inch Corrugated HDPE Pipe
SD21	18"	27.90'	0.50%	Inv. in=93.21	Inv. out=93.07	18 inch Corrugated HDPE Pipe
SD22	18"	19.83'	1.00%	Inv. in=97.54	Inv. out=97.35	18 inch Corrugated HDPE Pipe
SD23	18"	238.06'	1.78%	Inv. in=97.25	Inv. out=93.00	18 inch Corrugated HDPE Pipe
SD24	18"	54.62'	0.50%	Inv. in=92.87	Inv. out=92.60	18 inch Corrugated HDPE Pipe
SD24A	18"	19.24'	0.50%	Inv. in=93.10	Inv. out=93.00	
SD25	18"	109.74'	0.50%	Inv. in=92.50	Inv. out=91.95	18 inch Corrugated HDPE Pipe
SD26	18"	125.13'	0.35%	Inv. in=93.04	Inv. out=92.60	18 inch Corrugated HDPE Pipe
SD27	15"	20.18'	1.00%	Inv. in=93.79	Inv. out=93.59	15" N-12 ADS
SD28	18"	70.01'	0.50%	Inv. in=91.85	Inv. out=91.50	18 inch Corrugated HDPE Pipe
SD28 (1)	18"	109.90'	0.50%	Inv. in=91.38	Inv. out=90.83	18 inch Corrugated HDPE Pipe
SD29	18"	94.09'	0.50%	Inv. in=90.73	Inv. out=90.26	18 inch Corrugated HDPE Pipe
SD30	18"	97.03'	0.50%	Inv. in=90.16	Inv. out=89.67	18 inch Corrugated HDPE Pipe
SD30A	15"	20.25'	1.73%	Inv. in=92.35	Inv. out=92.00	
SD31	18"	91.58'	0.50%	Inv. in=89.57	Inv. out=89.11	18 inch Corrugated HDPE Pipe
SD32	18"	149.07'	0.50%	Inv. in=89.00	Inv. out=88.25	18 inch Corrugated HDPE Pipe
SD32A	18"	20.01'	1.00%	Inv. in=89.34	Inv. out=89.14	18 inch Corrugated HDPE Pipe
SD33	18"	158.21'	0.30%	Inv. in=88.15	Inv. out=87.68	18 inch Corrugated HDPE Pipe
SD34	18"	14.96'	0.50%	Inv. in=87.58	Inv. out=87.51	18 inch Corrugated HDPE Pipe
SD35	18"	164.82'	0.49%	Inv. in=88.46	Inv. out=87.66	18 inch Corrugated HDPE Pipe
SD35A	15"	46.37'	2.27%	Inv. in=89.65	Inv. out=88.60	
SD36	18"	41.24'	4.31%	Inv. in=90.38	Inv. out=88.60	18 inch Corrugated HDPE Pipe

STRUCTURE TABLE							
STRUCTURE NAME:	RIM ELEVATION	INV. IN:	INV. OUT	STA / OFFSET			
CB61	RIM = 94.92		INV OUT =90.70	Sta 60+66.20, Offset 8.17, R			
CB62	RIM = 100.42	INV IN =91.50 INV IN =94.00	INV OUT =91.38	Sta 32+15.63, Offset 193.70, R			
CB66	RIM = 101.26		INV OUT =96.00	Sta 51+94.51, Offset 37.51, R			
CB70	RIM = 103.50		INV OUT =99.40	Sta 27+41.77, Offset -95.62, L			
CB71	RIM = 103.50	INV IN =98.98	INV OUT =98.88	Sta 26+61.30, Offset -97.73, L			
CB72	RIM = 103.50	INV IN =98.49	INV OUT =98.39	Sta 25+64.59, Offset -100.46, L			
CB73	RIM = 104.27	INV IN =97.93	INV OUT =97.83	Sta 25+85.84, Offset -9.99, L			
CB74	RIM = 101.65	INV IN =97.32	INV OUT =97.22	Sta 24+82.15, Offset -9.71, L			
J1	RIM = 75.18	INV IN =74.64	INV OUT =74.64	Sta 47+54.66, Offset 219.28, R			
OCS1	RIM = 78.82	INV IN =74.75 INV IN =74.50	INV OUT =74.00	Sta 0+73.53, Offset -1.63, L			
OCS2	RIM = 90.50	INV IN =89.50 INV IN =86.50	INV OUT =86.50	Sta 38+22.42, Offset 304.39, R			
SD29	RIM = 98.81	INV IN =90.83	INV OUT =90.73	Sta 31+63.17, Offset 302.18, R			

Pipe Table								
NAME	SIZE	LENGTH	SLOPE	Inv. in	Inv. out	MATERIAL		
SD40	15"	102.52'	0.50%	Inv. in=93.82	Inv. out=93.31	15" N-12 ADS		
SD41	15"	70.34'	0.50%	Inv. in=94.27	Inv. out=93.92			
SD42	12"	113.86'	0.50%	Inv. in=94.94	Inv. out=94.37	12" N-12 ADS		
SD43	12"	15.83'	1.27%	Inv. in=95.24	Inv. out=95.04	12" N-12 ADS		
SD44	12"	16.05'	1.23%	Inv. in=93.37	Inv. out=93.17			
SD45	12"	116.83'	1.37%	Inv. in=93.07	Inv. out=91.47	12" N-12 ADS		
SD46	15"	71.38'	1.00%	Inv. in=93.54	Inv. out=92.83	12" N-12 ADS		
SD47	15"	36.19'	1.42%	Inv. in=92.73	Inv. out=92.21	15" N-12 ADS		
SD48	12"	80.84'	-1.18%	Inv. in=93.00	Inv. out=93.95	12 inch Corrugated HDPE Pip		
SD49	15"	90.73'	0.50%	Inv. in=93.91	Inv. out=93.46	15 inch Corrugated HDPE Pip		
SD50	15"	31.56'	0.50%	Inv. in=93.36	Inv. out=93.20	15 inch Corrugated HDPE Pip		
SD51	15"	30.18'	1.79%	Inv. in=93.54	Inv. out=93.00	15 inch Corrugated HDPE Pip		
SD60	12"	82.29'	0.89%	Inv. in=90.40	Inv. out=89.67			
SD61	12"	16.21'	1.24%	Inv. in=90.70	Inv. out=90.50			
SD66	15"	45.94'	4.35%	Inv. in=96.00	Inv. out=94.00			
SD70	12"	84.00'	0.50%	Inv. in=99.40	Inv. out=98.98	12" N-12 ADS		
SD71	12"	78.64'	0.50%	Inv. in=98.88	Inv. out=98.49	12" N-12 ADS		
SD72	12"	92.40'	0.50%	Inv. in=98.39	Inv. out=97.93	12" N-12 ADS		
SD73	12"	101.47'	0.50%	Inv. in=97.83	Inv. out=97.32	12" N-12 ADS		
SD74	12"	74.64'	0.50%	Inv. in=97.22	Inv. out=96.85	12" N-12 ADS		
UD1	6"	12.96'	1.07%	Inv. in=74.64	Inv. out=74.50	6.0 inch PERF. PVC Pipe		
UD1A	6"	28.98'	0.81%	Inv. in=74.87	Inv. out=74.64	6.0 inch PERF PVC Pipe		
UD2	6"	39.96'	1.25%	Inv. in=87.00	Inv. out=86.50	6" SDR35 PERFORATED Pipe		

	Little Acres Drive				
Number	Radius	Length	Line/Chord Direction		
L19		24.33	N35° 42' 05.55"E		
C17	150.00	38.55	N28° 20' 23.11"E		
L20		484.37	N20° 58' 40.67"E		
C18	300.00	59.02	N15° 20' 30.44"E		
L21		233.12	N9° 42' 20.21"E		
L22		43.09	N42° 13' 35.21"E		
C22	500.00	460.63	N15° 50' 03.23"E		
L23		80.99	N10° 33' 28.75"W		
C23	150.00	142.20	N16° 36' 00.12"E		
L24		303.30	N43° 45' 28.98"E		
C24	400.00	59.82	N39° 28' 24.96"E		
L25		137.03	N35° 11' 20.94"E		
C25	150.00	104.10	N55° 04' 11.47"E		
L26		87.70	N74° 57' 02.00"E		
C26	150.00	131.52	S79° 55' 48.53"E		
L27		27.92	S54° 48' 39.06"E		
C27	300.00	217.18	S75° 32' 59.23"E		

Number	Radius	Length	Line/Chord Direction	A Value
L14		107.82	S54° 48' 39.06"E	
C13	150.00	37.97	S47° 33' 30.29"E	
L15		145.26	S40° 18' 21.52"E	
C14	150.00	37.97	S47° 33' 30.29"E	
L16		77.97	S54° 48' 39.06"E	
C15	150.00	235.62	N80° 11' 20.94"E	
L17		35.81	N35° 11' 20.94"E	
C16	200.00	112.67	N19° 03' 03.11"E	
L18		222.67	N2° 54' 45.29"E	

Arctic Fox Drive				
Number	Radius	Length	Line/Chord Direction	A Value
L30		41.45	S68° 23' 45.76"E	
C29	150.00	173.83	S35° 11' 49.84"E	
L31		130.86	S1° 59' 53.93"E	
C30	40.41	247.52	N2° 31' 31.13"E	

STRUCTURE TABLE				
STRUCTURE NAME:	RIM ELEVATION	INV. IN:	INV. OUT	STA / OFFSET
SMH1	RIM = 85.39	INV IN =78.00		Sta 10+07.30, Offset 53.09, F
SMH2	RIM = 86.30	INV IN =81.50	INV OUT =81.40	Sta 10+41.29, Offset 54.65, F
SMH3	RIM = 94.48	INV IN =87.77	INV OUT =87.60	Sta 15+67.45, Offset 49.36, F
SMH4	RIM = 97.65		INV OUT =90.60	Sta 17+52.54, Offset 11.83, I
SMH6	RIM = 101.77	INV IN =96.77 INV IN =96.77	INV OUT =96.77	Sta 23+83.99, Offset -5.00, L
SMH7	RIM = 101.97	INV IN =96.80 INV IN =96.80		Sta 44+04.66, Offset -7.45, L
SMH8	RIM = 99.42	INV IN =94.40 INV IN =94.40	INV OUT =94.30	Sta 32+16.37, Offset -5.03, L
SMH9	RIM = 94.80	INV IN =90.00 INV IN =90.00	INV OUT =90.00	Sta 38+59.98, Offset -4.92, L

Pipe Table						
NAME	SIZE	LENGTH	SLOPE	Inv. in	Inv. out	MATERIAL
SP2	8"	40.55'	8.37%	Inv. in=81.40	Inv. out=78.00	8" SDR35
SP3	8"	533.45'	1.14%	Inv. in=87.60	Inv. out=81.50	8" SDR35
SP4	8"	188.85'	1.50%	Inv. in=90.60	Inv. out=87.77	8" SDR35
SP6A	3"	3.64'	102.42%	Inv. in=100.50	Inv. out=96.77	4" FM
SP6B	3"	3.16'	-111.20%	Inv. in=96.77	Inv. out=100.29	4" HDPE FM
SP6C	3"	3.33'	112.15%	Inv. in=100.50	Inv. out=96.77	3 inch HDPE Pipe
SP7A	3"	3.58'	29.65%	Inv. in=97.86	Inv. out=96.80	3 inch HDPE Pipe
SP7B	3"	3.38'	44.38%	Inv. in=98.30	Inv. out=96.80	3 inch HDPE Pipe
SP8A	4"	4.81'	-9.35%	Inv. in=94.30	Inv. out=94.75	4" HDPE Pipe
SP8B	4"	4.91'	7.62%	Inv. in=94.77	Inv. out=94.40	4" HDPE Pipe
SP8C	3"	5.06'	6.91%	Inv. in=94.75	Inv. out=94.40	2" HDPE FM
SP9A	3"	3.79'	0.00%	Inv. in=90.00	Inv. out=90.00	3 inch HDPE Pipe
SP9B	3"	4.37'	0.00%	Inv. in=90.00	Inv. out=90.00	3 inch HDPE Pipe
SP9C	3"	4.48'	0.00%	Inv. in=90.00	Inv. out=90.00	3 inch HDPE Pipe

3. 3-1-2018 Respond to Town Comments, re-submit to Town

2. 2-7-2018 SUBMIT TO DEP

1. 1—31—2018 Respond to Town Memos, submit to Town and DEP


Structure and Pipe Tables

Oceanview at Cumberland 277Tuttle Road, Cumberland, Maine

Seacoast Management Company 20 Blueberry Lane, Falmouth, Maine



DATE: 3-1-2018



SS:


FILE:


C13A

CSB

CSB

CSB





EROSION AND SEDIMENTATION NOTES:

1. The Site Contractor shall follow the "Maine Erosion and Sediment Control BMPs" published by the Maine DEP in 2003 and the "Maine Erosion and Sediment Control Practices Field Guide for Contractors published in 2016 or most current update". The manuals can be found on the Maine DEP web site. A Link to the field guide is shown

http://www.maine.gov/dep/land/erosion/escbmps/index.html

THE CONTRACTOR SHALL ALSO FOLLOW THE GUIDELINES LISTED IN

APPENDICES A, B, C IN MAINE DEP CHAPTER 500 RULES (2015 NOTES PROVIDED ON THIS SHEET).

GENERAL EROSION AND SEDIMENTATION CONTROL PRACTICES: **EROSION/SEDIMENT CONTROL DEVICES:**

THE FOLLOWING EROSION SEDIMENTATION CONTROL DEVICES ARE PROPOSED FOR CONSTRUCTION ON THIS PROJECT. INSTALL THESE DEVICES AS INDICATED ON THE PLANS.

1 SILT FENCE: SILT FENCE WILL BE INSTALLED ALONG THE DOWN GRADING EDGES OF DISTURBED AREAS TO TRAP RUNOFF BORNE SEDIMENTS UNTIL THE SITE IS STABILIZED. IN AREAS WHERE STORMWATER DISCHARGES THE SILT FENCE WILL BE REINFORCED WITH HAY BALES TO HELP MAINTAIN THE INTEGRITY OF THE SILT FENCE AND TO PROVIDE ADDITIONAL TREATMENT.

2. HAY BALES: HAY BALES TO BE PLACED IN LOW FLOW DRAINAGE SWALES AND PATHS TO TRAP SEDIMENTS AND REDUCE RUNOFF VELOCITIES. DO NOT PLACE HAY BALES IN FLOWING WATER OR STREAMS.

3. RIPRAP: PROVIDE RIPRAP IN AREAS WHERE CULVERTS DISCHARGE OR AS SHOWN ON THE PLANS.

4. LOAM, SEED, & MULCH: ALL DISTURBED AREAS, WHICH ARE NOT OTHERWISE TREATED, SHALL RECEIVE PERMANENT SEEDING AND MULCH TO STABILIZE THE DISTURBED AREAS. THE DISTURBED AREAS WILL BE REVEGETATED WITHIN 5 DAYS OF FINAL GRADING. SEEDING REQUIREMENTS ARE PROVIDED AT THE END OF THIS SPECIFICATION.

5. STRAW AND HAY MULCH: USED TO COVER DENUDED AREAS UNTIL PERMANENT SEED OR EROSION CONTROL MEASURES ARE IN PLACE. MULCH BY ITSELF CAN BE USED ON SLOPES LESS THAN 15% IN SUMMER AND 8% IN WINTER. JUTE MESH IS TO BE USED OVER MULCH ONLY. CURLEX II AND EXCELSIOR MAY BE USED IN PLACE OF JUTE MESH OVER MULCH.

6. MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL DRAINAGE WAYS WITH A SLOPE GREATER THAN 3% FOR SLOPES EXPOSED TO DIRECT WINDS AND FOR ALL OTHER SLOPES GREATER THAN 8%.

TEMPORARY EROSION/SEDIMENTATION CONTROL MEASURES:

PROVIDE THE FOLLOWING TEMPORARY EROSION/SEDIMENTATION CONTROL MEASURES DURING CONSTRUCTION OF THE DEVELOPMENT:

1. SILTATION FENCE ALONG THE DOWNGRADIENT SIDE OF THE PARKING AREAS AND OF ALL FILL SECTIONS. THE SILTATION FENCE WILL REMAIN IN PLACE UNTIL THE SITE IS 90% REVEGETATED. REMOVE SILTATION FENCE, WITHIN 30 DAYS AFTER PERMANENT STABILIZATION IS ATTAINED. REMOVE ANY ACCUMULATED SEDIMENT AND STABILIZE.

2. HAY BALES PLACED AT KEY LOCATIONS TO SUPPLEMENT THE SILT FENCE.

D. SURROUND STOCKPILE SOIL WITH SILTATION FENCE AT BASE OF PILE.

3. PROTECT TEMPORARY STOCKPILES OF STUMPS, GRUBBINGS, OR COMMON EXCAVATION AS FOLLOWS: A. SOIL STOCKPILE SIDE SLOPES SHALL NOT EXCEED 2:1. B. AVOID PLACING TEMPORARY STOCKPILES IN AREAS WITH SLOPES OVER 10 PERCENT, OR NEAR DRAINAGE

SWALES. SEE ITEM 3 IN CONSTRUCTION PHASE NOTES BELOW. C. STABILIZE STOCKPILES WITHIN 15 DAYS BY TEMPORARILY SEEDING WITH A HYDROSEED METHOD CONTAINING AN EMULSIFIED MULCH TACKIFIER OR BY COVERING THE STOCKPILE WITH MULCH.

4. ALL DENUDED AREAS WHICH HAVE BEEN ROUGH GRADED AND ARE NOT LOCATED WITHIN THE BUILDING PAD, OR PARKING AND DRIVEWAY SUBBASE AREA THAT WILL NOT BE WORKED FOR MORE THAN 7 DAYS SHALL RECEIVE MULCH OR NON-ERODABLE COVER, STABILIZE AREAS WITHIN 75 FEET OF A WETLAND OR WATERBODY WITHIN 48 HOURS OF THE INITIAL DISTURBANCE OR THE SOIL OR PRIOR TO ANY STORM EVENT. WHICHEVER COMES FIRST. IN THE EVENT THE CONTRACTOR COMPLETES FINAL GRADING AND INSTALLATION OF LOAM AND SOD WITHIN THE TIME PERIODS PRESENTED ABOVE, INSTALLATION OF MULCH AND NETTING, WHERE APPLICABLE, IS NOT REQUIRED.

5. IF WORK IS CONDUCTED BETWEEN OCTOBER 15 AND APRIL 15, ALL DENUDED AREAS ARE TO BE COVERED WITH HAY MULCH, APPLIED AT TWICE THE NORMAL APPLICATION RATE, AND ANCHORED WITH FABRIC NETTING. THE PERIOD BETWEEN FINAL GRADING AND MULCHING SHALL BE REDUCED TO A 15 DAY MAXIMUM.

6. TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED ONCE THE SITE HAS BEEN STABILIZED OR IN AREAS WHERE PERMANENT EROSION CONTROL MEASURES HAVE BEEN INSTALLED.

PERMANENT EROSION CONTROL MEASURES:

THE FOLLOWING PERMANENT CONTROL MEASURES ARE REQUIRED BY THIS EROSION/SEDIMENTATION

1. ALL AREAS DISTURBED DURING CONSTRUCTION, BUT NOT SUBJECT TO OTHER RESTORATION (PAVING, RIPRAP, ETC.), WILL BE LOAMED, LIMED, FERTILIZED AND SEEDED. NATIVE TOPSOIL SHALL BE STOCKPILED AND REUSED FOR FINAL RESTORATION WHEN IT IS OF SUFFICIENT QUALITY.

2. IF AN AREAS WILL NOT BE WORKED FOR MORE THAN ONE YEAR OR HAS BEEN BROUGHT TO FINAL GRADE, THEN PERMANENTLY STABILIZE THE AREA WITHIN 7 DAYS BY PLANTING VEGETATION, SEEDING, SOD, OR THROUGH THE USE OF PERMANENT MULCH, OR RIPRAP, OR ROAD SUB-BASE. IF USING VEGETATION FOR STABILIZATION. SELECT THE PROPER VEGETATION FOR THE LIGHT. SOIL. AND MOISTURE CONDITIONS: AMEND AREAS OF DISTURBED SUBSOILS WITH TOPSOIL. COMPOST, OR FERTILIZERS: PROTECT SEEDED AREAS WITH MULCH OR, IF NECESSARY, EROSION CONTROL BLANKETS; AND SCHEDULE SODDING, PLANTING, AND SEEDING TO AVOID DIE-OFF FROM SUMMER DROUGHT AND FALL FROSTS. NEWLY SEEDED OR SODDED AREAS MUST BE PROTECTED FROM VEHICLE TRAFFIC, EXCESSIVE PEDESTRIAN TRAFFIC, AND CONCENTRATED RUNOFF UNTIL THE VEGETATION IS WELL ESTABLISHED. IF NECESSARY, AREAS MUST BE SEEDED AND MULCHED AGAIN IF GERMINATION IS SPARCE, PLANT COVERAGE IS SPOTTY, OR TOPSOIL EROSION IS EVIDENT. ONE OR MORE OF THE FOLLOWING MAY APPLY TO A PARTICULAR SITE.

(a) Seeded areas. For seeded areas, permanent stabilization means a 90% cover of healthy plants with no evidence of washing or rilling of the topsoil.

(b) Sodded areas. For sodded areas, permanent stabilization means the complete binding of the sod roots into the underlying soil with no slumping of the sod or die-off.

(c) Permanent Mulch. For mulched areas, permanent mulching means total coverage of the exposed area with an approved mulch material. Erosion control mix may be used as mulch for permanent stabilization according to the approved application rates and limitations.

(d) Riprap. For areas stabilized with riprap, permanent stabilization means that slopes stabilized with riprap have an appropriate backing of a well-graded gravel or approved geotextile to prevent soil movement from behind the riprap. Stone must be sized appropriately. It is recommended that angular stone be

(e) Agricultural use. For construction projects on land used for agricultural purposes (e.g., pipelines across crop land), permanent stabilization may be accomplished by returning the disturbed land to agricultural

(f) Paved areas. For paved areas, permanent stabilization means the placement of the compacted gravel subbase is completed.

(g) Ditches, channels, and swales. For open channels, permanent stabilization means the channel is stabilized with a 90% cover of healthy vegetation, with a well-graded riprap lining, or with another non-erosive lining such as concrete or asphalt pavement. There must be no evidence of slumping of the channel lining, undercutting of the channel banks, or down-cutting of the channel.

3. SLOPES GREATER THAN 2:1 WILL RECEIVE RIPRAP.

POST-CONSTRUCTION REVEGETATION:

THE FOLLOWING GENERAL PRACTICES WILL BE USED TO PREVENT EROSION AS SOON AS AN AREA IS READY

1. A MINIMUM OF 4" OF LOAM WILL BE SPREAD OVER DISTURBED AREAS AND GRADED TO A UNIFORM DEPTH AND NATURAL APPEARANCE, OR STONE WILL BE PLACED ON SLOPES TO STABILIZE SURFACES.

2. IF FINAL GRADING IS REACHED DURING THE NORMAL GROWING SEASON (4/15 TO 9/15), PERMANENT SEEDING WILL BE DONE AS SPECIFIED BELOW. PRIOR TO SEEDING, LIMESTONE SHALL BE APPLIED AT A RATE OF 138 LBS/1000 SQ. FT. AND 10:20:20 FERTILIZER AT A RATE OF 18.4 LBS/1000 SQ. FT WILL BE APPLIED. BROADCAST SEEDING AT THE FOLLOWING RATES:

IT MUST BE REMOVED PRIOR TO PLACEMENT OF SEED.

KENTUCKY BLUEGRASS 0.46 LBS/1000 SF. RED TOP 0.05 LBS/1000 SF CREEPING RED FESCUE 0.46 LBS/1000 SF. TALL FESCUE 0.46 LBS/1000 SF. PERENNIAL RYE GRASS 0.11 LB/1000 SF.

3. AN AREA SHALL BE MULCHED IMMEDIATELY AFTER IS HAS BEEN SEEDED. MULCHING SHALL CONSIST OF HAY MULCH. HYDRO-MULCH. JUTE NET OVER MULCH. PRE-MANUFACTURED EROSION MATS OR ANY

SUITABLE SUBSTITUTE DEEMED ACCEPTABLE BY THE DESIGNER. A. HAY MULCH SHALL BE APPLIED AT THE RATE OF 2 TONS PER ACRE. HAY MULCH SHALL BE SECURED BY EITHER: (NOTE: SOIL SHALL NOT BE VISIBLE)

I. BEING DRIVEN OVER BY TRACKED CONSTRUCTION EQUIPMENT ON GRADES OF 5% AND LESS. II. BLANKETED BY TACKED PHOTODEGRADABLE/BIODEGRADABLE NETTING, OR WITH SPRAY, ON GRADES

III. SEE NOTE 6, GENERAL NOTES, AND NOTE 8, WINTER CONSTRUCTION.

B. HYDRO-MULCH SHALL CONSIST OF A MIXTURE OF EITHER ASPHALT, WOOD FIBER OR PAPER FIBER AND

WATER SPRAYED OVER A SEEDED AREA. HYDRO-MULCH SHALL NOT BE USED BETWEEN 9/15 AND 4/15. 4. CONSTRUCTION SHALL BE PLANNED TO ELIMINATE THE NEED FOR SEEDING BETWEEN SEPTEMBER 15

AND APRIL 15. SHOULD SEEDING BE NECESSARY BETWEEN SEPTEMBER 15 AND APRIL 15 THE FOLLOWING PROCEDURE SHALL BE FOLLOWED. ALSO REFER TO NOTE 9 OF WINTER CONSTRUCTION.

A. ONLY UNFROZEN LOAM SHALL BE USED. B. LOAMING, SEEDING AND MULCHING WILL NOT BE DONE OVER SNOW OR ICE COVER. IF SNOW EXISTS,

C. WHERE PERMANENT SEEDING IS NECESSARY, ANNUAL WINTER RYE (1.2 LBS/1000 SQ.FT) SHALL BE ADDED TO THE PREVIOUSLY NOTED AREAS. D. WHERE TEMPORARY SEEDING IS REQUIRED, ANNUAL WINTER RYE (2.6 LBS/1000 SQ. FT.) SHALL BE

SOWN INSTEAD OF THE PREVIOUSLY NOTED SEEDING RATE. E. FERTILIZING, SEEDING AND MULCHING SHALL BE APPLIED TO LOAM THE DAY THE LOAM IS SPREAD BY

F. ALTERNATIVE HAY MULCH SHALL BE SECURED WITH PHOTODEGRADABLE/BIODEGRADABLE NETTING. TRACKING BY MACHINERY ALONE WILL NOT SUFFICE.

5. FOLLOWING FINAL SEEDING, THE SITE WILL BE INSPECTED EVERY 30 DAYS UNTIL 90% COVER HAS BEEN ESTABLISHED. RESEEDING WILL BE CARRIED OUT BY THE CONTRACTOR WITHIN 10 DAYS OF NOTIFICATION BY THE ENGINEER THAT THE EXISTING CATCH IS INADEQUATE.

MONITORING SCHEDULE:

THE CONTRACTOR IS RESPONSIBLE FOR INSTALLING, MONITORING, MAINTAINING, REPAIRING, REPLACING AND REMOVING ALL OF THE EROSION AND SEDIMENTATION CONTROLS OR APPOINTING A QUALIFIED SUBCONTRACTOR TO DO SO. MAINTENANCE MEASURES WILL BE APPLIED AS NEEDED DURING THE ENTIRE CONSTRUCTION CYCLE. AFTER EACH RAINFALL, A VISUAL INSPECTION WILL BE MADE OF ALL EROSION AND SEDIMENTATION CONTROLS AS FOLLOWS:

1. HAY BALE BARRIERS, SILT FENCE, AND STONE CHECK DAMS SHALL BE INSPECTED AND REPAIRED ONCE A WEEK OR IMMEDIATELY FOLLOWING ANY SIGNIFICANT RAINFALL. SEDIMENT TRAPPED BEHIND THESE BARRIERS SHALL BE EXCAVATED WHEN IT REACHES A DEPTH OF 6" AND REDISTRIBUTED TO AREAS UNDERGOING FINAL GRADING. SHOULD THE HAY BALE BARRIERS PROVE TO BE INEFFECTIVE, THE CONTRACTOR SHALL INSTALL SILT FENCE BEHIND THE HAY BALES.

2. VISUALLY INSPECT RIPRAP ONCE A WEEK OR AFTER EACH SIGNIFICANT RAINFALL AND REPAIR AS NEEDED. REMOVE SEDIMENT TRAPPED BEHIND THESE DEVICES ONCE IT ATTAINS A DEPTH EQUAL TO 1/2 THE HEIGHT OF THE DAM OR RISER. DISTRIBUTE REMOVED SEDIMENT OFF-SITE OR TO AN AREA UNDERGOING FINAL GRADING.

3. REVEGETATION OF DISTURBED AREAS WITHIN 25' OF DRAINAGE-COURSE/STREAM WILL BE SEEDED WITH THE "MEADOW AREA MIX" AND INSPECTED ON A WEEKLY BASIS OR AFTER EACH SIGNIFICANT RAINFALL AND RESEEDED AS NEEDED. EXPOSED AREAS WILL BE RESEEDED AS NEEDED UNTIL THE AREA HAS OBTAINED 100% GROWTH RATE. PROVIDE PERMANENT RIPRAP FOR SLOPES IN EXCESS OF 3:1 AND WITHIN 25' OF DRAINAGE COURSE.

EROSION CONTROL DURING WINTER CONSTRUCTION: 1. WINTER CONSTRUCTION PERIOD: NOVEMBER 1 THROUGH APRIL 15.

2. WINTER EXCAVATION AND EARTHWORK SHALL BE COMPLETED SUCH THAT NO MORE THAN 1 ACRE OF THE SITE IS WITHOUT STABILIZATION AT ANY ONE TIME.

3. EXPOSED AREA SHALL BE LIMITED TO THOSE AREAS TO BE MULCHED IN ONE DAY PRIOR TO ANY SNOW EVENT. AT THE END OF EACH WORK WEEK NO AREAS MAY BE LEFT UNSTABILIZED OVER THE

4. CONTINUATION OF EARTHWORK OPERATIONS ON ADDITIONAL AREAS SHALL NOT BEGIN UNTIL THE EXPOSED SOIL SURFACE ON THE AREA BEING WORKED HAS BEEN STABILIZED, SUCH THAT NO LARGER AREA OF THE SITE IS WITHOUT EROSION CONTROL PROTECTION AS LISTED IN ITEM 2 ABOVE.

5. AN AREA SHALL BE CONSIDERED TO HAVE BEEN STABILIZED WHEN EXPOSED SURFACES HAVE BEEN EITHER MULCHED WITH STRAW OR HAY AT A RATE OF 150 LB. PER 1000 S.F. (WITH OR WITHOUT SEEDING) OR DORMANT SEEDED, MULCHED AND ANCHORED SUCH THAT SOIL SURFACE IS NOT VISIBLE THROUGH THE MULCH. NOTE: AN AREA IS ALSO CONSIDERED STABLE IF SODDED, COVERED WITH GRAVEL (PARKING LOTS) OR STRUCTURAL SAND.

6. BETWEEN THE DATES OF OCTOBER 15 AND APRIL 1, LOAM OR SEED WILL NOT BE REQUIRED. DURING PERIODS OF ABOVE FREEZING TEMPERATURES THE SLOPES SHALL BE FINE GRADED AND EITHER PROTECTED WITH MULCH OR TEMPORARILY SEEDED AND MULCHED UNTIL SUCH TIME AS THE FINAL TREATMENT CAN BE APPLIED. IF THE DATE IS AFTER NOVEMBER 1 AND IF THE EXPOSED AREA HAS BEEN LOAMED, FINAL GRADED WITH A UNIFORM SURFACE, THEN THE AREA MAY BE DORMANT SEEDED AT A RATE OF 3 TIMES HIGHER THAN SPECIFIED FOR PERMANENT SEED AND THEN MULCHED. IF CONSTRUCTION CONTINUES DURING FREEZING WEATHER, ALL EXPOSED AREAS SHALL BE CONTINUOUSLY GRADED BEFORE FREEZING AND THE SURFACE TEMPORARILY PROTECTED FROM EROSION BY THE APPLICATION OF MULCH. SLOPES SHALL NOT BE LEFT UNEXPOSED OVER THE WINTER OR ANY OTHER EXTENDED TIME OF WORK SUSPENSION UNLESS TREATED IN THE ABOVE MANNER. UNTIL SUCH TIME AS WEATHER CONDITIONS ALLOW, DITCHES TO BE FINISHED WITH THE PERMANENT SURFACE TREATMENT, EROSION SHALL BE CONTROLLED BY THE INSTALLATION OF BALES OF HAY, SILT FENCE OR STONE CHECK DAMS IN ACCORDANCE WITH THE STANDARD DETAILS SHOWN ON THE DESIGN DRAWINGS. NOTE: DORMANT SEEDING SHOULD NOT BE ATTEMPTED UNLESS SOIL TEMPERATURE REMAINS BELOW 50 DEGREES AND DAY TIME TEMPERATURES REMAIN IN THE 30'S.

7. MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL DRAINAGE WAYS WITH A SLOPE GREATER THAN 3% FOR SLOPES EXPOSED TO DIRECT WINDS AND FOR ALL OTHER SLOPES GREATER THAN 8%. VEGETATED DRAINAGE SWALES SHALL BE LINED WITH EXCELSIOR OR CURLEX.

8. MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL DRAINAGE WAYS WITH SLOPES GREATER THAN 15%. AFTER OCTOBER 1 THE SAME APPLIES FOR ALL SLOPES GREATER THAN 8%.

9. BETWEEN THE DATES OF OCTOBER 15 TO NOVEMBER 1, WINTER RYE IS RECOMMENDED FOR STABILIZATION. AFTER NOVEMBER 1, WINTER RYE IS NOT EFFECTIVE. AROUND NOVEMBER 15 OR LATER, ONCE TEMPERATURES OF THE AIR AND SOIL PERMIT, DORMANT SEEDING IS EFFECTIVE.

10. IN THE EVENT OF SNOWFALL (FRESH OR CUMULATIVE) GREATER THAN 1 INCH DURING WINTER CONSTRUCTION PERIOD ALL SNOW SHALL BE REMOVED FROM THE AREAS OF SEEDING AND MULCHING PRIOR TO PLACEMENT.

Construction Plan

FOLLOWING:

CONSTRUCTION OF THE PROJECT IS EXPECTED TO COMMENCE IN LATE SUMMER 2017 FOLLOWING ISSUE OF TOWN AND DEP PERMITS AND ONCE UNITS ARE PRE-SOLD. THE CONSTRUCTION OF THE ROAD AND LITHLITY INFRASTRUCTURE IS EXPECTED TO CONTINUE INTO THE SPRING OF 2018. CONSTRUCTION OF UNITS WILL DEPEND ON MARKET CONDITIONS BUT BASED ON THE RECENT SUCCESS WE WOULD EXPECT THE UNITS TO BE CONSTRUCTED WITHIN 2-3 YEARS. CONSTRUCTION SEQUENCING WILL INCLUDE THE

 TREE CLEARING AND STUMP REMOVAL. • REMOVAL OF THE THREE HOUSES AND ASSOCIATED DRIVES AND INFRASTRUCTURE.

 ROUGH GRADING, SITE BLASTING FOR ROADWAYS AND UNITS AND INSTALLATION OF UTILITIES AND STORMWATER SYSTEMS.

 FINISH GRAVELS AND SURFACES & PAVING LOAM, SEED AND STABILIZATION.

RAP APRONS SHALL BE INSTALLED, AS SHOWN ON THE PLANS.

CONSTRUCTION PHASE:

THE FOLLOWING GENERAL PRACTICES WILL BE USED TO PREVENT EROSION DURING CONSTRUCTION OF THIS

1. ONLY THOSE AREAS UNDER ACTIVE CONSTRUCTION WILL BE CLEARED AND LEFT IN AN UNTREATED OR UNVEGETATED CONDITION. IF FINAL GRADING, LOAMING AND SEEDING WILL NOT OCCUR WITHIN 7 DAYS, SEE

2. PRIOR TO THE START OF CONSTRUCTION IN A SPECIFIC AREA, SILT FENCING AND/OR HAY BALES WILL BE INSTALLED AT THE TOE OF SLOPE AND IN AREAS AS LOCATED ON THE PLANS TO PROTECT AGAINST ANY CONSTRUCTION RELATED EROSION. IMMEDIATELY FOLLOWING CONSTRUCTION OF CULVERTS AND SWALES, RIP

3. TOPSOIL WILL BE STOCKPILED WHEN NECESSARY IN AREAS WHICH HAVE MINIMUM POTENTIAL FOR EROSION AND WILL BE KEPT AS FAR AS POSSIBLE FROM THE EXISTING DRAINAGE COURSE. NO STOCKPILE SHALL BE CLOSER THEN 100' OF A RESOURCE INCLUDING, BUT NOT LIMITED TO, WETLANDS, STREAMS, AND OPEN WATER BODIES. ALL STOCKPILES SHALL HAVE A SILTATION FENCE BELOW THEM REGARDLESS OF TIME OF PRESENCE. ALL STOCKPILES EXPECTED TO REMAIN LONGER THAN 15 DAYS SHALL BE:

A. TREATED WITH ANCHORED MULCH (WITHIN 5 DAYS OF THE LAST DEPOSIT OF STOCKPILED SOIL). B. SEEDED WITH CONSERVATION MIX AND MULCHED IMMEDIATELY.

C. INSTALL SILT FENCE AROUND STOCKPILE AT BASE OF PILE. STOCKPILES TO HAVE SILT FENCE INSTALLED AT TIME OF ESTABLISHMENT AT BASE OF PILE.

4. ALL DISTURBED AREAS THAT WILL NOT BE WORKED FOR MORE THAN 7 DAYS SHALL BE EITHER: A. TREATED WITH ANCHORED MULCH IMMEDIATELY, OR B. SEEDED WITH CONSERVATION MIX OF ANNUAL RYE GRASS (0.9 LBS/1000 SQ. FT) AND MULCHED

5. ALL GRADING WILL BE HELD TO A MAXIMUM 2:1 SLOPE WHERE PRACTICAL. ALL SLOPES WILL BE STABILIZED WITH PERMANENT SEEDING, OR WITH STONE, WITHIN 7 DAYS AFTER FINAL GRADING IS COMPLETE. (SEE POST-CONSTRUCTION REVEGETATION FOR SEEDING SPECIFICATION.)

6. ALL CULVERTS WILL BE PROTECTED WITH STONE RIPRAP (D50 = 6" UNLESS OTHERWISE SPECIFIED) AT INLETS AND OUTLETS.

Maine DEP Chapter 500, APPENDIX C. Housekeeping

IMMEDIATELY.

These performance standards apply to all projects except for stormwater PBR projects.

1. Spill prevention. Controls must be used to prevent pollutants from construction and waste materials stored on site to enter stormwater, which includes storage practices to minimize exposure of the materials to stormwater. The site contractor or operator must develop, and implement as necessary, appropriate spill prevention, containment, and response planning measures.

NOTE: Any spill or release of toxic or hazardous substances must be reported to the Department. For oil spills, call 1-800-482-0777 which is available 24 hours a day. For spills of toxic or hazardous material, call 1-800-452-4664 which is available 24 hours a day. For more information, visit the Department's website at: http://www.maine.gov/dep/spills/emergspillresp/

2. Groundwater protection. During construction, liquid petroleum products and other hazardous materials with the potential to contaminate groundwater may not be stored or handled in areas of the site draining to an infiltration area. An "infiltration area" is any area of the site that by design or as a result of soils, topography and other relevant factors accumulates runoff that infiltrates into the soil. Dikes, berms, sumps, and other forms of secondary containment that prevent discharge to groundwater may be used to isolate portions of the site for the purposes of storage and handling of these materials. Any project proposing infiltration of stormwater must provide adequate pre-treatment of stormwater prior to discharge of stormwater to the infiltration area, or provide for treatment within the infiltration area, in order to prevent the accumulation of fines, reduction in infiltration rate, and consequent flooding and

See Appendix D for license by rule standards for infiltration of stormwater.

These materials must be prevented from becoming a pollutant source.

NOTE: Lack of appropriate pollutant removal best management practices (BMPs) may result in violations of the groundwater quality standard established by 38 M.R.S.A. §465-C(1).

3. Fugitive sediment and dust. Actions must be taken to ensure that activities do not result in noticeable erosion of soils or fugitive dust emissions during or after construction. Oil may not be used for dust control, but other water additives may be considered as needed. A stabilized construction entrance (SCE) should be included to minimize tracking of mud and sediment. If off-site tracking occurs, public roads should be swept immediately and no less than once a week and prior to significant storm events. Operations during dry months, that experience fugitive dust problems, should wet down aved access roads once a week or more frequently as needed with a water additive to suppress fugitive sediment

NOTE: Dewatering a stream without a permit from the Department may violate state water quality standards and the Natural Resources Protection Act

4. Debris and other materials. Minimize the exposure of construction debris, building and landscaping materials, trash, fertilizers, pesticides, herbicides, detergents, sanitary waste and other materials to precipitation and stormwater runoff.

NOTE: To prevent these materials from becoming a source of pollutants, construction and post-construction activities related to a project may be required to comply with applicable provision of rules related to solid, universal, and hazardous waste, including, but not limited to, the Maine solid waste and hazardous waste management rules; Maine hazardous waste management rules; Maine oil conveyance and storage rules; and Maine pesticide requirements

5. Excavation de-watering. Excavation de-watering is the removal of water from trenches, foundations, coffer dams, ponds and other areas within the construction area that retain water after excavation. In most cases the collected water is neavily silted and hinders correct and safe construction practices. The collected water removed from the ponded area, either through gravity or pumping, must be spread through natural wooded buffers or removed to areas that are specifically designed to collect the maximum amount of sediment possible, like a cofferdam sedimentation basin. Avoid allowing the water to flow over disturbed areas of the site. Equivalent measures may be taken if approved by the

NOTE: Dewatering controls are discussed in the "Maine Erosion and Sediment Control BMPs, Maine Department of

6. Authorized Non-stormwater discharges. Identify and prevent contamination by non-stormwater discharges. Where allowed non-stormwater discharges exist, they must be identified and steps should be taken to ensure the mplementation of appropriate pollution prevention measures for the non-stormwater component(s) of the discharge Authorized non-stormwater discharges are:

(a) Discharges from firefighting activity;

(b) Fire hydrant flushings:

(c) Vehicle washwater if detergents are not used and washing is limited to the exterior of vehicles (engine, undercarriage and transmission washing is prohibited

(d) Dust control runoff in accordance with permit conditions and Appendix (C)(3):

(e) Routine external building washdown, not including surface paint removal, that does not involve detergents; (f)Pavement washwater (where spills/leaks of toxic or hazardous materials have not occurred, unless all spilled material

(g) Uncontaminated air conditioning or compressor condensate;

(h) Uncontaminated groundwater or spring wate

had been removed) if detergents are not used

(i) Foundation or footer drain-water where flows are not contaminated (j) Uncontaminated excavation dewatering (see requirements in Appendix C(5));

(k) Potable water sources including waterline flushings; and

7. Unauthorized non-stormwater discharges . The Department's approval under this Chapter does not authorize a discharge that is mixed with a source of non stormwater, other than those discharges in compliance with Appendix C (6). Specifically, the Department's approval does not authorize discharges of the following:

(a) Wastewater from the washout or cleanout of concrete, stucco, paint, form release oils, curing compounds or other construction materials;

(b) Fuels, oils or other pollutants used in vehicle and equipment operation and maintenance;

(c) Soaps, solvents, or detergents used in vehicle and equipment washing; and Toxic or hazardous substances from a spill or other release.

(8) Additional requirements. Additional requirements may be applied on a site-specific basis.

Maine DEP Chapter 500, APPENDIX A. Erosion and sedimentation control (2015 Update)

Control BMPs Maine Department of Environmental Protection.'

apply to a particular site.

rates and limitations.

appropriately. It is recommended that angular stone be used.

released from this standard by the Department.

A person who conducts, or causes to be conducted, an activity that involves filling, displacing or exposing soil or other earthen materials shall take measures to prevent unreasonable erosion of soil or sediment beyond the project site or into a protected natural resource as defined in 38 M.R.S. §480-B. Erosion control measures must be in place before the activity begins. Measures must remain in place and functional until the site is permanently stabilized. Adequate and timely temporary and permanent

NOTE: Other requirements may apply, including, but not limited to the Natural Resources Protection Act 38 M.R.S. §480-B. NOTE: The Department has prepared protocols for the control of erosion and sedimentation. See "Maine Erosion and Sediment

1. Pollution prevention. Minimize disturbed areas and protect natural downgradient buffer areas to the extent practicable. Control stormwater volume and velocity within the site to minimize soil erosion. Minimize the disturbance of steep slopes. Control stormwater discharges, including both peak flow rates and volume, to minimize erosion at outlets. The discharge may not result in erosion of any open drainage channels, swales, stream channels or stream banks, upland, or coastal or freshwater wetlands off

Whenever practicable, no disturbance activities should take place within 50 feet of any protected natural resource. If disturbance activities take place between 30 feet and 50 feet of any protected natural resource, and stormwater discharges through the disturbed areas toward the protected natural resource, perimeter erosion controls must be doubled. If disturbance activities take place less than 30 feet from any protected natural resource, and stormwater discharges through the disturbed areas toward the protected natural resource, perimeter erosion controls must be doubled and disturbed areas must be temporarily or permanently stabilized within 7 days.

NOTE: Buffers improve water quality by helping to filter pollutants in run-off both during and after construction. Minimizing disturbed areas through phasing limits the amount of exposed soil on the site through retention of natural cover and by retiring areas as permanently stabilized. Less exposed soil results in fewer erosion controls to install and maintain. If work within an area is not anticipated to begin within two weeks' time, consider leaving the area in its naturally existing cover.

NOTE: Many construction activities within 75 feet of a protected natural resource require a permit under the Natural Resources Protection Act prior to initiation. For more information regarding the applicability of the NRPA to your project, you can visit the Department's website at http://www.maine.gov/dep/land/nrpa/index.html or contact staff of the Division of Land Resource Regulation at the nearest regional office

2. Sediment barriers. Prior to construction, properly install sediment barriers at the downgradient edge of any area to be disturbed and adjacent to any drainage channels within the disturbed area. Sediment barriers should be installed downgradient of soil or sediment stockpiles and stormwater prevented from running onto the stockpile. Maintain the sediment barriers by removing accumulated sediment, or removing and replacing the barrier, until the disturbed area is permanently stabilized. Where a discharge to a storm drain inlet occurs, if the storm drain carries water directly to a surface water and you have authority to access the storm drain inlet, you must install and maintain protection measures that remove sediment from the discharge.

3. Stabilized construction entrance. Prior to construction, properly install a stabilized construction entrance (SCE) at all points of egress from the site. The SCE is a stabilized pad of aggregate, underlain by a geotextile filter fabric, used to prevent traffic from tracking material away from the site onto public ROWs. Maintain the SCE until all disturbed areas are stabilized.

4. Temporary stabilization. Within 7 days of the cessation of construction activities in an area that will not be worked for more than 7 days, stabilize any exposed soil with mulch, or other non-erodible cover. Stabilize areas within 75 feet of a wetland or waterbody within 48 hours of the initial disturbance of the soil or prior to any storm event, whichever comes first.

5. Removal of temporary measures. Remove any temporary control measures, such as silt fence, within 30 days after permanent stabilization is attained. Remove any accumulated sediments and stabilize.

NOTE: It is recommended that silt fences be removed by cutting the fence materials at ground level to avoid additional soil

6. Permanent stabilization. If the area will not be worked for more than one year or has been brought to final grade, then permanently stabilize the area within 7 days by planting vegetation, seeding, sod, or through the use of permanent mulch, or riprap, or road sub-base. If using vegetation for stabilization, select the proper vegetation for the light, moisture, and soil conditions; amend areas of disturbed subsoils with topsoil, compost, or fertilizers; protect seeded areas with mulch or, if $necessary, erosion \ control\ blankets; \ and\ schedule\ sodding,\ planting,\ and\ seeding\ so\ to\ avoid\ die-off\ from\ summer\ drought\ and$ fall frosts. Newly seeded or sodded areas must be protected from vehicle traffic, excessive pedestrian traffic, and concentrated runoff until the vegetation is well-established with 90% cover by healthy vegetation. If necessary, areas must be reworked and

(a) Seeded areas. For seeded areas, permanent stabilization means a 90% cover of the disturbed area with mature, healthy plants with no evidence of washing or rilling of the topsoil.

restabilized if germination is sparse, plant coverage is spotty, or topsoil erosion is evident. One or more of the following may

(b) Sodded areas. For sodded areas, permanent stabilization means the complete binding of the sod roots into the underlying soil

(c) Permanent Mulch. For mulched areas, permanent mulching means total coverage of the exposed area with an approved mulch material. Erosion Control Mix may be used as mulch for permanent stabilization according to the approved application

(d) Riprap. For areas stabilized with riprap, permanent stabilization means that slopes stabilized with riprap have an appropriate backing of a well-graded gravel or approved geotextile to prevent soil movement from behind the riprap. Stone must be sized

(e) Agricultural use. For construction projects on land used for agricultural purposes (e.g., pipelines across crop land), permanent stabilization may be accomplished by returning the disturbed land to agricultural use.

(f)Paved areas. For paved areas, permanent stabilization means the placement of the compacted gravel subbase is completed,

provided it is free of fine materials that may runoff with a rain event (g) Ditches, channels, and swales. For open channels, permanent stabilization means the channel is stabilized with a 90% cover of healthy vegetation, with a well-graded riprap lining, turf reinforcement mat, or with another non-erosive lining such as concrete or asphalt pavement. There must be no evidence of slumping of the channel lining, undercutting of the channel banks,

7. Winter Construction. "Winter construction" is construction activity performed during the period from November 1 through April 15. If disturbed areas are not stabilized with permanent measi ures by November 1 or new soil disturbance occurs after Novembe 1, but before April 15, then these areas must be protected and runoff from them must be controlled by additional measures and

of each construction day, areas that have been brought to final grade must be stabilized. Mulch may not be spread on top of (b) Sediment Barriers. All areas within 75 feet of a protected natural resource must be protected with a double row of sediment

(a) Site Stabilization. For winter stabilization, hay mulch is applied at twice the standard temporary stabilization rate. At the end

(c) Ditch. All vegetated ditch lines that have not been stabilized by November 1, or will be worked during the winter construction period, must be stabilized with an appropriate stone lining backed by an appropriate gravel bed or geotextile unless specifically

(d) Slopes. Mulch netting must be used to anchor mulch on all slopes greater than 8% unless erosion control blankets or erosion control mix is being used on these slopes

NOTE: The Department has prepared protocols for the control of erosion and sedimentation during the winter

months. See "Maine Erosion and Sediment Control BMPs Maine Department of Environmental Protection 8. Stormwater channels. Ditches, swales, and other open stormwater channels must be designed, constructed, and stabilized using measures that achieve long-term erosion control. Ditches, swales and other open stormwater channels must be sized to handle, at a minimum, the expected volume run-off. Each channel should be constructed in sections so that the section's grading, shaping, and installation of the permanent lining can be completed the same day. If a channel's final grading or lining installation must be delayed, then diversion berms must be used to divert stormwater away from the channel, properly-spaced check dams must be installed in the channel to slow the water velocity, and a temporary lining installed along the channel to prevent

scouring. Permanent stabilization for channels is addressed under Appendix A(5)(g) above. (a) The channel should receive adequate routine maintenance to maintain capacity and prevent or correct any erosion of the

channel's bottom or side slopes. (b) When the watershed draining to a ditch or swale is less than 1 acre of total drainage and less than ¼ acre of impervious area,

diversion of runoff to adjacent wooded or otherwise vegetated buffer areas is encouraged where the opportunity exists. 9. Sediment basins. Sediment basins must be designed to provide storage for either the calculated runoff from a 2-year, 24-hour storm or provide for 3,600 cubic feet of capacity per acre draining to the basin. Outlet structures must discharge water from the surface of the basin whenever possible. Erosion controls and velocity dissipation devices must be used if the discharging waters are likely to create erosion. Accumulated sediment must be removed as needed from the basin to maintain at least ½ of the

design capacity of the basin. The use of cationic treatment chemicals, such as polymers, flocculants, or other chemicals that contain an overall positive charge designed to reduce turbidity in stormwater must receive prior approval from the Department. When requesting approval to use cationic treatment chemicals, you must describe appropriate controls and implementation procedures to ensure the use will not lead to a violation of water quality standards. In addition, you must specify the type(s) of soil likely to be treated on the site, chemicals to be used and how they are to be applied and in what quantity, any manufacturer's recommendations, and any

training had by personnel who will handle and apply the chemicals. 10. Roads. Gravel and paved roads must be designed and constructed with crowns or other measures, such as water bars, to ensure that stormwater is delivered immediately to adjacent stable ditches, vegetated buffer areas, catch basin inlets, or street

NOTE: (1) Gravel and paved roads should be maintained so that they continue to conform to this standard in order to prevent erosion problems. (2) The Department recommends that impervious surfaces, including roads, be designed and constructed so that stormwater is distributed in sheet flow to natural vegetated buffer areas wherever such areas are available. Road ditches should be designed so that stormwater is frequently (at least every 100 to 200 feet) discharged via ditch turnouts in sheet flow to adjacent natural buffer areas wherever possible. 11. Culverts. Culverts must be sized to avoid unintended flooding of upstream areas or frequent overtopping of roadways.

least as high as the expected maximum elevation of storage behind the culvert. Culvert outlet design must incorporate measures, such as aprons, to prevent scour of the stream channel. Outlet protection measures must be designed to stay within the channel limits. The design must take account of tailwater depth. 12. Parking areas. Parking areas must be constructed to ensure runoff is delivered to adjacent swales, catch basins, curb gutters, or buffer areas without eroding areas downslope. The parking area's subbase compaction and grading must be done to ensure

Culvert inlets must be protected with appropriate materials for the expected entrance velocity, and protection must extend at

runoff is evenly distributed to adjacent buffers or side slopes. Catch basins must be located and set to provide enough storage

depth at the inlet to allow inflow of peak runoff rates without by-pass of runoff to other areas. 13. Additional requirements. Additional requirements may be applied on a site-specific basis.

Maine DEP Chapter 500, APPENDIX B. Inspection and maintenance (2015 Update)

This appendix applies to all projects, except that a project that is eligible for stormwater PBR need only meet the standards in Section 1.

See Appendix D(5) for additional maintenance requirements related to infiltration of stormwater

1. During construction. The following standards must be met during construction.

(a) Inspection and corrective action. Inspect disturbed and impervious areas, erosion control measures, materials storage areas that are exposed to precipitation, and locations where vehicles enter or exit the site. Inspect these areas at least once a week as well as before and within 24 hours after a storm event (rainfall), and prior to completing permanent stabilization measures. A person with knowledge of erosion and stormwater control, including the standards and conditions in the permit, shall conduct the inspections

(b) Maintenance. If best management practices (BMPs) need to be repaired, the repair work should be initiated upon discovery of the problem but no later than the end of the next workday. If additional BMPs or significant repair of BMPs are necessary, implementation must be completed within 7 calendar days and prior to any storm event (rainfall). All measures must be maintained in effective operating condition until areas are permanently stabilized

(c) Documentation. Keep a log (report) summarizing the inspections and any corrective action taken. The log must include the name(s) and qualifications of the person making the inspections, the date(s) of the inspections, and major observations about the operation and naintenance of erosion and sedimentation controls, materials storage areas, and vehicles access points to the parcel. Major observations must include BMPs that need maintenance, BMPs that failed to operate as designed or proved inadequate for a particular location, and location(s) where additional BMPs are needed. For each BMP requiring maintenance, BMP needing replacement, and location needing additional BMPs, note in the log the corrective action taken and when it was taken.

The log must be made accessible to Department staff and a copy must be provided upon request. The permittee shall retain a copy of the log for a period of at least three years from the completion of permanent stabilization.

. Post-construction. The following standards must be met after construction.

(a) Plan. Carry out an approved inspection and maintenance plan that is consistent with the minimum requirements of this section. The plan must address inspection and maintenance of the project's permanent erosion control measures and stormwater management system. This plan may be combined with the plan listed in Section 2(a) of this appendix. See Section 7(C)(2) for submission requirements.

(b) Inspection and maintenance. All measures must be maintained in effective operating condition. A person with knowledge of erosion and stormwater control, including the standards and conditions in the permit, shall conduct the inspections. The following areas, facilities, and neasures must be inspected and identified deficiencies must be corrected. Areas, facilities, and measures other than those listed below may also require inspection on a specific site. Inspection or maintenance tasks other than those discussed below must be included in the maintenance plan developed for a specific site.

NOTE: Expanded and more-detailed descriptions for specific maintenance tasks may be found in the Maine DEP's "Stormwater Management for Maine: Best Management Practices."

(i) Inspect vegetated areas, particularly slopes and embankments, early in the growing season or after heavy rains to identify active or potential rosion problems. Replant bare areas or areas with sparse growth. Where rill erosion is evident, armor the area with an appropriate lining or divert the erosive flows to on-site areas able to withstand the concentrated flows. See permanent stabilization standards in Appendix A(5).

Inspect ditches, swales and other open stormwater channels in the spring, in late fall, and after heavy rains to remove any obstructions to flow, remove accumulated sediments and debris, to control vegetated growth that could obstruct flow, and to repair any erosion of the ditch lining. Vegetated ditches must be mowed at least annually or otherwise maintained to control the growth of woody vegetation and maintain flow capacity. Any woody vegetation growing through riprap linings must also be removed. Repair any slumping side slopes as soon as practicable. If the ditch has a riprap lining, replace riprap on areas where any underlying filter fabric or underdrain gravel is howing through the stone or where stones have dislodged. The channel must receive adequate routine maintenance to maintain capacity and prevent or correct any erosion of the channel's bottom or sideslope

(iii) Inspect culverts in the spring, in late fall, and after heavy rains to remove any obstructions to flow; remove accumulated sediments and

debris at the inlet, at the outlet, and within the conduit; and to repair any erosion damage at the culvert's inlet and outlet.

(iv) Inspect and clean out catch basins. Clean-out must include the removal and legal disposal of any accumulated sediments and debris at the bottom of the basin, at any inlet grates, at any inflow channels to the basin, and at any pipes between basins. If the basin outlet is designed to trap floatable materials, then remove the floating debris and any floating oils (using oil-absorptive pads). (v) Inspect resource and treatment buffers once a year for evidence of erosion, concentrating flow, and encroachment by development. If flows are concentrating within a buffer, site grading, level spreaders, or ditch turn-outs must be used to ensure a more even distribution of flow into a buffer. Check down slope of all spreaders and turn-outs for erosion. If erosion is present, adjust or modify the spreader's or turnout's

lip to ensure a better distribution of flow into a buffer. Clean-out any accumulation of sediment within the spreader bays or turn-out pools.

(vi) Inspect at least once per year, each stormwater management pond or basin, including the pond's embankments, outlet structure, and

(vii)Inspect at least one per year, each underdrained filter, including the filter embankments, vegetation, underdrain piping, and overflow spillway. Remove and dispose of accumulated sediments in the filter. If needed, rehabilitate any clogged surface linings, and flush underdrain

emergency spillway. Remove and dispose of accumulated sediments in the pond. Control woody vegetation on the pond's embankments.

(viii)Inspect each manufactured system installed on the site, including the system's inlet, treatment chamber(s), and outlet at least once per year, or in accordance with the maintenance guidelines recommended by the manufacturer based on the estimated runoff and pollutant load expected to the system from the project. Remove and dispose of accumulated sediments, debris, and contaminated waters from the system and, if applicable, remove and replace any clogged or spent filter media.

(i) Clear accumulations of winter sand in parking lots and along roadways at least once a year, preferably in the spring. Accumulations on pavement may be removed by pavement sweeping. Accumulations of sand along road shoulders may be removed by grading excess sand to the pavement edge and removing it manually or by a front-end loader. Grading of gravel roads, or grading of the gravel shoulders of gravel or paved roads, must be routinely performed to ensure that stormwater drains immediately off the road surface to adjacent buffer areas or stable ditches, and is not impeded by accumulations of graded material on the road shoulder or by excavation of false ditches in the shoulder If water bars or open-top culverts are used to divert runoff from road surfaces, clean-out any sediments within or at the outlet of these

(ii) Manage each buffer's vegetation consistently with the requirements in any deed restrictions for the buffer. Wooded buffers must remain ully wooded and have no disturbance to the duff layer. Vegetation in non-wooded buffers may not be cut more than three times per year, and may not be cut shorter than six inches.

NOTE: Contact the Department's Division of Watershed Management (Maine DEP) for assistance developing inspection and maintenance requirements for other drainage control and runoff treatment measures installed on the site. The maintenance needs for most measures may be found in the Maine DEP's "Stormwater Management for Maine: Best Management Practices."

(d) Documentation. Keep a log (report) summarizing inspections, maintenance, and any corrective actions taken. The log must include the date on which each inspection or maintenance task was performed, a description of the inspection findings or maintenance completed, and the name of the inspector or maintenance personnel performing the task. If a maintenance task requires the clean-out of any sediments or debris, indicate where the sediment and debris was disposed after removal. The log must be made accessible to Department staff and a copy provided to the Department upon request. The permittee shall retain a copy of the log for a period of at least five years from the completion

3. Re-certification. Submit a certification of the following to the Department within three months of the expiration of each five-year interval from the date of issuance of the permit

(b) Inspection and repair of stormwater control system. All aspects of the stormwater control system have been inspected for damage, wear, and malfunction, and appropriate steps have been taken to repair or replace the system, or portions of the system

(c) Maintenance. The erosion and stormwater maintenance plan for the site is being implemented as written, or modifications to the plan have

(a) Identification and repair of erosion problems. All areas of the project site have been inspected for areas of erosion, and appropriate steps

Municipalities with separate storm sewer systems regulated under the Maine Pollutant Discharge Elimination System (MPDES) Program may report on all regulated systems under their control as part of their required annual reporting in lieu of separate certification of each system Municipalities not regulated by the MPDES Program, but that are responsible for maintenance of permitted stormwater systems, may report on multiple stormwater systems in one report.

4. Duration of maintenance. Perform maintenance as described and required in the permit unless and until the system is formally accepted by the

maintenance of the system. If a municipality or quasi-municipal district chooses to accept a stormwater management system, or a componen

the components of the system for which the municipality or district will assume responsibility, and that the municipality or district agrees to

of a stormwater system, it must provide a letter to the Department stating that it assumes responsibility for the system. The letter must specify

maintain those components of the system in compliance with Department standards. Upon such assumption of responsibility, and approval by

municipality or quasi-municipal district, or is placed under the jurisdiction of a legally created association that will be responsible for the


the Department, the municipality, quasi-municipal district, or association becomes a co-permittee for this purpose only and must comply with all terms and conditions of the permit.

5. Additional requirements. Additional requirements may be applied on a site-specific basis.

been submitted to and approved by the Department, and the maintenance log is being maintaine

Respond to Town Memos, Re-submit to Town SUBMIT TO DEP Re-Submit to Town and Maine DEP

Erosion Control Notes





SHEET:


CSB


JOB #: 109 SS: FILE:


DATE: 3-1-20187

 RESIDENTIAL SUBDIVISIONS TOWN AND STATE APPROVA SITE PLANNING & DESIGN ENGINEERING: STORMWATER MANAGEMEN ROAD AND UTILITY DESIGN FROSION CONTROL BLANK CONSULTING ENGINEERS Email: cbelanger@roadrunner.com 63 Second Avenue, Augusta, Maine 04330 Ph 207-622-1462, Cell 207-242-5713 SCALE:


Oceanview at Cumberland 291 Tuttle Road, Cumberland, Maine Seacoast Management Company 20 Blueberry Lane, Falmouth, Maine













-3" GALVANIZED ANGLE

IRON TO BE USED AS

BRACE FOR AIR RELEASE VALVE (2 TOTAL)





Oceanview at Cumberland 291 Tuttle Road, Cumberland, Maine

Seacoast Management Company 20 Blueberry Lane, Falmouth, Maine

ENGINEERING STORMWATER MANAGEMEN ROAD AND UTILITY DESIGN EROSION CONTROL PLANS

CHRISTOPHER


BELANGER

9098

SONAL

 RESIDENTIAL SUBDIVISIONS TOWN AND STATE APPROVAL SITE PLANNING & DESIGN CONSULTING ENGINEERS Email: cbelanger@roadrunner.com

63 Second Avenue , Augusta, Maine 04330 Ph 207-622-1462, Cell 207-242-5713 SHEET: FIELD WK: SCALE: DRN BY: JOB #: 109 SS: CH'D BY: FILE: DATE: 3-1-2018



3. SEE PLANS FOR LOCATIONS OF DRAINBOARD AND PERIMETER DRAINS.

TRENCH WIDTH

TRENCH REPAIR

BITUMINOUS CONCRETE

NOT TO SCALE


NOT TO SCALE

BITUMINOUS CONCRETE


SAWCUT EXISTING PAVEMENT

NOT TO SCALE

PERIMETER OR FOUNDATION DRAIN DETAIL



4'-0" O.C.



Perforations Down

NOT TO SCALE OV @ CUMBERLAND SENIOR HOUSING

MEDOT Specifications for Underdrains (ME DOT #703.22) Sieve Size % Passing by Weight Underdrain Type B 90-100 1/2" 75-100 50-100 #4 #20 15-80 #50 0-15 #200 0-5 Underdrain Type C 100 3/4" 90-100 3/8" 0-75 #4 0-25

CONSTRUCTION OVERSIGHT ROOF DRIPLINE INSTALLATION

The Contractor will retain the services of a professional engineer of the clients choosing to inspect the construction and stabilization of all stormwater management structures to be built as part of the project. If necessary, the inspecting engineer will interpret the construction plans for the contractor. Once all stormwater management structures are constructed and stabilized, the inspecting engineer will notify the department in writing within 30 days to state that the structures have been completed. Accompanying the engineer's notification must be a copy of the test results for any soil fill, aggregate, or mulch materials used in the construction of the stormwater management structures and a log of the engineer's inspections giving the date of each inspection, the time of each inspection, and the items inspected on each visit.

Roof Dripline Filtration


Construction inspections: At a minimum, the professional engineer's inspection will occur after foundation soil preparation but prior to placement of the geotextile lining, after the foundation drain pipe is installed but not yet backfilled, after the pipe bedding gravel is placed but prior to the placement of the gravel filter media, after the gravel filter media has been placed but prior to installing the crushed stone surface layer, and after the surface crushed stone surface layer is installed.

Testing and submittals: The gravel filter media and pipe bedding media used in the roof dripline filtration BMP must be confirmed as suitable by testing. The contractor shall identify the source of these gravels and obtain samples for testing. All testing must be done by a certified laboratory. All results of field and laboratory testing shall be submitted to the project engineer for confirmation. It shall be the contractor's responsibility to ensure completion of the following sampling and testing before the gravel is placed as part of the dripline filter's


• Obtain a sample of the gravel filter media. The sample must be a composite of three different locations (grabs) from the gravel stockpile. The sample size required will be determined by the testing laboratory. Perform a sieve analysis conforming to ASTM C136 (Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates 1996A) of the sand filter media showing it meets the following gradation:


• If the underdrain pipes will be bedded in gravel, obtain a sample of the gravel fill to be used for the pipe bedding. The sample must be a composite of three different locations (grabs) from the stockpile or pit face. The sample size required will be determined by the testing laboratory. Perform a sieve analysis conforming to ASTM C136 (Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates 1996A) of the gravel to be used for the underdrain pipe bedding. The gravel fill must conform to MEDOT specification 703.22 Underdrain

If the underdrain pipes will be bedded in crushed stone, obtain a sample of the crushed stone to be used for the pipe bedding. The sample must be a composite of three different locations (grabs) from the stockpile. The sample size required will be determined by the testing laboratory. Perform a sieve analysis conforming to ASTM C136 (Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates 1996A) of the crushed stone to be used for the underdrain pipe bedding. The crushed stone fill must conform to MEDOT specification 703.22 Underdrain Type C.



NOT TO SCALE





FOUNDATION

UNDERDRAIN PIPE

BACKFILL

- FOR PERMANENT REPAIR

FOR TEMPORARY REPAIR


ALL AROUND TRENCH (SHIPLAP JOINT)


ALL AROUND TRENCH (SHIPLAP JOINT)

BITUMINOUS CONCRETE TOP COURSE

MDOT 403 HOT MIX ASPHALT 12.5 MM

ST-UD-FOUND/02-97





Roof Dripline BMP and Misc. Details


Oceanview at Cumberland 277 Tuttle Road, Cumberland, Maine


Seacoast Management Company 20 Blueberry Lane, Falmouth, Maine





 COMMERCIAL PROJECTS RESIDENTIAL SUBDIVISIONS SITE PLANNING & DESIGN


63 Second Avenue , Augusta, Maine 04330 Ph 207-622-1462, Cell 207-242-5713 SCALE: FIELD WK: JOB #: 109 DRN BY: SS: CH'D BY: FILE: DATE: 3-1-2018












Not to Scale




<u>QTY:</u> 10





2. DESIGNED FOR HS-20 LOADING.


3. JOINTS SEALED WITH BUTYL RUBBER JOINT SEALANT, AASHTO M-19. 4. EXTERIOR OF JOINT TO BE SEALED WITH 12" EZ-WRAP.

APPROX. WEIGHTS: FOOTER: 4,560LBS (1.14CY) — 5. CONTRACTOR SHALL PROVIDE SHOP DRAWING TO ENGINEER FOR APPROVAL PRIOR TO ARCH SECTION: 3,600LBS (.90CY) CONSTRUCTION.









SECTION VIEW: A

REINFORCING DETAIL

2.	2-7-2018	SUBMIT TO DEP
1.	1-31-2018	Respond to Town Memos, submit to Town
		Arch 1 Culvert Details


3. 3-1-2018 Respond to Town Memos, Re-submit to Town

Oceanview at Cumberland 291 Tuttle Road, Cumberland, Maine CSB

CSB

CSB


Seacoast Management Company 20 Blueberry Lane, Falmouth, Maine







FILE:

CONSULTII	• EROSION ENGINEERS Email: cbelange Maine 04330 Ph 207-622-146	er@roadrunner.com
FIELD WK:	SCALE:	SHEET:
DRN BY:	JOB #: 109	\sim
CH'D BY:	SS:	C20







PROGRESS PLAN

NOT FOR CONSTRUCTION

THIS DOCUMENT IS ISSUED FOR INFORMATIONAL PURPOSES ONLY.
THE DATA SHOWN HEREON IS SUBJECT TO REVISION.

Prepared in association with:

LICHT


ENVIRONMENTAL DESIGN, LLC

3.	3-1-2018	Respond to Town Memos, Re-submit to Town	CSB
2.	2-7-2018	SUBMIT TO DEP	CSB
1.	1-31-2018	Respond to Town Memos, submit to Town and DEP	CSB

Mallard Way Wet Pond Plan and Profile

Oceanview at Cumberland 291 Tuttle Road, Cumberland, Maine

Seacoast Management Company 20 Blueberry Lane, Falmouth, Maine



	BELANGER	2 :
	ENGINEERII	NG:
	CONSULTING ENGINEERS venue, Augusta, Maine 04330	Email: cl


• COMMERCIAL PROJECTS
• RESIDENTIAL SUBDIVISIONS
• TOWN AND STATE APPROVALS
• SITE PLANNING & DESIGN
• STORMWATER MANAGEMENT
• ROAD AND UTILITY DESIGN
• EROSION CONTROL PLANS
Email: cbelanger@roadrunner.com
Ph 207-622-1462, Cell 207-242-5713


FIELD WK: SCALE: 1"=20' SHEET:


DRN BY: JOB #: 109


CH'D BY: SS:


DATE: 3-1-2018 FILE:















REV 3/18/16



FOR ADDITIONAL INFORMATION PLEASE CONTACT ACF ENVIRONMENTAL 1-800-448-3636 www.acfenvironmental.com

REVISION

- OBSERVATION/ MAINTENANCE


PORT WITH FOCALPOINT

INSPECTION PORT CAP

DATE

PROJECT NO. 109 DATE March 1, 2018

NOTE: ENGINEER OF RECORD TO REVIEW, APPROVE AND ENDORSE FINAL SITE SPECIFIC DESIGN.




Drainage Class

Excessively Well Drained EWD Well Drained WDModerately Well Drained MWD Somewhat Poorly Drained SPD PD Poorly Drained Very Poorly Drained VPD

Slope Designation


0-3% *3-8%* 8-15% 15-25% >25%


3. Note: High Intensity Soil Survey has been prepared by Mark Hampton Associates, Inc. in accordance with the standards adopted by the Maine Association of Professional Soil Scientists, and the Maine Board of Certification of Geologists and Soil Scientists.











Oceanview at Cumberland 291 Tuttle Road, Cumberland, Maine

Seacoast Management Company 20 Blueberry Lane, Falmouth, Maine




SUBMIT TO DEP


1. 1-31-2018 Re-submit to Town and DEP

2. 2.7-2018

CSB

FIELD WK: SCALE: 1"=100' DRN BY: JOB #: 109 C32 CH'D BY: SS: DATE: 3-1-2018 FILE:






PORTLAND WATER DISCRICT STANDARD DETAILS 1


Oceanview at Cumberland 277 Tuttle Road, Cumberland, Maine


Seacoast Management Company 20 Blueberry Lane, Falmouth, Maine



J	R	BELA	NGER	R	RESIDETOWN	ERCIAL PRO NTIAL SUBE AND STATE ANNING &	DIVISIONS APPROVAL	_S
J	以	ENGIN	IEERII NG ENGINEERS	NG	STORMROAD /EROSIC	IWATER MA AND UTILITY ON CONTRO	ANAGEMEN Y DESIGN IL PLANS	ΙT
	63 Second	Avenue , Augusta,		Ph 207	cbelange -622-146	r@roadrun 2, Cell 207-	ner.com 242-5713	

WHIIII	CONSULTII 63 Second Avenue , Augusta,	NG ENGINEERS Email: cbelange	er@roadrunner.com 52, Cell 207-242-5713
11111	FIELD WK:	SCALE:	SHEET:
	DRN BY:	JOB #: 109	C22
	CH'D BY:	SS:	C33
	DATE: 3-1-2018	FILE:	





- 12" MIN. CLEARANCE

TYPICAL SMALL METER PIT (%" TO 2" METER)

SERVICE PIPE


BLOCKING -

AS REQUIRED

- 3. THE INTERIOR OF THE METER PIT SHALL BE A MINIMUM OF 4' IN DIAMETER, AND THE METER PIT OPENING SHALL BE A MINIMUM OF 30" IN DIAMETER WITH A CAST IRON FRAME. THE METER PIT COVER SHALL BE CAST IRON, 32" MINIMUM IN DIAMETER, AND BE EITHER PERMANENTLY LABELED "WATER" OR HAVE NO LABEL. ANY STEEL PLATE MATERIAL SHALL BE COATED WITH A RUST INHIBITOR PAINT.
- 4. WALL-MOUNTED LADDER RUNGS SHALL NOT BE INSTALLED WITHIN METER PIT.
- 5. ALL PIPING INSIDE AND EXTENDING THROUGH THE METER PIT SHALL BE MADE OF COPPER, WITH A MINIMUM OF 6" CLEARANCE FROM THE METER PIT FLOOR. BLOCKING SHALL BE INSTALLED AS REQUIRED TO SUPPORT THE PIPE.
- 6. CUSTOMER SHALL ENSURE THE METER PIT AND COVER ARE PROPERLY RATED FOR TRAFFIC FLOW, IF APPLICABLE.

METER NOTES

- 7. ONLY PWD PERSONNEL ARE AUTHORIZED TO INSTALL WATER METERS. PWD PERSONNEL ARE ADDITIONALLY AUTHORIZED TO OPERATE METER VALVES AS NEEDED FOR INSTALLATION AND
- 8. PWD WILL SUPPLY THE WATER METER. ALL OTHER FITTINGS, INCLUDING A METER RESETTER FOR 1" OR SMALLER METERS, SHALL BE SUPPLIED AND INSTALLED BY CUSTOMER.
- 9. FOR 1.5" AND 2" METERS, CUSTOMER SHALL INSTALL A FLANGED METER SPOOL PIECE, SUPPLIED BY PWD AT NO ADDITIONAL CHARGE, PRIOR TO METER SET. THE METER SPOOL WILL BE MADE AVAILABLE FOR CUSTOMER PICKUP AT PWD CUSTOMER SERVICE, 225 DOUGLASS STREET, PORTLAND DURING NORMAL BUSINESS HOURS.
- 10. CUSTOMER WILL INSTALL TWO BALL VALVES AT LEAST 24" APART FOR METER INSTALLATION, ALLOWING FOR THE WATER METER TO BE CENTERED UNDER THE METER PIT OPENING. THE BALL VALVES SHALL BE SOLDERED IN PLACE.
- 11. THE METER PIT MAY HOUSE UP TO TWO 5/8", 3/4" OR 1" METERS WITH PRIOR APPROVAL FROM PWD.



TYPICAL MAIN OFFSET


3. 3-1-2018 Respond to Town Memos, Re-submit to Town CSB SUBMIT TO DEP 1. 1-31-2018 Re-Submit to Town and Maine DEP

CSB

PORTLAND WATER DISCRICT STANDARD DETAILS 2

Oceanview at Cumberland 277 Tuttle Road, Cumberland, Maine


Seacoast Management Company 20 Blueberry Lane, Falmouth, Maine



		 COMMERCIAL PROJECTS
	BELANGER	 RESIDENTIAL SUBDIVISIONS
	PLIMITOLI	 TOWN AND STATE APPROVA
7114		SITE PLANNING & DESIGN
-	FAICINIFFDIAI	STORMWATER MANAGEMEN
	'ENGINEERIN(ROAD AND UTILITY DESIGN
	CONCLUTING ENGINEERS	• ERUSIUN CUNTRUL PLANS
•		ail: cbelanger@roadrunner.com
63 Second	Avenue , Augusta, Maine 04330 Ph	207-622-1462, Cell 207-242-5713

 TOWN AND STATE APPROVALS SITE PLANNING & DESIGNSTORMWATER MANAGEMENT • ROAD AND UTILITY DESIGN • EROSION CONTROL PLANS : cbelanger@roadrunner.com 7-622-1462, Cell 207-242-5713 SHEET: SCALE:

FIELD WK: JOB #: 109 DRN BY: SS: CH'D BY: FILE: DATE: 3-1-2018



1. Inc. 72-1686

Anthony Mancini. II.
179 SHERIDAN ST.
PORTLAND, ME 04101
P: (207)774-5829 F: (207)772-168
E: info@mancinielectric.com



DATE DESCRIPTION

03/02/2018 REVISED PLAN FROM

BELANGER ENGINEERING

anview at Cumberland 291 Tuttle Road tumberland, Maine

tric Layout

Site - Photometric Lay

SHEET

ES 1