

MEMORANDUM

ADMINISTRATION DEPARTMENT TOWN OF CUMBERLAND, MAINE

Date: May 12, 2022

To: Cumberland Planning Board

From: Carla Nixon, Town Planner

Subject: Sketch Plan Review: Proposed Major Subdivision - Tuttle Road

This item is a sketch plan review for a proposed 7 lot subdivision of single -family homes on a vacant lot located across from the Fire Station on Tuttle Road.

Please review my memo to Natalie Burns, Town Attorney, and her response, regarding the question of whether the 75' (and 100' from Tuttle Road) buffer can be waived/reduced.

From: Carla Nixon < cnixon@cumberlandmaine.com>

Sent: Monday, May 2, 2022 1:12 PM

To: Natalie L. Burns <nburns@jensenbaird.com>

Cc: Christina Silberman <csilberman@cumberlandmaine.com>; William Longley

<wl><wlongley@cumberlandmaine.com; William Shane <wshane@cumberlandmaine.com; Dan Diffin

<dpd@smemaine.com>

Subject: Re: Proposed Wyatt Subdivision Question

Thanks, Natalie. Very helpful.

Get Outlook for iOS

From: Natalie L. Burns <nburns@jensenbaird.com>

Sent: Friday, April 29, 2022 9:34:07 AM

To: Carla Nixon < cnixon@cumberlandmaine.com>

Cc: Christina Silberman < csilberman@cumberlandmaine.com; William Longley

<wl><wlongley@cumberlandmaine.com; William Shane <wshane@cumberlandmaine.com; Dan Diffin

<dpd@smemaine.com>

Subject: RE: Proposed Wyatt Subdivision Question

WARNING: This is an external email that originated outside of our email system. DO NOT CLICK links or open attachments unless you recognize the sender and know that the content is safe!

Carla,

Section 250-44 states that the Planning Board may waive a standard if it finds either than an unnecessary hardship will result from strict compliance with the subdivision standards or if there are special circumstances of a particular plan that makes the standard inapplicable. The waiver can't have the effect of nullifying the intent and purpose of the Comprehensive Plan, the Subdivision Ordinance or the Zoning Ordinance. It also can't endanger public safety. The Ordinance defines "unnecessary hardship" as "a substantial burden on the applicant which affects the applicant's ability to achieve a reasonable economic return" on the project.

This would appear to fall within either of the criteria for a waiver. Because these buffer requirements only exist in the Subdivision Ordinance and not in the Zoning Ordinance, the Board has the authority to waive them. Any waiver will need to be noted on the subdivision plan and recorded within 2 years of the final subdivision approval.

Thanks,

Natalie

Natalie L. Burns, Esq.

Attorney

JENSEN BAIRD

Ten Free Street P.O. Box 4510 Portland, ME 04112 T: (207) 775-7271

From: Carla Nixon < cnixon@cumberlandmaine.com>

Sent: Thursday, April 28, 2022 2:23 PM

To: Natalie L. Burns < nburns@jensenbaird.com>

Cc: Christina Silberman <csilberman@cumberlandmaine.com>; William Longley

<<u>wlongley@cumberlandmaine.com</u>>; William Shane <<u>wshane@cumberlandmaine.com</u>>; Dan Diffin

<dpd@smemaine.com>

Subject: Proposed Wyatt Subdivision Question

Hi Natalie.

There is a vacant parcel located across from the Fire Station on Tuttle Road. A developer is proposing a 7 lot, single family subdivision to be served by public water and sewer. It is in an identified "Growth Area" in our Comprehensive Plan. When Bill Longley and I first looked at it, it appeared feasible as it is in the Town Center District (TCD) which allows for small lots with small setbacks. However, when the Subdivision Ordinance is considered, the development is not feasible due to the significant perimeter buffers (75') required of all major subdivisions (and in this case, because the development is off Tuttle Road, the buffer is increased to 150' (Section 250-10 (Clustered) and 250-12 (Traditional) along Tuttle Road).

So, the question for you is whether the Planning Board has the authority to reduce the buffer requirements of the subdivision ordinance given the location of the development.

I have this on the May 17th Planning Board agenda for Sketch Plan Review. If your answer is positive, then the applicant will prepare a Traditional and Clustered subdivision plan for the Board to consider.

I believe that these large buffers were in place when the town was envisioning subdivisions in rural areas. This parcel is quite different and would likely be able to be developed more intensely if the recently-adopted law regarding affordable housing/increased density is in place next July.

I also want to add that the Town has approved three other major subdivisions (two condo projects and one apartment building) in the TCD, but they were done with a contract zoning.

Let me know if you need any other information.

Thank you for your help.

Carla



Carla Nixon
Director of Planning, Town of Cumberland
207-829-2206
www.cumberlandmaine.com
290 Tuttle Road, Cumberland, Maine 04021







Confidentiality Notice: This message is intended only for the person to whom addressed in the text above and may contain privileged or confidential information. If you are not that person, any use of this message is prohibited. We request that you notify us by reply to this message, and then delete all copies of this message, attachments and/or files, including any contained in your reply.



April 28, 2022

Town of Cumberland 290 Tuttle Road Cumberland, ME 04021

Re: Wyatt Drive – Proposed Subdivision

Sketch Plan Application Updates

Dear Planning:

Trillium Engineering Group (TEG) is providing the following updates for the Wyatt Drive Sketch Plan submission. TEG previously submitted this application on April 21, 2022 but has updated the plans based on conversations with Town Planner Carla Nixon.

Per the ordinance, the proposed subdivision will require a 75' vegetated buffer around the side and rear property lines, as well as a 150' vegetated buffer from Tuttle Road. TEG is requesting this requirement be waived, as said buffer will leave the site with only 20,736 square feet of buildable area, which is not feasible for a subdivision. See Sheet C101-C for additional information.

Assuming the vegetated buffer requirement can be waived, TEG has prepared two separate subdivision plans. Sheet C101-A depicts a seven-lot traditional subdivision with setbacks and lot density calculations meeting and exceeding the Town Center District standards. Sheet C101-B, meanwhile, depicts a five-lot clustered subdivision with 29,764 square feet of open space. It is our professional opinion that the traditional subdivision plan shown on Sheet C101-A is a better fit for this site, as it provides more lots and the open space requirement will not be necessary in the Town Center District.


Net residential density calculations for the traditional and clustered subdivisions have been provided on their respective sheets. Per Mark Cenci, this site does not feature any wetlands or protected resources which would affect the net residential density calculations.

Thank you for taking the time to review this. Should you have any further questions or require any additional information, please do not hesitate to ask.

Sincerely,

David Latham, P.E.

Trillium Engineering Group






CLIENT: ANDERSON LANDSCAPING

> PRELIMINARY NOT FOR CONSTRUCTION


SUBDIVISION



PROPOSED SITE PLAN - TRADITIONAL

SUBDIVISION DRAWN:

PROJECT NUMBER: C101-A




189 MAIN STREET SUITE 200 YARMOUTH, ME 04096

ANDERSON LANDSCAPING 352 MEMORIAL HIGHWAY NORTH YARMOUTH, ME 04097

> PRELIMINARY NOT FOR CONSTRUCTIO

SUBDIVISION




PROPOSED SITE PLAN - CLUSTERED

SUBDIVISION

DRAWN: PROJECT NUMBER:

C101-B




TRILLIUM
ENGINEERING GROUP

189 MAIN STREET SUITE 200
YARMOUTH, ME 04096

CLIENT:
ANDERSON
LANDSCAPING
352 MEMORIAL HIGHWAY
NORTH YARMOUTH, ME 04097

PRELIMINARY NOT FOR CONSTRUCTIO

WATT DRIVE CUMB
ROPOSED SUBDIVISION



SHEET TITLE:

PROPOSED SITE PLAN

DESIGNED:	DL
DRAWN:	DL
DATE:	04-21-22
PROJECT NUMBER:	22-103

C101-C



April 19, 2022

Town of Cumberland 290 Tuttle Road Cumberland, ME 04021

Re: Wyatt Drive – Proposed Subdivision

Sketch Plan Application

Dear Planning:

Trillium Engineering Group is providing this project narrative for the proposed subdivision to be developed off Tuttle Road (Tax Map U11, Lot 4A). This development proposes a new access road connecting to a proposed seven-lot subdivision located on a currently undeveloped parcel.

The existing site is currently undeveloped with a mix of forested vegetation and lawn area. The proposed state shall install a new access road and remove a portion of the existing tree line as shown on Sheet C101. The road shall be 22 feet wide with granite curb on either side of the road. Additionally, a 4 foot wide gravel sidewalk shall be installed for minor pedestrian traffic.

Access to each lot shall be provided by 16 foot wide driveways. The exact dimensions of the proposed housing units are to be determined, but the Owner currently plans for said units to have garages along with the living area. Approximate building footprints have been shown on each of the respective lots.

The site is to be served by public water and sewer as shown on Sheet C101 and on Sheet C200's "Proposed Driveway Section". Sizes and locations of the proposed lines are still preliminary and are subject to change.

Because this project is still in the sketch plan phase, Trillium Engineering Group has not performed a full stormwater analysis on the existing and proposed conditions.

Thank you for taking the time to review this. Should you have any further questions or require any additional information, please do not hesitate to ask.


Sincerely,

David Latham, P.E.

Trillium Engineering Group

TUTTLE ROAD SUBDIVISION

WYATT DRIVE, CUMBERLAND, ME APRIL 21, 2022



LOCUS MAP

NOT TO SCALE

DRAWING LIST

C100 EXISTING SITE PLAN

C101 PROPOSED GRADING & DRAINAGE PLAN

C200 SITE DETAILS

C300 EROSION CONTROL DETAILS

OWNER:

ANDERSON LANDSCAPING 352 MEMORIAL HIGHWAY NORTH YARMOUTH, ME 04097

CONSULTANTS:


TRILLIUM ENGINEERING GROUP 189 MAIN STREET YARMOUTH, ME 04096



CLIENT:
ANDERSON
LANDSCAPING
352 MEMORIAL HIGHWAY
NORTH YARMOUTH, ME 040

PRELIMINARY
NOT FOR CONSTRUCTION

WYATT DRIVE CUMI




SHEET TITLE:

COVER SHEET

DESIGNED:	DL
DRAWN:	DL
DATE:	04-21-22
PROJECT NUMBER:	22-103

Cc



TRILLIUM
ENGINEERING GROUP
189 MAIN STREET SUITE 200
YARMOUTH, ME 04096

ANDERSON
LANDSCAPING


352 MEMORIAL HIGHWAY

NORTH YARMOUTH, ME 04097

PRELIMINARY OT FOR CONSTRUCTION

BERLAND, ME

UTTLE ROAD SUBDIVISIO



SHEET TITLE:

EXISTING SITE PLAN


DESIGNED: DL

DRAWN: DL

DATE: 04-21-22

PROJECT NUMBER: 22-103

C100



TRILLIUM
ENGINEERING GROUP

189 MAIN STREET SUITE 200
YARMOUTH, ME 04096

CLIENT:
ANDERSON
LANDSCAPING
352 MEMORIAL HIGHWAY
NORTH YARMOUTH, ME 04097

PRELIMINARY NOT FOR CONSTRUCTION

I FOR CONSTRUCTION

WYATT DRIVE

WYATT DRIVE

PROPOSED SUBDIVISION

SHEET TITLE:

PROPOSED GRADING AND DRAINAGE PLAN


DESIGNED: DL

DRAWN: DL

DATE: 04-21-22

PROJECT NUMBER: 22-103


C101



- NOTES:

 1. POWER, TELEPHONE, AND CABLE TV SHALL NOT BE PLACED LESS THAN 30 INCHES DEEP. 2. DEPTH OF OTHER UTILITIES AS PER THE RECOMMENDATION OF THE APPLICABLE UTILITY COMPANY.
- 3. WARNING TAPE SHALL BE PLACED OVER EACH LINE. PVC CONDUIT IS REQUIRED FOR STREET CROSSINGS
- AND UNDER PAVEMENT MORE THAN 12 FEET IN LENGTH. 4. LOAM AND SEED SHALL BE IN ACCORDANCE WITH MDOT SPECIFICATIONS 615 AND 618, METHOD ONE. 5. ENTIRE WIDTH OF ROADWAY AND SHOULDERS SHALL BE STRIPPED AND GRUBBED OF TOP SOIL, ORGANICS AND OTHER DELETERIOUS MATERIAL. ALL STUMPS AND UNSUITABLE MATERIAL (IF ANY) SHALL BE REMOVED
- IF WITHIN 5 FEET OF FINISHED GRADE UNDER ALL PAVED AREAS. 6. SUITABLE GRANULAR FILL MATERIAL SHALL CONSIST OF HARD DURABLE MINERALS LESS VERY FINE SANDS, SILT, CLAY, OR ORGANIC MATERIALS. MATERIAL SHALL BE PLACED IN LIFTS NOT TO EXCEED 12 INCHES. COMPACTION SHALL BE ACHIEVED BY MECHANICAL MEANS OF A "DYNAPAC", TANDEM VIBRATORY WALK BEHIND ROLLER, OR TRACKING WITH HEAVY EQUIPMENT.

<u>RE</u>		<u>DED MIN</u> ATURES		<u>ACEMENT</u> VEMENT	Ι	
BASE 1	MAT THICKNESS, IN INCHES					
TEMPERATURE F	1/2	3/4	1	1 1/2	2	
+40 - 50	_	-	310	300	285	2
+50 - 60	-	310	300	295	280	2
+60 - 70	310	300	290	285	275	2
+70 - 80	300	290	285	280	270	2
+80 - 90	290	280	275	270	265	2
+90	280	275	270	265	260	2
ROLLING TIME MIN.	4	6	8	12	15	1



BIT. PAVEMENT


∠AGGREGATE SUBBASE,

-AGGREGATE BASE,

SCALE: NTS

TYPE "D"

TYPE "A"




TYP. PIPE TRENCH SECTION

SCALE: NTS

PROPOSED DRIVEWAY SECTION

SCALE: NTS

PLASTIC 'ELECTRIC' MARKER TAPE PLACED APPROX. 12" BELOW ∕— 4" LOAM & SEED FINISH GRADE-(OR PARKING SECTION) 4" LOAM & SEED-CLEAN BACKFILL CONTAINING NO ROCKS LARGER THAN 6'-0" GRANITE TIPDOWN 4 INCHES IN DIAMETER FILTER FABRIC — PRIMARY, SECONDARY, OR _4" x 8½" FILTER FABRIC SERVICE CABLE, OR CABLE TV IN ½" DIA. CONDUIT. -COMMUNICATION CABLE —SOIL BEDDING CONTAINING 6" 12" MIN. MIN. NO ROCKS $JOINT = \frac{1}{4}" + \frac{1}{8}"$ 2'-0"



SEWER "Y" CONNECTION DETAIL


SCALE: NTS

SCALE: NTS

TYP. WIRE TRENCH SECTION

GRANITE CURB INSTALLATION DETAIL

ELEVATION



1. CONTRACTOR SHALL CONFIRM ALL PIPE SIZES WITH THE CITY WATER DISTRICT. 2. WORK AND MATERIALS TO BE IN ACCORDANCE WITH THE CITY WATER DISTRICT STANDARDS. 3. CONTRACTOR SHALL STUB NEW SERVICES AT THE EDGE OF THE R.O.W. IN THE MIDDLE OF EACH LOT, UNLESS OTHERWISE NOTED ON THE PLAN/PROFILES. 4. FINAL LOCATION OF ALL BLOW OFF VALVES, SHUT OFF VALVES, STREET BOXES AND HYDRANT

VALVES SHALL BE IN ACCORDANCE WITH THE CITY WATER DISTRICT.

TYP. WATER SERVICE CONNECTION DETAIL

SCALE: NTS

SHEET TITLE:

ENGINEERING GROUP

189 MAIN STREET SUITE 200

YARMOUTH, ME 04096

CLIENT:

SUBDIVISIO

ANDERSON

LANDSCAPING

352 MEMORIAL HIGHWAY

NORTH YARMOUTH, ME 04097

PRELIMINARY

NOT FOR CONSTRUCTION

SITE DETAILS

DRAWN: DL 04-21-22 PROJECT NUMBER: 22-103

EROSION AND SEDIMENTATION NOTES

1. THIS PLAN HAS BEEN DEVELOPED TO PROVIDE A STRATEGY FOR DEALING WITH SOIL EROSION AND SEDIMENTATION DURING AND AFTER PROJECT CONSTRUCTION. THIS PLAN IS BASED ON THE STANDARD AND SPECIFICATIONS FOR EROSION PREVENTION AS CONTAINED IN THE MAINE EROSION AND SEDIMENT CONTROL HANDBOOK FOR CONSTRUCTION: "MAINE EROSION AND SEDIMENT CONTROL BMPs" PUBLISHED BY THE MAINE DEP, LATEST EDITION.

GENERAL EROSION AND SEDIMENTATION CONTROL PRACTICES

1. EROSION/SEDIMENT CONTROL DEVICES

THE FOLLOWING EROSION SEDIMENTATION CONTROL DEVICES ARE PROPOSED FOR CONSTRUCTION

ON THIS PROJECT. INSTALL THESE DEVICES AS INDICATED ON THE PLANS. 1.1 SILT FENCE: SILT FENCE WILL BE INSTALLED ALONG THE DOWN GRADING EDGES OF DISTURBED AREAS TO TRAP RUNOFF BORNE SEDIMENTS UNTIL THE SITE IS STABILIZED. IN AREAS WHERE STORMWATER DISCHARGES THE SILT FENCE WILL BE REINFORCED WITH HAY BALES TO HELP MAINTAIN

THE INTEGRITY OF THE SILT FENCE AND TO PROVIDE ADDITIONAL TREATMENT.

- 1.2 HAY BALES TO BE PLACED IN LOW FLOW DRAINAGE SWALES AND PATHS TO TRAP SEDIMENTS AND REDUCE RUNOFF VELOCITIES. DO NOT PLACE HAY BALES IN FLOWING WATER OR STREAMS.
- 1.3 RIPRAP: PROVIDE RIPRAP IN AREAS WHERE CULVERTS DISCHARGE OR AS SHOWN ON THE PLANS. 1.4 LOAM, SEED, & MULCH: ALL DISTURBED AREAS, WHICH ARE NOT OTHERWISE TREATED, SHALL RECEIVE PERMANENT SEEDING AND MULCH TO STABILIZE THE DISTURBED AREAS. THE DISTURBED AREAS WILL BE REVEGETATED WITHIN 5 DAYS OF FINAL GRADING. SEEDING REQUIREMENTS ARE
- PROVIDED AT THE END OF THIS SPECIFICATION. 1.5 STRAW AND HAY MULCH; USED TO COVER DENUDED AREAS UNTIL PERMANENT SEED OR EROSION CONTROL MEASURES ARE IN PLACE. MULCH BY ITSELF CAN BE USED ON SLOPES LESS THAN 15% IN SUMMER AND 8% IN WINTER. ALL OTHER SLOPES MUST BE COVERED WITH JUTE MESH OVER MULCH,
- OR CURLEX II OR EXCELSIOR MAY BE USED IN PLACE OF JUTE MESH AND MULCH OVER LOAM AND SEED. 1.6 MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL DRAINAGE WAYS WITH A SLOPE GREATER THAN 3% FOR SLOPES EXPOSED TO DIRECT WINDS AND FOR ALL OTHER SLOPES GREATER THAN 8%.
- 2. TEMPORARY EROSION/SEDIMENTATION CONTROL MEASURES PROVIDE THE FOLLOWING TEMPORARY EROSION/SEDIMENTATION CONTROL MEASURES DURING

VEGETATED DRAINAGE SWALES SHALL BE LINED WITH EXCELSIOR OR CURLEX.

- CONSTRUCTION OF THE DEVELOPMENT: 2.1 SILTATION FENCE ALONG THE DOWNGRADIENT SIDE OF THE PARKING AREAS AND OF ALL FILL
- SECTIONS. THE SILTATION FENCE WILL REMAIN IN PLACE UNTIL THE SITE IS 85% REVEGETATED. 2.2 HAY BALES PLACED AT KEY LOCATIONS TO SUPPLEMENT THE SILT FENCE.
- 2.3 PROTECT TEMPORARY STOCKPILES OF STUMPS, GRUBBINGS, OR COMMON EXCAVATION AS FOLLOWS:
- A. SOIL STOCKPILE SIDE SLOPES SHALL NOT EXCEED 2:1. B. AVOID PLACING TEMPORARY STOCKPILES IN AREAS WITH SLOPES OVER 10 PERCENT, OR
- NEAR DRAINAGE SWALES. SEE ITEM 3 IN CONSTRUCTION PHASE NOTES BELOW. C. STABILIZE STOCKPILES WITHIN 15 DAYS BY TEMPORARILY SEEDING WITH A HYDROSEED METHOD CONTAINING AN EMULSIFIED MULCH TACKIFIER OR BY COVERING THE STOCKPILE
- D. SURROUND STOCKPILE SOIL WITH SILTATION FENCE AT BASE OF PILE.
- 2.4 ALL DENUDED AREAS WHICH HAVE BEEN ROUGH GRADED AND ARE NOT LOCATED WITHIN THE BUILDING PAD, OR PARKING AND DRIVEWAY SUBBASE AREA SHALL RECEIVE MULCH WITHIN 30 DAYS OF INITIAL DISTURBANCE OF SOIL OR WITHIN 15 DAYS AFTER COMPLETING THE ROUGH GRADING OPERATIONS. IN THE EVENT THE CONTRACTOR COMPLETES FINAL GRADING AND INSTALLATION OF LOAM AND SOD WITHIN THE TIME PERIODS PRESENTED ABOVE, INSTALLATION OF MULCH AND NETTING, WHERE APPLICABLE,
- 2.5 IF WORK IS CONDUCTED BETWEEN OCTOBER 15 AND APRIL 15, ALL DENUDED AREAS ARE TO BE COVERED WITH HAY MULCH, APPLIED AT TWICE THE NORMAL APPLICATION RATE, AND ANCHORED WITH FABRIC NETTING. THE PERIOD BETWEEN FINAL GRADING AND MULCHING SHALL BE REDUCED TO A 15 DAY MAXIMUM.
- 2.6 TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED ONCE THE SITE HAS BEEN STABILIZED OR IN AREAS WHERE PERMANENT EROSION CONTROL MEASURES HAVE BEEN INSTALLED.
- PERMANENT EROSION CONTROL MEASURES THE FOLLOWING PERMANENT CONTROL MEASURES ARE REQUIRED BY THIS EROSION/SEDIMENTATION
- 3.1 ALL AREAS DISTURBED DURING CONSTRUCTION, BUT NOT SUBJECT TO OTHER RESTORATION (PAVING, RIPRAP, ETC.), WILL BE LOAMED, LIMED, FERTILIZED AND SEEDED. NATIVE TOPSOIL SHALL BE STOCKPILED AND REUSED FOR FINAL RESTORATION WHEN IT IS OF SUFFICIENT QUALITY.
- 3.2 SLOPES GREATER THAN 2:1 WILL RECEIVE RIPRAP.

CONSTRUCTION PHASE

THE FOLLOWING GENERAL PRACTICES WILL BE USED TO PREVENT EROSION DURING CONSTRUCTION OF THIS PROJECT. 1. ONLY THOSE AREAS UNDER ACTIVE CONSTRUCTION WILL BE CLEARED AND LEFT IN AN UNTREATED

- OR UNVEGETATED CONDITION. IF FINAL GRADING, LOAMING AND SEEDING WILL NOT OCCUR WITHIN 15 DAYS, SEE ITEM NO. 4. 2. PRIOR TO THE START OF CONSTRUCTION IN A SPECIFIC AREA, SILT FENCING AND/OR HAY BALES
- WILL BE INSTALLED AT THE TOE OF SLOPE AND IN AREAS AS LOCATED ON THE PLANS TO PROTECT AGAINST ANY CONSTRUCTION RELATED EROSION. IMMEDIATELY FOLLOWING CONSTRUCTION OF CULVERTS AND SWALES, RIP RAP APRONS SHALL BE INSTALLED, AS SHOWN ON THE PLANS.
- 3. TOPSOIL WILL BE STOCKPILED WHEN NECESSARY IN AREAS WHICH HAVE MINIMUM POTENTIAL FOR EROSION AND WILL BE KEPT AS FAR AS POSSIBLE FROM THE EXISTING DRAINAGE COURSE. NO STOCKPILE SHALL BE CLOSER THEN 100' OF A RESOURCE INCLUDING, BUT NOT LIMITED TO, WETLANDS, STREAMS, AND OPEN WATER BODIES. ALL STOCKPILES SHALL HAVE A SILTATION FENCE BELOW THEM REGARDLESS OF TIME OF PRESENCE. ALL STOCKPILES EXPECTED TO REMAIN LONGER THAN 15 DAYS SHALL BE:
- A. TREATED WITH ANCHORED MULCH (WITHIN 5 DAYS OF THE LAST DEPOSIT OF STOCKPILED SOIL). B. SEEDED WITH CONSERVATION MIX AND MULCHED IMMEDIATELY.
- C. INSTALL SILT FENCE AROUND STOCKPILE AT BASE OF PILE.
- STOCKPILES TO HAVE SILT FENCE INSTALLED AT TIME OF ESTABLISHMENT AT BASE OF PILE. 4. ALL DISTURBED AREAS EXPECTED TO REMAIN LONGER THAN 30 DAYS SHALL BE EITHER:
- A. TREATED WITH ANCHORED MULCH IMMEDIATELY, OR
- B. SEEDED WITH CONSERVATION MIX OF ANNUAL RYE GRASS (0.9 LBS/1000 SQ. FT) AND MULCHED IMMEDIATELY.
- ALL GRADING WILL BE HELD TO A MAXIMUM 2:1 SLOPE WHERE PRACTICAL. ALL SLOPES WILL BE STABILIZED WITH PERMANENT SEEDING, OR WITH STONE, WITHIN 5 DAYS AFTER FINAL GRADING IS COMPLETE. (SEE POST-CONSTRUCTION REVEGETATION FOR SEEDING SPECIFICATION.)
- 6. ALL CULVERTS WILL BE PROTECTED WITH STONE RIPRAP (D50 = 6" UNLESS OTHERWISE SPECIFIED) AT INLETS AND OUTLETS.

POST-CONSTRUCTION REVEGETATION

THE FOLLOWING GENERAL PRACTICES WILL BE USED TO PREVENT EROSION AS SOON AS AN AREA IS READY TO UNDERGO FINAL GRADING.

- 1. A MINIMUM OF 4" OF LOAM WILL BE SPREAD OVER DISTURBED AREAS AND GRADED TO A UNIFORM DEPTH AND NATURAL APPEARANCE, OR STONE WILL BE PLACED ON SLOPES TO STABILIZE SURFACES.
- 2. IF FINAL GRADING IS REACHED DURING THE NORMAL GROWING SEASON (4/15 TO 9/15), PERMANENT SEEDING WILL BE DONE AS SPECIFIED BELOW. PRIOR TO SEEDING, LIMESTONE SHALL BE APPLIED AT A RATE OF 138 LBS/1000 SQ. FT. AND 10:20:20 FERTILIZER AT A RATE OF 18.4 LBS/1000 SQ.FT WILL BE APPLIED. BROADCAST SEEDING AT THE FOLLOWING RATES:

KENTUCKY BLUEGRASS 0.46 LBS/1000 SF. CREEPING RED FESCUE 0.46 LBS/1000 SF.

RED TOP 0.05 LBS/1000 SF. TALL FESCUE 0.46 LBS/1000 SF. PERENNIAL RYE GRASS 0.11 LB/1000 SF.

- 3. AN AREA SHALL BE MULCHED IMMEDIATELY AFTER IS HAS BEEN SEEDED. MULCHING SHALL CONSIST OF HAY MULCH, HYDRO-MULCH, JUTE NET OVER MULCH, PRE-MANUFACTURED EROSION MATS OR ANY SUITABLE SUBSTITUTE DEEMED ACCEPTABLE BY THE DESIGNER.
- A. HAY MULCH SHALL BE APPLIED AT THE RATE OF 2 TONS PER ACRE. HAY MULCH SHALL BE SECURED BY EITHER: (NOTE: SOIL SHALL NOT BE VISIBLE)
- I. BEING DRIVEN OVER BY TRACKED CONSTRUCTION EQUIPMENT ON GRADES OF 5% AND LESS. II. BLANKETED BY TACKED PHOTODEGRADABLE/BIODEGRADABLE NETTING, OR WITH SPRAY, ON GRADES GREATER THAN 5%.
- III. SEE NOTE 6, GENERAL NOTES, AND NOTE 8, WINTER CONSTRUCTION.
- B. HYDRO-MULCH SHALL CONSIST OF A MIXTURE OF EITHER ASPHALT, WOOD FIBER OR PAPER FIBER AND WATER SPRAYED OVER A SEEDED AREA. HYDRO-MULCH SHALL NOT BE USED BETWEEN 9/15 AND 4/15. CONSTRUCTION SHALL BE PLANNED TO ELIMINATE THE NEED FOR SEEDING BETWEEN SEPTEMBER
- 15 AND APRIL 15. SHOULD SEEDING BE NECESSARY BETWEEN SEPTEMBER 15 AND APRIL 15 THE FOLLOWING PROCEDURE SHALL BE FOLLOWED. ALSO REFER TO NOTE 9 OF WINTER CONSTRUCTION. A. ONLY UNFROZEN LOAM SHALL BE USED.
- B. LOAMING, SEEDING AND MULCHING WILL NOT BE DONE OVER SNOW OR ICE COVER. IF SNOW EXISTS, IT MUST BE REMOVED PRIOR TO PLACEMENT OF SEED.
- C. WHERE PERMANENT SEEDING IS NECESSARY, ANNUAL WINTER RYE (1.2 LBS/1000 SQ.FT) SHALL
- BE ADDED TO THE PREVIOUSLY NOTED AREAS. D. WHERE TEMPORARY SEEDING IS REQUIRED, ANNUAL WINTER RYE (2.6 LBS/1000 SQ. FT.) SHALL
- BE SOWN INSTEAD OF THE PREVIOUSLY NOTED SEEDING RATE. E. FERTILIZING, SEEDING AND MULCHING SHALL BE APPLIED TO LOAM THE DAY THE LOAM IS
- SPREAD BY MACHINERY.
- F. ALTERNATIVE HAY MULCH SHALL BE SECURED WITH PHOTODEGRADABLE/BIODEGRADABLE NETTING. TRACKING BY MACHINERY ALONE WILL NOT SUFFICE.
- 5. FOLLOWING FINAL SEEDING, THE SITE WILL BE INSPECTED EVERY 30 DAYS UNTIL 85% COVER HAS BEEN ESTABLISHED. RESEEDING WILL BE CARRIED OUT BY THE CONTRACTOR WITHIN 10 DAYS OF NOTIFICATION BY THE ENGINEER THAT THE EXISTING CATCH IS INADEQUATE.

MONITORING SCHEDULE

THE CONTRACTOR IS RESPONSIBLE FOR INSTALLING, MONITORING, MAINTAINING, REPAIRING, REPLACING AND REMOVING ALL OF THE EROSION AND SEDIMENTATION CONTROLS OR APPOINTING A QUALIFIED SUBCONTRACTOR TO DO SO. MAINTENANCE MEASURES WILL BE APPLIED AS NEEDED DURING THE ENTIRE CONSTRUCTION CYCLE

AFTER EACH RAINFALL, A VISUAL INSPECTION WILL BE MADE OF ALL EROSION AND SEDIMENTATION CONTROLS AS FOLLOWS: HAY BALE BARRIERS, SILT FENCE, AND STONE CHECK DAMS SHALL BE INSPECTED AND REPAIRED ONCE A WEEK OR IMMEDIATELY FOLLOWING ANY SIGNIFICANT RAINFALL. SEDIMENT TRAPPED BEHIND

THESE BARRIERS SHALL BE EXCAVATED WHEN IT REACHES A DEPTH OF 6" AND REDISTRIBUTED TO

- AREAS UNDERGOING FINAL GRADING. SHOULD THE HAY BALE BARRIERS PROVE TO BE INEFFECTIVE, THE CONTRACTOR SHALL INSTALL SILT FENCE BEHIND THE HAY BALES. 2. VISUALLY INSPECT RIPRAP ONCE A WEEK OR AFTER EACH SIGNIFICANT RAINFALL AND REPAIR AS NEEDED. REMOVE SEDIMENT TRAPPED BEHIND THESE DEVICES ONCE IT ATTAINS A DEPTH EQUAL TO 1/2 THE HEIGHT OF THE DAM OR RISER. DISTRIBUTE REMOVED SEDIMENT OFF—SITE OR TO AN AREA
- REVEGETATION OF DISTURBED AREAS WITHIN 25' OF DRAINAGE-COURSE/STREAM WILL BE SEEDED WITH THE "MEADOW AREA MIX" AND INSPECTED ON A WEEKLY BASIS OR AFTER EACH SIGNIFICANT RAINFALL AND RESEFDED AS NEFDED. FYPOSED AREAS WILL BE RESEFDED AS NEFDED LINTH THE AREA HAS OBTAINED 100% GROWTH RATE. PROVIDE PERMANENT RIPRAP FOR SLOPES IN EXCESS OF 3:1 AND WITHIN 25' OF DRAINAGE COURSE.

- 1. WINTER CONSTRUCTION PERIOD: NOVEMBER 1 THROUGH APRIL 15.
- THE SITE IS WITHOUT STABILIZATION AT ANY ONE TIME.
- 4. CONTINUATION OF EARTHWORK OPERATIONS ON ADDITIONAL AREAS SHALL NOT BEGIN UNTIL THE

EXPOSED SOIL SURFACE ON THE AREA BEING WORKED HAS BEEN STABILIZED, SUCH THAT NO LARGER


- AN AREA SHALL BE CONSIDERED TO HAVE BEEN STABILIZED WHEN EXPOSED SURFACES HAVE BEEN EITHER MULCHED WITH STRAW OR HAY AT A RATE OF 150 LB. PER 1000 S.F. (WITH OR WITHOUT SEEDING) OR DORMANT SEEDED. MULCHED AND ANCHORED SUCH THAT SOIL SURFACE IS NOT VISIBLE THROUGH THE MULCH. NOTE: AN AREA IS ALSO CONSIDERED STABLE IF SODDED, COVERED WITH GRAVEL (PARKING LOTS) OR STRUCTURAL SAND.
- BETWEEN THE DATES OF OCTOBER 15 AND APRIL 1, LOAM OR SEED WILL NOT BE REQUIRED. DURING PERIODS OF ABOVE FREEZING TEMPERATURES THE SLOPES SHALL BE FINE GRADED AND EITHER PROTECTED WITH MULCH OR TEMPORARILY SEEDED AND MULCHED UNTIL SUCH TIME AS THE FINAL TREATMENT CAN BE APPLIED. IF THE DATE IS AFTER NOVEMBER 1 AND IF THE EXPOSED AREA HAS BEEN LOAMED, FINAL GRADED WITH A UNIFORM SURFACE, THEN THE AREA MAY BE DORMANT SEEDED AT A RATE OF 3 TIMES HIGHER THAN SPECIFIED FOR PERMANENT SEED AND THEN MULCHED. IF CONSTRUCTION CONTINUES DURING FREEZING WEATHER, ALL EXPOSED AREAS SHALL BE CONTINUOUSLY GRADED BEFORE FREEZING AND THE SURFACE TEMPORARILY PROTECTED FROM EROSION BY THE APPLICATION OF MULCH. SLOPES SHALL NOT BE LEFT UNEXPOSED OVER THE WINTER OR ANY OTHER EXTENDED TIME OF WORK SUSPENSION UNLESS TREATED IN THE ABOVE MANNER. UNTIL SUCH TIME AS WEATHER CONDITIONS ALLOW, DITCHES TO BE FINISHED WITH THE PERMANENT SURFACE TREATMENT, EROSION SHALL BE CONTROLLED BY THE INSTALLATION OF BALES OF HAY, SILT FENCE OR STONE CHECK DAMS IN ACCORDANCE WITH THE STANDARD DETAILS SHOWN ON THE DESIGN DRAWINGS. NOTE: DORMANT SEEDING SHOULD NOT BE ATTEMPTED UNLESS SOIL TEMPERATURE REMAINS BELOW 50 DEGREES AND DAY TIME TEMPERATURES REMAIN
- MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL DRAINAGE WAYS WITH A SLOPE GREATER THAN 3% FOR SLOPES EXPOSED TO DIRECT WINDS AND FOR ALL OTHER SLOPES GREATER THAN 8%.
- MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL DRAINAGE WAYS WITH SLOPES GREATER
- AFTER NOVEMBER 1, WINTER RYE IS NOT EFFECTIVE. AROUND NOVEMBER 15 OR LATER, ONCE
- 10. IN THE EVENT OF SNOWFALL (FRESH OR CUMULATIVE) GREATER THAN 1 INCH DURING WINTER CONSTRUCTION PERIOD ALL SNOW SHALL BE REMOVED FROM THE AREAS OF SEEDING AND MULCHING PRIOR TO PLACEMENT.


1. WEEKLY INSPECTIONS, AS WELL AS ROUTINE INSPECTIONS FOLLOWING RAIN FALLS, SHALL BE CONDUCTED BY THE GENERAL CONTRACTOR OF ALL TEMPORARY AND PERMANENT EROSION CONTROL DEVICES UNTIL FINAL ACCEPTANCE OF THE PROJECT (85% GRASS CATCH). NECESSARY REPAIRS SHALL BE MADE TO CORRECT UNDERMINING OR DETERIORATION. FINAL ACCEPTANCE SHALL INCLUDE A SITE INSPECTION TO VERIFY THE STABILITY OF ALL DISTURBED AREAS AND SLOPES. UNTIL FINAL INSPECTION, ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL IMMEDIATELY BE CLEANED AND REPAIRED BY THE GENERAL CONTRACTOR AS REQUIRED. DISPOSAL OF ALL TEMPORARY EROSION AND CONTROL DEVICES SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.


IT IS RECOMMENDED THAT THE OWNER HIRE THE SERVICES OF THE DESIGN ENGINEER TO PROVIDE COMPLIANCE INSPECTIONS (DURING ACTIVE CONSTRUCTION) RELATIVE TO IMPLEMENTATION OF THE STORMWATER AND EROSION CONTROL PLANS. SUCH INSPECTIONS SHOULD BE LIMITED TO ONCE A WEEK OR AS NECESSARY AND BE REPORTABLE TO THE OWNER, TOWN AND DEP.


MAINTENANCE AFTER CONSTRUCTION

- 1. LONG-TERM PROVISIONS FOR PERMANENT MAINTENANCE OF ALL EROSION AND SEDIMENTATION OWNER OR THEIR DESIGNEE. SUCH RESPONSIBILITIES INCLUDE BUT ARE NOT LIMITED TO THOSE DETAILED AS FOLLOWS:
- A. PARKING LOT SHALL BE MECHANICALLY SWEPT TWICE PER YEAR. THE FIRST SHALL TAKE PLACE THIS POINT. THE SECOND SWEEPING SHALL TAKE PLACE AFTER WINTER SANDING OPERATIONS
- ACCESS TO THE STRUCTURE IS THROUGH THE TOP. THE OIL/WATER SEPARATOR UNIT SHALL BE PUMPED DOWN AND THE SEDIMENT AND TRASH SHALL BE REMOVED AT THE TIME OF THE INSPECTION. THE REMOVAL OF ALL SEDIMENT AND TRASH WILL HELP MINIMIZE VOLUME LOSS.
- 2. THE OWNER SHALL FILE A YEARLY MAINTENANCE REPORT TO THE CITY DOCUMENTING THE REQUIRED MAINTENANCE FOR THE STORMWATER SYSTEM.









BAG DETAIL

"SILTSACK" INSTALLATION INSTRUCTION

- 1. REMOVE THE CATCH BASIN GRATE AND PLACE THE SACK INTO THE OPENING. HOLD OUT APPROXIMATELY SIX (6) INCHES OF THE SACK BEYOND THE BASIN FRAME TO ALLOW ACCESS TO THE "SILTSACK" LIFTING STRAPS. REPLACING THE GRATE BACK INSIDE OF ITS FRAME WILL HOLD THE SACK IN PLACE.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MONITORING AND MAINTAINING THIS SEDIMENT CONTROL DEVICE. THE SACK IS CONSIDERED FULL AND READY TO EMPTY WHEN THE THE "RESTRAINT CORD" IS NO LONGER VISIBLE.
- 3. THE "SILTSACK" IS REMOVED BY PLACING TWO (2) PIECES IF 1 INCH DIAMETER REBAR THROUGH THE LIFTING LOOPS LOCATED ON EACH SIDE OF THE SACK AND LIFTING WITH AN APPROPRIATE PIECE OF CONSTRUCTION EQUIPMENT. THE LIFTING STRAPS ARE CONNECTED TO THE BOTTOM OF THE SACK AND THE LIFTING ACTION WILL CAUSE THE SACK TO TURN INSIDE OUT, AND EMPTYING THE CONTENTS. THE SACK SHOULD THEN BE CLEANED, RINSED AND RETURNED TO ITS ORIGINAL SHAPE AND PLACED BACK IN THE BASIN.
- 4. THE "SILTSACK" IS REUSABLE, THEREFORE, ONCE THE CONSTRUCTION CYCLE IS COMPLETE, REMOVE THE SACK FROM THE BASIN, CLEAN AND STORE OUT OF DIRECT SUNLIGHT UNTIL ITS NEXT USE.
- 5. THE "SILTSACK" SEDIMENT CONTROL DEVICE IS MANUFACTURED BY: ACF ENVIRONMENTAL

EROSION CONTROL DURING WINTER CONSTRUCTION


- WINTER EXCAVATION AND EARTHWORK SHALL BE COMPLETED SUCH THAT NO MORE THAN 1 ACRE OF
- EXPOSED AREA SHALL BE LIMITED TO THOSE AREAS TO BE MULCHED IN ONE DAY PRIOR TO ANY SNOW EVENT. AT THE END OF EACH WORK WEEK NO AREAS MAY BE LEFT UNSTABILIZED OVER THE WEEKEND.
- AREA OF THE SITE IS WITHOUT EROSION CONTROL PROTECTION AS LISTED IN ITEM 2 ABOVE.

- VEGETATED DRAINAGE SWALES SHALL BE LINED WITH EXCELSIOR OR CURLEX.
- THAN 15%. AFTER OCTOBER 1 THE SAME APPLIES FOR ALL SLOPES GREATER THAN 8%.
- BETWEEN THE DATES OF OCTOBER 15 TO NOVEMBER 1, WINTER RYE IS RECOMMENDED FOR STABILIZATION. TEMPERATURES OF THE AIR AND SOIL PERMIT, DORMANT SEEDING IS EFFECTIVE.

SITE INSPECTION AND MAINTENANCE

SHORT-TERM SEDIMENTATION MAINTENANCE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO CLEAN OUT ALL SWALES AND STRUCTURES PRIOR TO TURNING PROJECT OVER TO THE CITY.

- CONTROL FACILITIES AFTER ACCEPTANCE OF THE PROJECT SHALL BE THE RESPONSIBILITY OF THE
- IN THE MID WINTER (JANUARY THAW) TO REMOVE ACCUMULATED SANDS FROM WINTER SANDING TO TERMINATE BUT PRIOR TO MAY 1.
- B. INSPECTION OF STORMWATER OUTLET STRUCTURE SHOULD BE CONDUCTED TWICE PER YEAR.



TERMINAL TRENCH

- UNROLL MAT ONTO GROUND IN DIRECTION OF WATER FLOW.

- SECURE MAT SNUGLY INTO ALL TRANSVERSE CHECK SLOTS.

WATER FLOW, START NEW ROLLS IN A TRANSVERSE DITCH.

OVERLAP EDGES BEFORE BACKFILLING AND COMPACTING.

EROSION CONTROL BLANKET

- FOLOW COLORED DOT PATTERNS BY MANUFACTURER

- DRIVE WOODEN STAKES TO WITHIN THREE (3) INCHES OF GROUND

12" TO 18" LONG, DEPENDING ON SOIL DENSITY.

SURFACE. DO NOT DRIVE FLUSH TO SURFACE.

MAT SHOULD LIE FLAT. DO NOT STRETCH MAT OVER GROUND. STRETCHING MAY

- OVERLAP ADJACENT EDGES OF MAT BY THREE (3) INCHES (MIN.) AND STAKE

- STAKE OVERLAPS LONGITUDINALLY AT THREE (3) TO FIVE (5) FOOT INTERVALS.

REQUIRED ON ALL SLOPES > 8% (WINTER CONSTRUCTION)

REQUIRED ON ALL SLOPES > 15% (SUMMER CONSTRUCTION)

CAUSE MAT TO BRIDGE DEPRESSIONS IN THE SURFACE AND ALLOW EROSION UNDERNEATH

- OVERLAP ROLL ENDS BY THREE (3) FEET (MIN.) WITH UPSLOPE MAT ON TOP TO PREVENT

WOOD STAKES ARE RECOMMENDED FOR PINNING MAT TO THE GROUND SURFACE. STAKES

SHOULD BE 1" X 3" NOMINAL STOCK CUT IN A TRIANGULAR SHAPE. STAKES SHOULD BE

GENERAL INSTALLATION GUIDELINES ON SLOPES

STAPLE OUTSIDE EDGE

ON 2' CENTERS

4" OVERLAP OF NETTING

WHERE 2 OR MORE STRIP

STAPLE ON 18" CENTERS

WIDTHS ARE REQUIRED.

CONSTRUCTION NOTES:

EROSION CONTROL BLANKET

SILTATION FENCE DETAIL

A. BURY THE TOP OF THE NETTING

4" DOWN FROM THE TRENCH

OF TOP STRIP 4" AND STAPLE

IN DITCHES OR STEEP SLOPES.

IN A TRENCH 6" OR MORE DEEP

B. TAM TRENCH FULL OF SOIL. SECURE

WITH ROW OF STAPLES, 12" SPACING,

C. OVERLAP— BURY UPPER END OF LOWER STRIP AS IN "A" & "B". OVERLAP END

D. CHECK SLOT- FOLD OF NETTING BURIED

IN SLIT TRENCH AND TAMPED; DOUBLE ROW OF STAPLES AT 12" SPACING.


JSE CHECK SLOTS AT 15" SPACING

UPLIFT OF MAT END BY WATER FLOW. IF INSTALLING IN THE DIRECTION OF A CONCENTRATED

- BURY TRANSVERSE TERMINAL ENDS OF MAT TO SECURE AND PREVENT EROSIVE FLOW UNDERNEATH.

BACKFILL AND COMPACT TRENCHES AND CHECK SLOTS AFTER STAKING THE MAT IN BOTTOM OF TRENCH.

- IN ALL TRANSVERSE TERMINAL TRENCHES AND CHECK SLOTS, STAKE EACH MAT AT ITS CENTER AND



1 1/2"

1 1/2"

TYPICAL STAPLES

NO. 11 GAUGE WIRE

WOODEN


STAPLES

(ALTERNATE)


ANCHORAGE


(PREFERRED)

STAKE



MUST BE TOED INTO GROUND





MAY BE USED IN LIEU OF SILT FENCE EROSION CONTROL MIX DETAIL SILTATION FENCE INSTALLATION


BY AN INTERCEPTION DITCH.

- 1. EXCAVATE A 6"x6" TRENCH ALONG THE LINE OF PLACEMENT FOR THE FILTER BARRIER.
- 2. UNROLL A SECTION AT A TIME AND POSITION THE POSTS AGAINST THE BACK (DOWNSTREAM) WALL OF THE TRENCH. 3. DRIVE POSTS INTO THE GROUND UNTIL APPROXIMATELY 2" OF FABRIC IS LYING ON THE TRENCH BOTTOM. JOIN SECTION
- AS SHOWN ABOVE. 4. LAY THE TOE-IN FLAP OF FABRIC ONTO THE UNDISTURBED BOTTOM OF THE TRENCH, BACKFILL THE TRENCH AND TAMP THE SOIL. TOE-IN CAN ALSO BE ACCOMPLISHED BY LAYING THE FABRIC FLAP ON UNDISTURBED GROUND AND PILING AND TAMPING FILL AT THE BASE, BUT MUST BE ACCOMPLISHED
- 5. BARRIER SHALL BE MIRAFI SILT FENCE OR APPROVED EQUAL.



ANDERSON LANDSCAPING 352 MEMORIAL HIGHWAY NORTH YARMOUTH, ME 04097

PRELIMINARY NOT FOR CONSTRUCTION



SHEET TITLE:

EROSION CONTROL **DETAILS**

DESIGNED: DRAWN: 04-21-22 PROJECT NUMBER: 22-103